

Edisto IRM Beef Production Systems - Corral

Amount	Item	Unit Cost	Total Cost
71	Used guard rail - 26 ft. sections - \$1.00 per ft.	\$ 26.00	\$ 1,846.00
54	5-6 in. Pressure Treated Posts - 8 ft. long	\$ 9.28	\$ 501.12
8	5-6 in. Pressure Treated Posts - 14 ft. long	\$ 26.30	\$ 210.40
26	5/8 in. Threaded rod - 3 ft. long	\$ 4.97	\$ 129.22
25	5/8 in. Nuts - lbs.	\$ 2.86	\$ 71.50
23	5/8 in. Washers - lbs.	\$ 0.85	\$ 19.55
15	Concrete mix - 80 lb. bags	\$ 4.19	\$ 62.85
1	Geo-Tec fabric - roll [8 ft. wide x 300 ft. long]	\$ 300.00	\$ 300.00
30	Crush & Run - tons	\$ 18.00	\$ 540.00
11	ROHN galvanized gates - 12 ft. long - 2 in. round tubing	\$ 150.00	\$ 1,650.00
2	ROHN galvanized gates - 8 ft. long - 2 in. round tubing	\$ 114.00	\$ 228.00
3	ROHN galvanized gates - 4 ft. long - 2 in. round tubing	\$ 80.00	\$ 240.00
13	Gate latches	\$ 3.95	\$ 51.35
4	RIVERODE panels - 10 ft. long - 8 rails - 72 in. tall - 1-1/2 in. square tubing	\$ 165.00	\$ 660.00
2	RIVERODE panels - 8 ft. long - 8 rails - 72 in. tall - 1-1/2 in. square tubing	\$ 150.00	\$ 300.00
2	RIVERODE covered slide gates - for 30 in. alley - 1-1/2 in. square tubing	\$ 250.00	\$ 500.00
2	RIVERODE slide gates - for 30 in. alley - 1-1/2 in. square tubing	\$ 225.00	\$ 450.00
1	PEARSON squeeze chute	\$ 2,520.00	\$ 2,520.00
1	PEARSON palpation cage	\$ 475.00	\$ 475.00
1	TRU-TEST Ez-Weigh 1 indicator	\$ 567.00	\$ 567.00
1	TRU-TEST MP800 load bars - 32 in.	\$ 1,150.00	\$ 1,150.00
1	Steel for scale floor	\$ 150.00	\$ 150.00
1	Plywood - 1/2 in. - smooth both sides - 4 ft. x 8 ft. sheet - for hip height chart	\$ 25.00	\$ 25.00
16	Ready-mix concrete w/ fiberglass - yards	\$ 71.02	\$ 1,136.32
1	Roof - 20 ft. trusses, lumber, tin, screws, nails, etc.	\$ 1,382.35	\$ 1,382.35
1	Water and electricity - PVC, wiring, switches, breakers, etc.	\$ 619.25	\$ 619.25
5	Lights	\$ 11.00	\$ 55.00
1	Water hydrant - no freeze - 6 ft.	\$ 60.00	\$ 60.00
Total Cost			\$ 15,899.91