



CONTRACT DOCUMENTS
AND
TECHNICAL SPECIFICATIONS
MASS GRADING
IMPROVEMENTS
FOR
CUICAR TECHNOLOGY
NEIGHBORHOOD 3

PREPARED FOR:

LICAR, LLC

JUNE 16, 2020

J-28283.0000

TABLE OF CONTENTS

PAGE NUMBERS

CONTRACT DOCUMENTS

00021	Invitation to Bid	00021-1	-	00021-1
00110	Instructions to Bidders	00110-1	-	00110-8
00313	Bid Form	00313-1	-	00313-5
00411	Bid Bond	00411-1	-	00411-2
00506	Standard Form of Agreement Between Owner and Contractor	00506-1	-	00506-7
00611	Performance Bond	00611-1	-	00611-6
00621	Payment Bond	00621-1	-	00621-6
00631	Notice of Award	00631-1	-	00631-3
00641	Notice to Proceed	00641-1	-	00641-2
00700	General Conditions	00700-1	-	00700-42
00710	Special Conditions	00710-1	-	00710-6
00815	Supplementary Conditions	00815-1	-	00815-5
01011	Summary of Work	01011-1	-	01011-2
01012	Soil Investigation Data for Bidders	01012-1	-	01012-1
01135	Bidder's Qualifications	01135-1	-	01135-8
01300	Submittals	01300-1	-	01300-7
01400	Quality Control	01400-1	-	01400-3
01410	Testing Services	01410-1	-	01410-4
01702	Contract Closeout	01702-1	-	01702-2

TECHNICAL PROVISIONS

02070	Selective Demolition	02070-1	-	02070-3
02110	Site Clearing	02110-1	-	02110-3
02204	Earthwork	02204-1	-	02204-7
02210	Soil Erosion Control	02210-1	-	02210-7
02275	Rip-Rap	02275-1	-	02275-3
02720	Storm Drainage	02720-1	-	02720-15
02902	Grassing	02902-1	-	02902-6

DOCUMENT 00021**INVITATION TO BID****Legal Notice**

1. Sealed bids for the Mass Grading Improvements for CUICAR Technology Neighborhood 3 owned by LICAR, LLC will be received by the owner at TD Gallery at 5 Research Drive, Greenville, SC 29607 until 3:00 PM on July 14, 2020 at which time they will be publicly opened.
2. The project consists of the following generally described work: Mass Grading Improvements for 23 acres within the CUICAR Technology Neighborhood 3. The Mass Grading Improvements will include clearing, grading, installation of storm drainage and erosion control improvements.
3. Plans and Specifications are open to inspection at Thomas & Hutton or may be obtained from Thomas & Hutton, 501 River Street, Suite 200 Greenville, SC 29601 upon payment of \$100.00 (plus shipping charges as applicable). The payment is non-refundable. Plans and specifications can also be obtained online at the following link: www.clemson.edu/giving/cufoundations/structure/culsf/culsf-flex-lab-building-project/ If the Contractor is downloading plans and specifications electronically, it is the contractor's responsibility to check the website for issuance of Addenda.
4. Questions and interpretations must be submitted in writing to the engineer, Thomas & Hutton, Ryan Page at page.r@tandh.com. The deadline for questions is close of business on July 7, 2020.
5. Bids shall be accompanied by a bid bond or certified cashier's check in an amount not less than 5% of the base bid. All bonds shall be by a surety company licensed in **South Carolina** with an "A" minimum rating of performance and a financial strength of at least five times the contract price as listed in the most current publication of "Best's Key Rating Guide Property Liability." Performance and Payment Bonds, each in an amount equal to 100% of the contract price shall be required of the successful bidder if contract is awarded. Each Bond shall be accompanied by a "Power of Attorney" authorizing the attorney-in-fact to bind the surety and certified to include the date of the bond.
6. Owner reserves the right to reject any or all Bids, including without limitation, the rights to reject any or all nonconforming, nonresponsive, unbalanced or conditional Bids and to reject the Bid of any Bidder if Owner believes it would not be in the best interest of the Project to make an award to Bidder, whether because the Bid is not responsive or the Bidder is unqualified or of doubtful financial ability or fails to meet any other pertinent standard or criteria established by the Owner.
7. A non-mandatory Pre-Bid Conference will be held onsite at the curb cut into Technology Neighborhood 3 on Innovation Drive on June 30, 2020, at 9:00 AM. All prospective bidders are encouraged to attend. A map showing the Pre-Bid Conference location is posted on the Owner's website referenced above in section 3.

LICAR, LLC
END OF INVITATION TO BID

DOCUMENT 00110**INSTRUCTIONS TO BIDDERS**

INTENTION: It is intended the Instructions to Bidders, General Conditions, Supplementary Conditions, Technical Specifications and Construction Drawings shall cover the complete work to which they relate.

ARTICLE 1 **DEFINED TERMS:** In addition to the terms defined in the General Conditions, (EJCDC C-700)(2007), additional terms used in these Instructions to Bidders have the meanings indicated below which are applicable to both the singular and plural thereof.

- 1.1. **Bidder** - One who submits a Bid directly to Owner as distinct from a sub-bidder, who submits a bid to a Bidder.
- 1.2. **Successful Bidder** - The lowest, responsible, and responsive Bidder to whom Owner (based on Owner's evaluation as hereinafter provided) makes an award.
- 1.3. **Bid** - A complete and properly signed offer to execute work for the prices stipulated in Bid Form and submitted in accordance with the Bidding Documents.
- 1.4. **Addenda** - Graphic or written documents issued by Engineer prior to the opening of Bids issued to clarify, revise, add to, or delete information in the original bidding documents or in previous addenda.

ARTICLE 2 **BID FORM:** All Bids must be made upon the Bid Forms hereto annexed, and shall state the amount bid for each item shown, and all bids must be for materials and work called for in the specifications. **Deposits for plans and specifications are not refundable.**

- 2.1 The Bid Form is included with the Bidding Documents; additional copies may be obtained from Engineer.
- 2.2 All blanks on the Bid Form must be completed by printing in black ink or by typewriter.
- 2.3 Bids by corporations must be executed in the corporate name by the president or a vice-president (or other corporate officer accompanied by evidence of authority to sign) and the corporate seal must be affixed and attested by the secretary or an assistant secretary. The corporate address and state of incorporation must be shown below the signature.
- 2.4 All names must be typed or printed in black ink below the signature.
- 2.5 The Bid shall contain an acknowledgment of receipt of all Addenda (the numbers of which must be filled in on the Bid Form.)

- 2.6 The address and telephone number for communications regarding the Bid must be shown.

ARTICLE 3 QUALIFICATIONS OF BIDDERS:

- 3.1 To demonstrate qualifications to perform the Work, each Bidder must be prepared to submit within five days after Bid opening upon Owner's request detailed written evidence such as financial data, previous experience, present commitments, and other such data as may be necessary to assist Owner in determining Contractor's qualifications.
- 3.2 Each Bid must contain evidence of Contractor's authority to conduct business in the state where the Work is to be performed. State Contractor license number, if applicable, must also be shown on the Bid Form.

ARTICLE 4 COPIES OF BIDDING DOCUMENTS:

- 4.1 Complete sets of Bidding Documents must be used in preparing Bids; neither Owner nor Engineer assumes any responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bidding Documents.
- 4.2 Owner and Engineer in making copies of Bidding Documents available for a non-refundable deposit do so only for the purpose of obtaining Bids for the Work and do not confer a license or grant for any other use.

ARTICLE 5 EXAMINATION OF BIDDING DOCUMENTS, OTHER DATA, AND SITE:

- 5.1 It is the responsibility of each Bidder before submitting a bid:
- 5.1.1 To examine and study thoroughly the Bidding Documents and other related data identified in the Bidding Documents;
- 5.1.2 To visit the work site to ascertain by inspection pertinent local conditions such as location, character and accessibility of the site including existing surface and subsurface conditions in the work area; availability of facilities, location and character of existing work within or adjacent thereto, labor conditions, etc.
- 5.1.3 To become familiar with and satisfy Bidder as to all federal, state, and local Laws and Regulations that may affect cost, progress, or performance of the Work;
- 5.1.4 To obtain and carefully study (or assume responsibility for doing so) all addition or supplementary examination investigations, explorations, tests, studies, and data concerning conditions (surface, subsurface, and Underground Facilities) at or contiguous to the Site which may affect cost, progress, or performance or the Work or which relate any aspect of the means, methods, techniques, sequences, and procedures of construction to be employed by Bidder, including any specific means, methods, techniques, sequences, and procedures of construction expressly

- required of the bidding documents, and safety precautions and programs incident thereto;
- 5.1.5 To study and carefully correlate Bidder's knowledge and observations with the Bidding Documents and such other related data; and
 - 5.1.6 To promptly notify Engineer of all conflicts, errors, ambiguities or discrepancies which Bidder has discovered in or between the Bidding Documents and such other related documents;
 - 5.1.7 to agree at the time of submitting its Bid that no further examinations, investigations, explorations, tests, studies or data are necessary for the determination of its Bid for performance of the Work at the price bid and within the times and in accordance with the other terms and conditions of the Bidding Documents;
 - 5.1.8 To become aware of the general nature of the work to be performed by OWNER and others at the Site that relates to the Work as indicated in the Bidding Documents;
 - 5.1.9 To determine that the Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for the performance of the Work.
- 5.2 The Owner shall make available to all prospective bidders, previous to receipt of bids, information that it may have as to sub-soil conditions and surface topography at the work site. Such information shall be given as the best factual information available without being considered as a representation of the Owner.
- 5.3 The submission of a Bid will constitute an incontrovertible representation by Bidder that Bidder has complied with every requirement of this Article 5, that without exception, the Bid is premised upon performing and furnishing the Work required by the Bidding Documents and applying any specific means, methods, techniques, sequences, and procedures of construction that may be shown or indicated or expressly required by the Bidding Documents, that Bidder has given ENGINEER written notice of all conflicts, errors, ambiguities, and discrepancies that Bidder has discovered in the Bidding Documents and the written resolutions thereof by ENGINEER are acceptable to Bidder, and that the Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performing and furnishing the Work.

ARTICLE 6

PRE-BID CONFERENCE: A non-mandatory pre-Bid conference will be held onsite at 9:00 AM on June 30, 2020 at the curb cut into CU-ICAR Technology Neighborhood 3 from Innovation Drive. Representatives of OWNER and ENGINEER will be present to discuss the Project. Bidders are encouraged to attend and participate in the conference. ENGINEER will transmit to all prospective Bidders of record such Addenda as ENGINEER considers necessary in response to questions arising at the conference. It is the contractor's responsibility to be added to the

plan holders list if plans and specifications are downloaded online. Oral statements may not be relied upon and will not be binding or legally effective.

ARTICLE 7 INTERPRETATIONS AND ADDENDA:

- 7.1 All questions about the meaning or intent of the Bidding Documents are to be directed to Engineer. The person submitting the request shall do so in writing and be responsible for its prompt delivery. Interpretations or clarifications considered necessary by Engineer in response to such questions will be issued by Addenda mailed or delivered to all parties recorded by Engineer as having received the Bidding Documents. Questions received less than ten days prior to the date for opening of Bids may not be answered. Only questions answered by formal written Addenda will be binding. Oral and other interpretations or clarifications will be without legal effect.
- 7.2 Addenda may also be issued to modify the Bidding Documents as deemed advisable by Owner or Engineer.

ARTICLE 8 BID SECURITY:

- 8.1 Each Bid must be accompanied by Bid security made payable to Owner in an amount of five (5) percent of Bidder's maximum Bid price and in the form of a certified or bank check or a Bid Bond (on form attached, if a form is prescribed) issued by a surety company licensed in **South Carolina** with an "A" minimum rating of performance and a financial strength of at least five times the contract price as listed in the most current publication of "Best's Key Rating Guide Property Liability."
- 8.2 The Bid security of Successful Bidder will be retained until such Bidder has executed the Agreement, furnished the required contract security and met the other conditions of the Notice of Award, whereupon the Bid security will be returned. If the Successful Bidder fails to execute and deliver the Agreement and furnish the required contract security within fifteen days after the Notice of Award, Owner may annul the Notice of Award and the Bid security of that Bidder will be forfeited. The Bid security of other Bidders whom Owner believes to have a reasonable chance of receiving the award may be retained by Owner until the earlier of the seventh day after the Effective Date of the Agreement or the sixty-first day after the Bid opening, whereupon Bid security furnished by such bidders will be returned. Bid security with Bids that are not competitive will be returned within seven days after the Bid opening.

ARTICLE 9 CONTRACT COMPLETION TIME: The Work will be substantially completed within **92 days** after the date when the Contract Times commence to run as provided in paragraph 2.03 of the General Conditions, and completed and ready for final payment in accordance with paragraph 14.07 of the General Conditions within **122 days** after the date when the Contract Times commence to run. Included in the contract times are days for rain delay. Time delays due to rain in excess of the above days shall be reported by the Contractor to the Engineer in writing, within 30 days of each event. Liquidated Damages for the project will be \$200 for each day expiring after the time specified in paragraph 3.1 of the Agreement.

ARTICLE 10 SUBSTITUTE AND “OR-EQUAL” ITEMS:

- 10.1 The Contract, if awarded, will be on the basis of materials and equipment specified or described in the Bidding Documents without consideration of possible substitute or “or-equal” items. Whenever it is specified or described in the Bidding Documents that a substitute or “or-equal” item of material or equipment may be furnished or used by CONTRACTOR if acceptable to ENGINEER, application for such acceptance will not be considered by ENGINEER until after the Effective Date of the Agreement. The procedure for submission of any such application by CONTRACTOR and consideration by ENGINEER is set forth in the General Conditions and may be supplemented in the General Requirements.

ARTICLE 11 SUBCONTRACTORS, SUPPLIERS, AND OTHERS:

- 11.1 Each bid must be accompanied by a list of Subcontractors, Suppliers, individuals, or entities proposed for those portions of the Work for which such identification is required. Such list shall be accompanied by an experience statement with pertinent information regarding similar projects and other evidence of qualification for each such Subcontractor, Supplier, individual, or entity. If OWNER or ENGINEER, after due investigation, has reasonable objection to any proposed Subcontractor, Supplier, individual, or entity, OWNER or ENGINEER may, before the Notice of Award is given, request apparent Successful Bidder to submit a substitute, without an increase in the Bid.
- 11.2 If apparent Successful Bidder declines to make any such substitution, OWNER may award the Contract to the next lowest Bidder proposing to use acceptable Subcontractors, Suppliers, individuals, or entities. Declining to make requested substitutions will not constitute grounds for forfeiture of the Bid security of any Bidder. Any Subcontractor, Supplier, individual, or entity so listed and against which OWNER or ENGINEER makes no written objection prior to the giving of the Notice of Award will be deemed acceptable to OWNER and ENGINEER subject to revocation of such acceptance after the Effective Date of the Agreement as provided in paragraph 6.06 of the General Conditions.
- 11.3 CONTRACTOR shall not be required to employ any Subcontractor, Supplier, individual, or entity against whom CONTRACTOR has reasonable objection.

- ARTICLE 12 SUBMITTAL OF BIDS:** Bids shall be submitted at the time and place indicated in the Invitation to Bid and shall be enclosed in a sealed opaque envelope, marked with the project title, and name and address of Bidder, and accompanied by the Bid security and other required documents. If the Bid is sent through the mail or other delivery system, the sealed envelope shall be enclosed in a separate envelope with the notation “BID ENCLOSED” on the face of it. Contractor license number(s) shall be written on the face of the bid envelope.

Each Bidder is responsible for seeing their Bid is received by the Owner not later than the advertised time set for the opening of Bids.

ARTICLE 13 MODIFICATION AND WITHDRAWAL OF BIDS:

- 13.1 Bids may be modified or withdrawn by an appropriate document duly executed (in the manner a Bid must be executed) and delivered to the place where Bids are to be submitted at any time prior to the opening of bids.
- 13.2 If, within twenty-four hours after Bids are opened, any Bidder files a duly signed, written notice with Owner and promptly thereafter demonstrates to the reasonable satisfaction of Owner there was a material and substantial mistake in the preparation of its Bid, Bidder may withdraw its Bid and the Bid security will be returned. Thereafter, Bidder will be disqualified from further bidding on the Work to be provided.

ARTICLE 14 OPENING OF BIDS: Bids will be opened and (unless obviously non-responsive) read aloud publicly at the place where Bids are to be submitted. An abstract of the amount of the base Bids and major alternates (if any) will be made available to Bidders after the opening of Bids.

ARTICLE 15 ACCEPTANCE OF BIDS: Bids may not be withdrawn (except as noted in Paragraph 13) after the time set for the opening of Bids. Bids will remain subject to acceptance for 60 days after the day of the Bid opening, but the Owner may, in its sole discretion, release any Bid and return the Bid security prior to expiration of the acceptance period.

ARTICLE 16 AWARD OF CONTRACT:

- 16.1 Owner reserves the right to reject any or all Bids, including without limitation, the rights to reject any or all nonconforming, nonresponsive, unbalanced or conditional Bids and to reject the Bid of any Bidder if Owner believes it would not be in the best interest of the Project to make an award to a Bidder, whether because the Bid is not responsive, or the Bidder is unqualified or of doubtful financial ability or fails to meet any other pertinent standard or criteria established by the Owner.
- 16.2 Owner also reserves the right to waive all informalities not involving price, time, or changes in the Work and to negotiate contract terms with the Successful Bidder. Discrepancies between the multiplication of units of Work and unit prices will be resolved in favor of the unit prices. Discrepancies between the indicated sum of any column of figures and the correct sum thereof will be resolved in favor of the correct sum. Discrepancies between words and figures will be resolved in favor of the words.
- 16.3 In evaluating Bids, Owner will consider the qualification of Bidders, whether or not the Bids comply with the prescribed requirements, and such alternates, unit prices and other data, as may be requested in the Bid Form or prior to the Notice of Award.

The Owner will also consider whether the Bidder involved:

- a) Maintains a permanent place of business;
- b) Has adequate plant and equipment to do the work properly and expeditiously;
- c) Has suitable financial status to meet obligations incidental to the work;
- d) Has appropriate technical experience.

- 16.4. Owner may consider the qualifications and experience of Subcontractors, Suppliers, and other persons and organizations proposed for those portions of the Work as to which the identity of Subcontractors, Suppliers, and other persons and organizations must be submitted as provided in the Supplementary Conditions. Owner also may consider the operating costs, maintenance requirements, performance data and guarantees of major items of materials and equipment proposed for incorporation in the Work when such data is required to be submitted prior to the Notice of Award.
- 16.5. Owner may conduct such investigations as Owner deems necessary to assist in the evaluation of any bid and to establish the responsibility, qualifications and financial ability of Bidders, proposed Subcontractors, Suppliers and other persons and organizations to perform and furnish the Work in accordance with the Contract Documents to Owner's satisfaction within the prescribed time.
- 16.6. If the contract is to be awarded, it will be awarded to the Bidder whose evaluation by Owner indicates the award will be in the best interest of the Project.
- 16.7. If the contract is to be awarded, Owner will give Successful Bidder a Notice of Award within 60 days after the day of the Bid opening.

ARTICLE 17 MODIFICATIONS OF QUANTITIES: If the lowest bona fide Bid exceeds the money available for the Work, the Owner reserves the right to delete enough of the Work to bring the cost within the available funds. The Owner also reserves the right to delete whichever items or portions of items considered to be in the best interest of the Owner.

ARTICLE 18 CONTRACT SECURITY: The General Conditions and Supplementary Conditions set forth Owner's requirements as to performance and payment bonds. When the Successful Bidder delivers the executed Agreement to the Owner, it must be accompanied by the required performance and payment bonds.

ARTICLE 19 SIGNING THE AGREEMENT: When the Owner gives a Notice of Award to the Successful Bidder, it will be accompanied by the required number of unsigned counterparts of the Agreement with all other written Contract Documents attached. Within 15 days thereafter, Contractor shall sign and deliver the required counterparts of the Agreement and attached documents to Owner with the required Bonds. Within 10 days thereafter, Owner shall deliver one fully signed counterpart to Contractor.

ARTICLE 20 LAWS AND REGULATIONS: The Contractor shall comply with local, District, County, State, and Federal laws applicable to the work.

The Contractor shall comply with the Department of Labor Safety and Health Regulations for Construction promulgated under the Occupational Safety and Health Act of 1970 as amended through January 1, 2004 (PL 91-596) and under Section 107 of the Contract Work and Safety Standards Act (PL) 91-54). The regulations are administered by the Department of Labor and the Contractor shall allow access to the project to personnel from this Department.

ARTICLE 21 CONTRACTOR'S AND SUBCONTRACTOR'S INSURANCE: Contractor shall not commence work under this contract until obtaining all the insurance required by the Supplementary Conditions.

ARTICLE 22 TERMINATION OF CONTRACT: If the Owner is made to stop construction of the work because of an order from a Court or State Department, the contract shall be terminated. Payment will be made for work completed and a proration of the work underway, materials stored, and for the overhead and profit of the completed work and work underway. Payment will not be made for anticipated profit and overhead on work not completed or underway.

DOCUMENT 00313**BID FORM**

**PROJECT IDENTIFICATION: Mass Grading Improvements for
CUICAR Technology Neighborhood 3**

T&H Project No.: 28283.0000

THIS BID IS SUBMITTED TO: LICAR, LLC

1. The undersigned BIDDER proposes and agrees, if this Bid is accepted, to enter into an agreement with OWNER in the form included in the Contract Documents to perform and furnish all Work as specified or indicated in the Contract Documents for the Bid Price and within the Bid Times indicated in this Bid and in accordance with the other terms and conditions of the Contract Documents.
2. BIDDER accepts all of the terms and conditions of the Advertisement or Invitation to Bid and Instructions to Bidders, including without limitation those dealing with the disposition of Bid security. This Bid will remain subject to acceptance for 60 days after the day of Bid opening, or for such longer period of time BIDDER may agree to in writing upon request of OWNER.
3. In submitting this Bid, BIDDER represents, as more fully set forth in the Agreement, that:
 - a. BIDDER has examined and carefully studied the Plans and Specifications for the work and contractual documents relative thereto, and has read all Technical Provisions, Supplementary Conditions, and General Conditions, furnished prior to the opening of Bids and can fulfill the requirements of the work to be performed.
 - b. BIDDER further acknowledges hereby receipt of the following Addenda:

ADDENDUM NO.	DATE

- c. BIDDER has visited the site and become familiar with and is satisfied as to the general, local and site conditions possibly affecting cost, progress, performance and furnishing of the Work.
- d. BIDDER is familiar with and is satisfied as to all federal, state, and local Laws and Regulations possibly affecting cost, progress, performance and furnishing of the Work.

- e. BIDDER has carefully studied all reports of explorations and tests of subsurface conditions at or contiguous to the site and all drawings of physical conditions in or relating to existing surface or subsurface structure at or contiguous to the site (except underground Facilities) have been identified in the Supplementary Conditions. BIDDER acknowledges such reports and drawings are not Contract Documents and may not be complete for BIDDER's purposes. BIDDER acknowledges OWNER and Engineer do not assume responsibility for the accuracy or completeness of information and data shown or indicated in the Bidding Documents with respect to Underground Facilities at or contiguous to the site. BIDDER has obtained and carefully studied (or assumes responsibility for having done so) all such additional or supplementary examinations, investigations, explorations, tests, studies and data concerning conditions (surface, subsurface and Underground Facilities) at or contiguous to the site or otherwise which may affect cost progress, performance or furnishing of the work or which relate to any aspect of the means, methods, techniques, sequences and procedures of construction to be employed by BIDDER and safety precautions and programs incident thereto. BIDDER does not consider any additional examinations, investigations, explorations, tests, studies, or data are necessary for the determination of this Bid for performance and furnishing of the Work in accordance with the times, price and other terms and conditions of the Bidding Documents.
 - f. BIDDER is aware of the general nature of Work to be performed by Owner and others at the site relating to Work for which this Bid is submitted as indicated in the Bidding Documents.
 - g. BIDDER has correlated the information known to BIDDER, information and observations obtained from visits to the site, reports and drawings identified in the Bidding Documents and all additional examinations, investigations, explorations, tests, studies, and data with the Bidding Documents.
 - h. BIDDER has given ENGINEER written notice of all conflicts, errors, ambiguities, or discrepancies BIDDER has discovered in the Bidding Documents and the written resolution thereof by ENGINEER is acceptable to BIDDER. The Bidding Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performing and furnishing the Work for which this Bid is submitted.
 - i. This bid is genuine and not made in the interest of or on behalf of any undisclosed person, firm or corporation and is not submitted in conformity with any agreement or rules of any group, association, organization or corporation; BIDDER has not directly or indirectly induced or solicited any other Bidder to submit a false or sham Bid; BIDDER has not solicited or induced any person, firm or corporation to refrain from bidding; and BIDDER has not sought by collusion to obtain for itself any advantage over any other Bidder or over OWNER.
4. BIDDER will complete the Work in accordance with the Contract Documents for the following price(s):

BASE BID PROPOSAL

Item	Description	Quantity	Units	Unit Price	Total
1	Clearing & Grubbing	23	AC		
2	Demolition of Existing Sanitary Sewer	1	LS		
3	Earthwork	1	LS		
4	36" RCP	367	LF		
5	30" RCP	169	LF		
6	24" RCP	110	LF		
7	24" CMP	73	LF		
8	18" RCP	410	LF		
9	36" Flared End Section	2	EA		
10	24" Flared End Section	3	EA		
11	Temporary CMP Outlet Structure with Filter Berm and Forebay	1	EA		
12	Junction Box	2	EA		
13	Roof Inlet	6	EA		
14	Emergency Spillway for Pond 1	1	EA		
15	12" Temporary Slope Drains	70	LF		
16	Sediment Marker	1	EA		
17	Temporary Skimmer (complete configuration)	1	EA		
18	Porous Baffles	167	LF		
19	Rip Rap with Filter Fabric	106	SY		
21	Silt Fence	4,000	LF		
22	Construction Entrance	1	EA		
23	Concrete Washout	1	EA		
24	Stone Check Dam	17	EA		
25	Rock Sediment Dike	1	EA		
26	Erosion Control Matting Blanket	13,000	SY		
27	Type "C" Inlet Protection	5	EA		
28	Type "F" Inlet Protection	4	EA		
29	Grassing	23	AC		
TOTAL PROJECT:					

LUMP SUM BID

LUMP SUM BID PRICE: _____

(Use words)

(\$ _____)
(Figures)

In addition to the Lump Sum Base Bid Line Items, the following will be used for establishing a unit price for listed items if encountered during construction.

Item	Description	Units	Unit Price
1	Mass Rock Excavation	CY	
2	Trench Rock Excavation	CY	
3	Unsuitable Material	CY	

5. BIDDER agrees the Work will be substantially complete within 92 calendar days after the date when the Contract Times commence to run as provided in paragraph 2.03 of the General Conditions, and completed and ready for final payment in accordance with paragraph 14.07 of the General Conditions within 122 calendar days after the date when the Contract Times commence to run.
6. BIDDER accepts provisions of the Agreement as to liquidated damages in the event of failure to complete the Work within times specified in the Agreement. Liquidated Damages for the project are \$200 for each day expiring after the time specified in paragraph 3.1 of the Agreement.
7. The following documents are attached to and made a condition of this Bid:
 - a. Required Bid Security in the form of 5 percent of the Bid Total Price.
 - b. A tabulation of Subcontractors, Suppliers and other persons and organizations required to be identified in this Bid.
 - c. Required BIDDER's Qualification Statement with supporting data.
8. The undersigned further agrees in case of failure on his/her part to execute the said contract and the Bond within 15 consecutive calendar days after written notice being given of the award of the contract, the check or bid bond accompanying this bid, and the monies payable thereon shall be paid into the funds of the Owner as liquidated damages for such failure, otherwise, the check or bid bond accompanying this proposal shall be returned to the undersigned.
9. Communications concerning this Bid shall be addressed to:

Thomas & Hutton
501 River Street, Suite 200
Greenville, SC 29601

Attn: Ryan Page
page.r@tandh.com
864-412-2217

- 10. Terms used in this Bid which are defined in the General Conditions or Instructions will have the meanings indicated in the General Conditions of Instructions.

SUBMITTED on _____, 2020.

CONTRACTOR'S NAME

ADDRESS:

BY: _____

State Utility Contractor License No. _____ SC

DOCUMENT 00411

BID BOND

BIDDER (Name and Address):

SURETY (Name and Address of Principal Place of Business):

OWNER (Name and Address):

BID

BID DUE DATE: _____

PROJECT (Brief Description Including Location):

BOND

BOND NUMBER: _____ DATE: _____

(Not later than Bid Due Date)

PENAL SUM: _____

(5% of Bid Sum)

IN WITNESS WHEREOF, Surety and Bidder, intending to be legally bound hereby, subject to the terms printed on the reverse side hereof, do each cause this Bid Bond to be duly executed on its behalf by its authorized officer, agent, or representative.

BIDDER

SURETY

(Seal)
Bidder's Name and Corporate Seal

(Seal)
Surety's Name and Corporate Seal

By: _____
Signature and Title

By: _____
Signature and Title
(Attach Power of Attorney)

Attest: _____
Signature and Title

Attest: _____
Signature and Title

- Note:
- (1) Above addresses are to be used for giving required notice.
 - (2) Any singular reference to Bidder, Surety, Owner, or other party shall be considered plural where applicable.

PENAL SUM FORM

1. Bidder and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to pay to Owner upon default of Bidder the penal sum set forth on the face of this Bond.
2. Default of Bidder shall occur upon the failure of Bidder to deliver within the time required by the Bidding Documents the executed Agreement required by the Bidding Documents and any performance and payment bonds required by the Bidding Documents and Contract Documents.
3. This obligation shall be null and void if:
 - 3.1 Owner accepts Bidder's bid and Bidder delivers within the time required by the Bidding Documents (or any extension thereof agreed to in writing by Owner) the executed Agreement required by the Bidding Documents and any performance and payment bonds required by the Bidding Documents and Contract Document, or
 - 3.2 All bids are rejected by Owner, or
 - 3.3 Owner fails to issue a notice of award to Bidder within the time specified in the Bidding Documents (or any extension thereof agreed to in writing by bidder and, if applicable, consented to by Surety when required by paragraph 5 hereof.)
4. Payment under this Bond will be due and payable upon default of Bidder and within 30 calendar days after receipt by Bidder and Surety of written notice of default from Owner, which notice will be given with reasonable promptness, identifying this Bond and the Project and including a statement of the amount due.
5. Surety waives notice of and any and all defenses based on arising out of any time extension to issue notice of award agreed to in writing by Owner and Bidder, provided that the time for issuing notice of award including extensions shall not in the aggregate exceed 120 days from Bid Due Date without Surety's written consent.
6. No suit or action shall be commenced under this Bond prior to 30 calendar days after the notice of default required in paragraph 4 above is received by Bidder and Surety, and in no case later than one year after Bid Due Date.
7. Any suit or action under this Bond shall be commenced only in a court of competent jurisdiction located in the state in which the Project is located.
8. Notice required hereunder shall be in writing and sent to Bidder and Surety at their respective addresses shown on the face of this Bond. Such notices may be sent by personal delivery, commercial courier or by United States Registered or Certified Mail, return receipt requested, postage pre-paid, and shall be deemed to be effective upon receipt by the party concerned.
9. Surety shall cause to be attached to this Bond a current and effective Power of Attorney evidencing the authority of the officer, agent or representative who executed this Bond on behalf of Surety to execute, seal and deliver such Bond and bind the Surety thereby.
10. This Bond is intended to conform to all applicable statutory requirements. Any applicable requirement of any applicable statute that has been omitted from this Bond shall be deemed to be included herein as if set forth at length. If any provision of the Bond conflicts with any applicable provision of any applicable statute, then the provision of said statute shall govern and the remainder of this Bond that is not in conflict therewith shall continue in full force and effect.
11. The term "bid" as used herein includes a bid, offer or proposal as applicable.

DOCUMENT 00506**STANDARD FORM OF AGREEMENT
BETWEEN OWNER AND CONTRACTOR**

THIS AGREEMENT is dated as of the ____ day of _____ in the year 20__ by and between LICAR, LLC hereinafter called OWNER) and _____ (hereinafter called CONTRACTOR).

OWNER and CONTRACTOR, in consideration of the mutual covenants hereinafter set forth, agree as follows:

ARTICLE 1 WORK

CONTRACTOR shall complete all Work as specified or indicated in the Contract Documents. The Work is generally described as follows:

Mass Grading Improvements for CUICAR Technology Neighborhood 3 work includes clearing, earthwork, rough grading, stormwater and erosion control improvements for approximately 23 acres.

ARTICLE 2 ENGINEER

The Project has been designed by Thomas & Hutton Engineering Co. who is hereinafter called ENGINEER and who is to act as OWNER's representative, assume all duties and responsibilities and have the rights and authority assigned to ENGINEER in the Contract Documents in connection with the completion of the Work in accordance with the Contract Documents.

ARTICLE 3 CONTRACT TIMES

All time limits for Substantial Completion and completion and readiness for final payment as stated in the Contract Documents are of essence to the Contract.

- 3.1 The Work will be substantially completed within **92 days** after the date when the Contract Times commence to run as provided in paragraph 2.03 of the General Conditions, and completed and ready for final payment in accordance with paragraph 14.07 of the General Conditions within **122 days** after the date when the Contract Times commence to run. Included in the contract times are 7 days for rain delay. Time delays due to rain in excess of the above days shall be reported by the Contractor to the Engineer in writing, within 30 days of each event.
- 3.2 *Liquidated Damages.* OWNER and CONTRACTOR recognize time is of the essence for this Agreement and OWNER will suffer financial loss if the Work is not completed within the times specified in paragraph 3.1 above, plus any extensions thereof allowed in accordance with Article 12 of the General Conditions. The parties also recognize the delays, expense, and difficulties involved in proving the actual loss suffered by OWNER if the Work is not substantially complete on time. Accordingly, instead of requiring any such proof, OWNER and CONTRACTOR agree to liquidated damages for delay (but not as a penalty) the CONTRACTOR shall pay OWNER two hundred dollars (\$200.00) for each day expiring after the time

specified in paragraph 3.1 for Substantial Completion until the Work is substantially complete. After Substantial completion, if CONTRACTOR shall neglect, refuse or fail to complete the remaining Work within the time specified in paragraph 3.1 for completion and readiness for final payment or any proper extension thereof granted by OWNER, CONTRACTOR, shall pay OWNER two hundred dollars (\$200.00) for each day expiring after the time specified in paragraph 3.1 for completion and readiness for final payment.

ARTICLE 4 CONTRACT PRICE

4.1 LUMP SUM WORK

OWNER shall pay CONTRACTOR for completion of the Work in accordance with the Contract Documents a Lump Sum in the amount of:

\$ _____ (dollars), (\$ _____)
(use words) (figures)

ARTICLE 5 PAYMENT PROCEDURES

CONTRACTOR shall submit Applications for Payment in accordance with Article 14 of the General Conditions. Applications for Payment will be processed by ENGINEER as provided in the General Conditions.

5.1 *Progress Payments; Retainage.* OWNER shall make progress payments on account of the Contract Price on the basis of CONTRACTOR's Applications for Payment as recommended by ENGINEER, on or about the **25th** day of each month during performance of the Work as provided in paragraphs 5.1.1., 5.1.1.2. and 5.2. below. All such payments will be measured by the schedule of values established in paragraph 2.07 of the General Conditions (and in the case of Unit Price Work based on the number of units completed) as provided in the General Requirements.

5.1.1 *For Cost of Work:* Progress payments on account of the Cost of the Work will be made:

5.1.1.1 Prior to Substantial Completion, progress payments will be made in an amount equal to the percentage indicated below, but, in each case, less the aggregate of payments previously made and less such amounts as ENGINEER shall determine, or OWNER may withhold, in accordance with paragraph 14.02 of the General Conditions.

97.5% of the Work completed (with the balance being retainage). If Work has been 50% completed as determined by ENGINEER, and if the character and progress of the Work have been satisfactory to OWNER and ENGINEER, OWNER, on recommendation of ENGINEER, may determine as long as the character and progress of the Work remain satisfactory to them, there will be no additional retainage on account of Work completed, in which case the remaining

progress payments prior to Substantial Completion will be in an amount equal to 100% of the Work completed.

97.5% of Cost of the Work (with the balance being retainage) applicable to materials and equipment not incorporated in the Work (but delivered, suitably stored and accompanied by documentation satisfactory to OWNER as provided in paragraph 14.02.A.1 of the General Conditions).

5.1.1.2 Omitted.

- 5.2 *Final Payment.* Upon final completion and acceptance of the Work in accordance with paragraph 14.07 of the General Conditions, OWNER shall pay the remainder of the Contract Price as recommended by ENGINEER as provided in said paragraph 14.07.

ARTICLE 6 INTEREST

All moneys not paid within thirty (30) days of the due date as provided in Article 14 of the General Conditions, shall bear interest at the rate of one (1) percent annually or the minimum required by law at the place of the Project, whichever is greater.

ARTICLE 7 CONTRACTOR'S REPRESENTATIONS

In order to induce OWNER to enter into this Agreement CONTRACTOR makes the following representations:

- 7.1 CONTRACTOR has examined and carefully studied the Contract Documents (including the Addenda indicated in Article 8 hereinafter) and the other related data identified in the Bidding Documents.
- 7.2 CONTRACTOR has visited the site and become familiar with and is satisfied as to the general, local and site conditions possibly affecting cost, progress, performance or furnishing of the Work.
- 7.3 CONTRACTOR is familiar with and is satisfied as to all federal, state, and local Laws and Regulations possibly affecting cost, progress, performance and furnishing of the Work.
- 7.4 CONTRACTOR has carefully studied all reports of explorations and tests of subsurface conditions at or contiguous to the Site and all drawings of physical conditions in or relating to existing surface or subsurface structures at or contiguous to the Site (except Underground Facilities) which have been identified in the Supplementary Conditions as provided in the General Conditions. CONTRACTOR acknowledges such reports and drawings are not Contract Documents and may not be complete for CONTRACTOR's purposes. CONTRACTOR acknowledges OWNER and ENGINEER do not assume responsibility for the accuracy or completeness of information and data shown or indicated in the Contract Documents with respect to Underground Facilities at or contiguous to the site. CONTRACTOR has obtained and carefully studied (or assumes responsibility for having done so) all such additional supplementary examinations, investigations, explorations, tests, studies and data concerning conditions (surface, subsurface

and Underground Facilities) at or contiguous to the site or otherwise which may affect cost, progress, performance or furnishing of the construction to be employed by CONTRACTOR and safety precautions and programs incident thereto. CONTRACTOR does not consider any additional examinations, investigations, explorations, tests, studies or data are necessary for the performance and furnishing of the Work at the Contract Price, within the Contract Times and in accordance with the other terms and conditions of the Contract Documents.

- 7.5 CONTRACTOR is aware of the general nature of work to be performed by OWNER and others at the site relating to the Work as indicated in the Contract Documents.
- 7.6 CONTRACTOR has correlated the information known to CONTRACTOR, information and observations obtained from visits to the site, reports and drawings identified in the Contract Documents and all additional examinations, investigations, explorations, tests, studies and data with the Contract Documents.
- 7.7 CONTRACTOR has given ENGINEER written notice of all conflicts, errors, ambiguities or discrepancies CONTRACTOR has discovered in the Contract Documents and the written resolution thereof by ENGINEER is acceptable to CONTRACTOR, and the Contract Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performance and furnishing of the Work.

ARTICLE 8 CONTRACT DOCUMENTS

The Contract Documents which comprise the entire agreement between OWNER and CONTRACTOR concerning the Work consist of the following:

- 8.1 Invitation to Bid
- 8.2 Instructions to Bidders
- 8.3 Bid Form
- 8.4 Bid Bond
- 8.5 Standard Form of Agreement Between Owner and Contractor
- 8.6 Performance Bond
- 8.7 Payment Bond
- 8.8 Notice of Award
- 8.9 Notice to Proceed
- 8.10 General Conditions (pages 1 to 62, inclusive)
- 8.11 Special Conditions

- 8.12 Supplementary Conditions
- 8.13 Summary of Work
- 8.14 Soil Investigation
- 8.15 Submittals
- 8.16 Quality Control
- 8.17 Testing Services
- 8.18 Contract Closeout
- 8.19 Technical Specifications consisting of 7 sections, as listed in the Table of Contents.
- 8.20 Drawings consisting of sheets ____ through ____ with each sheet bearing the following general title:

Sheet	Description	Job No.	P.E. Signature Date
CO	Cover Sheet	28283.0000	04/21/2020
G1.1	General Notes and Legend	28283.0000	04/21/2020
G1.2	Sheet Index	28283.0000	04/21/2020
EX1.1	Existing Conditions	28283.0000	04/21/2020
EX1.2	Existing Conditions	28283.0000	04/21/2020
DM1.1	Demolition Plan	28283.0000	04/21/2020
DM1.2	Demolition Plan	28283.0000	04/21/2020
EC0.1	Erosion Control Notes	28283.0000	04/21/2020
EC0.2	Erosion Control Notes	28283.0000	04/21/2020
EC1.1	Erosion Control Plan-Land Disturbance	28283.0000	04/21/2020
EC1.2	Erosion Control Plan-Land Disturbance	28283.0000	04/21/2020
EC2.1	Erosion Control Plan-Construction	28283.0000	04/21/2020
EC2.2	Erosion Control Plan-Construction	28283.0000	04/21/2020
EC3.1	Erosion Control Plan-Stabilization	28283.0000	04/21/2020
EC3.2	Erosion Control Plan-Stabilization	28283.0000	04/21/2020
EC4.1	Erosion Control Details	28283.0000	04/21/2020
EC4.2	Erosion Control Details	28283.0000	04/21/2020
EC4.3	Erosion Control Details	28283.0000	04/21/2020
C1.1	Grading and Drainage Plan	28283.0000	04/21/2020
C1.2	Grading and Drainage Plan	28283.0000	04/21/2020
C1.3	Drainage Profiles	28283.0000	04/21/2020
C1.4	Grading and Drainage Details	28283.0000	04/21/2020

- 8.21 Addenda numbers ____ to ____, inclusive.

Exhibits to this Agreement:

- a. CONTRACTOR's Bid marked "Exhibit ____."

- b. Documentation submitted by CONTRACTOR prior to Notice of Award.
- c. Any modification, including Change Orders, duly delivered after execution of Agreement.

There are no Contract Documents other than those listed above in this Article 8. The Contract Documents may only be amended, modified or supplemented as provided in paragraph 3.04 of the General Conditions.

ARTICLE 9 MISCELLANEOUS

- 9.1 Terms used in this Agreement which are defined in Article 1 of the General Conditions will have the meanings indicated in the General Conditions.
- 9.2 No assignment by a party hereto of any rights under or interests in the Contract Documents will be binding on another party hereto without the written consent of the party sought to be bound; and, specifically but without limitation, moneys becoming due and moneys due, may not be assigned without such consent (except to the extent the effect of this restriction may be limited by law), and unless specifically stated to the contrary in any written consent to an assignment, no assignment will release or discharge the assignor from any duty or responsibility under the Contract Documents.
- 9.3 OWNER and CONTRACTOR each binds itself, its partners, successors, assigns and legal representatives to the other party hereto, its partners, successors, assigns and legal representatives in respect to all covenants, agreements and obligations contained in the Contract Documents.
- 9.4 Any provision or part of the Contract Documents held to be void or unenforceable under any Law or Regulation shall be deemed stricken, and all remaining provisions shall continue to be valid and binding upon OWNER and CONTRACTOR, who agree the Contract Documents shall be reformed to replace such stricken provision or part thereof with a valid and enforceable provision coming as close as possible to expressing the intention of the stricken provision.

IN WITNESS WHEREOF, OWNER and CONTRACTOR have signed this Agreement in five counterparts. Two counterparts each have been delivered to OWNER and CONTRACTOR and one counterpart to ENGINEER. All portions of the Contract Documents have been signed, initialed or identified by Owner and Contractor or identified by ENGINEER on their behalf.

This Agreement will be effective on _____, 2020 (which is the Effective Date of the Agreement).

OWNER _____

CONTRACTOR_____

BY (typed) _____

BY (typed)_____

BY _____

BY_____

ATTEST _____

ATTEST_____

Address for giving notices

Address for giving notices

License No. _____

Agent for service of process: _____

CORPORATE SEAL

CORPORATE SEAL

DOCUMENT 00611**PERFORMANCE BOND**

KNOW ALL MEN BY THESE PRESENTS, _____,
(Name & Address of Contractor)

hereinafter called "Principal" and _____,
(Name & Address of Surety)

_____ of _____

State of _____, hereinafter called the "Surety" are held and
firmly bound unto _____

hereinafter called the "Owner" in the penal sum of _____

_____ Dollars(\$_____)
(Contract Sum)

lawful money of the United States of America, to be paid to OWNER, for the payment whereof well and truly to be made we do bind ourselves, our respective executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the above bounden Principal has entered into a certain contract with the Owner dated the _____ day of _____, 2020 for the construction of:

Mass Grading Improvements for CUICAR Technology Neighborhood 3

which said contract is incorporated hereby by reference and made a part hereof, and is hereinafter referred to as the Construction Contract.

NOW THEREFORE, THE CONDITION OF THIS OBLIGATION is such, if the Principal shall promptly and faithfully perform and comply with the terms and conditions of said contract; and shall indemnify and save harmless the Owner against and from all costs, expenses, damages, injury or loss to which said Owner may be subjected by reason of any wrongdoing, including patent infringement, misconduct, want of care or skill, default, or failure of performance on the part of said Principal, its agents, subcontractors or employees, in the execution or performance of said Construction Contract, then this obligation shall be null and void; otherwise it shall remain in full force and effect.

1. The Contractor and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Owner for the performance of the Construction Contract, which is incorporated herein by reference.

2. If the Contractor performs the Construction Contract, the Surety and the Contractor shall have no obligation under this Bond, except to participate in conferences as provided in Subparagraph 3.1.
3. If there is no Owner Default, the Surety's obligations under this Bond shall arise after:
 - 3.1 The Owner has notified the Contractor and the Surety at its address described in Paragraph 10 below, the Owner is considering declaring a Contractor Default and has requested and attempted to arrange a conference with the Contractor and the Surety to be held not later than fifteen days after receipt of such notice to discuss methods of performing the Construction Contract. If the Owner, the Contractor and the Surety agree, the Contractor shall be allowed a reasonable time to perform the Construction Contract, but such an agreement shall not waive the Owner's right, if any, subsequently to declare a Contractor Default; and
 - 3.2 The Owner has declared a Contractor Default and formally terminated the Contractor's right to complete the contract. Such Contractor Default shall not be declared earlier than twenty days after the Contractor and the Surety have received notice as provided in Subparagraph 3.1; and
 - 3.3 The Owner has agreed to pay the Balance of the Contract Price to the Surety in accordance with the terms of the Construction Contract or to a Contractor selected to perform the Construction Contract in accordance with the terms of the contract with the Owner.
4. When the Owner has satisfied the conditions of Paragraph 3, the Surety shall promptly and at the Surety's expense, take one of the following actions:
 - 4.1 Arrange for the Contractor, with consent of the Owner, to perform and complete the Construction Contract; or
 - 4.2 Undertake to perform and complete the Construction Contract itself, through its agents or through independent Contractors; or
 - 4.3 Obtain bids or negotiated proposals from qualified Contractors acceptable to the Owner in a contract for performance and completion of the Construction Contract, arrange for a contract to be prepared for execution by the Owner and the Contractor selected with the Owner's concurrence, to be secured with performance and payment bonds executed by a qualified surety equivalent to the bonds issued on the Construction Contract, and pay to the Owner the amount of damages as described in Paragraph 6 in excess of the Balance of the Contract Price incurred by the Owner resulting from the Contractor's default; or
 - 4.4 Waive its right to perform and complete, arrange for completion, or obtain a new Contractor and with reasonable promptness under the circumstances:

- 4.4.1 After investigation, determine the amount for which it may be liable to the Owner and, as soon as practicable after the amount is determined, tender payment therefor to the Owner; or
 - 4.4.2 Deny liability in whole or in part and notify the Owner citing reasons therefor.
5. If the Surety does not proceed as provided in paragraph 4 with reasonable promptness, the Surety shall be deemed to be in default on this Bond fifteen days after receipt of an additional written notice from the Owner to the Surety demanding that the Surety perform its obligations under this Bond, and the Owner shall be entitled to enforce any remedy available to the Owner. If the Surety proceeds as provided in Subparagraph 4.4, and the Owner refuses the payment tendered or the Surety has denied liability, in whole or in part, without further notice the Owner shall be entitled to enforce any remedy available to the Owner.
6. After the Owner has terminated the Contractor's right to complete the Construction Contract, and if the Surety elects to act under Subparagraph 4.1, 4.2, or 4.3 above, then the responsibilities of the Surety to the Owner shall not be greater than those of the Contractor under the Construction Contract. To the limit of the amount of this Bond, but subject to commitment by the Owner of the Balance of the Contract Price to mitigation of costs and damages on the Construction Contract, the Surety is obligated without duplication for:
 - 6.1 The responsibilities of the Contractor for correction of defective work and completion of the Construction Contract:
 - 6.2 Additional legal, design professional and delay costs resulting from the Contractor's Default, and resulting from the actions or failure to act of the Surety under Paragraph 4; and
 - 6.3 Liquidated damages, or if no liquidated damages are specified in the Construction Contract, actual damages caused by delayed performance or non-performance of the Contractor.
7. The Surety shall not be liable to the Owner or others for obligations of the Contractor unrelated to the Contract, and the Balance of the Contract Price shall not be reduced or set off on account of any such unrelated obligations. No right of action shall accrue on this Bond to any person or entity other than the Owner or its heirs, executors, administrators, or successors.
8. The Surety hereby waives notice of any changes, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.
9. Any proceeding, legal or equitable, under this Bond may be instituted in any court of competent jurisdiction in the location in which the work or part of the work is located and shall be instituted within two years after Contractor Default or within two years after the Contractor ceased working or within two years after the Surety refuses or fails to perform its obligations under this Bond, whichever occurs first. If the provisions of this Paragraph are void or prohibited by law, the minimum

period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.

10. Notice to the Surety, the Owner or the Contractor shall be mailed or delivered to the address shown on the signature page.
11. When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. The intent is this Bond shall be construed as a statutory bond and not as a common law bond.
12. DEFINITIONS:
 - 12.1 Balance of the Contract Price: The total amount payable by the Owner to the Contractor under the Construction Contract after all proper adjustments have been made, including allowance to the Contractor of any amounts received or to be received by the Owner in settlement of insurance or other claims for damages to which the Contractor is entitled, reduced by all valid and proper payments made to or on behalf of the Contractor under the Construction Contract.
 - 12.2 Construction Contract: The agreement between the Owner and the Contractor identified on the signature page, including all Contract Documents and changes thereto;
 - 12.3 Contractor Default: Failure of the Contractor, which has neither been remedied nor waived, to perform or otherwise to comply with the terms of the Construction Contract.
 - 12.4 Owner Default: Failure of the Owner, which has neither been remedied nor waived, to pay the Contractor as required by the Construction Contract or to perform and complete or comply with the other terms thereof.

IN WITNESS WHEREOF, this instrument is executed in six counterparts, each one of which shall be deemed an original, on this the ____ day of _____, 20__.

CONTRACTOR AS PRINCIPAL:

Principal

(Principal) Secretary

By: _____
(Signature & Title)

(SEAL)

Address

Witness as to Principal

Address

SURETY:

Surety (Company)

(Surety) Secretary

By: _____
Attorney-in-Fact

(SEAL)

Witness as to Surety

Address

Notes:

1. Date of Bond must not be prior to date of Contract. If Contractor is a Partnership, all partners should execute bond.
2. Bond must be countersigned by a South Carolina resident agent.
3. Surety companies executing bonds must appear on the Treasury Department's most current list (Circular 570 as amended) and be authorized to transact business in the state where the project is located.

DOCUMENT 00621**PAYMENT BOND**

KNOW ALL MEN BY THESE PRESENTS, _____,
(Name & Address of Contractor)

hereinafter called "Principal" and _____,
(Name & Address of Surety)

_____ of _____

State of _____, hereinafter called the "Surety" are held and

firmly bound unto _____

hereinafter called the "Owner" in the penal sum of _____

_____ Dollars (\$ _____)
(Contract Sum)

lawful money of the United States of America, to be paid to OWNER, for the payment whereof well and truly to be made we do bind ourselves, our respective executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the above bounden Principal has entered into a certain contract with the Owner dated the _____ day of _____, 2020 for the construction of:

Mass Grading Improvements for CUICAR Technology Neighborhood 3

which said contract is incorporated hereby by reference and made a part hereof, and is hereinafter referred to as the Construction Contract.

NOW THEREFORE, THE CONDITION OF THIS OBLIGATION is such, if the Principal shall promptly make payment to all claimants as hereinafter defined, for all labor and materials supplied in the prosecution of the work provided for in said Construction Contract, then this obligation shall be void; otherwise it shall remain in full force and effect, subject, however, to the following conditions:

1. The Contractor and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Owner for the performance of the Construction Contract, which is incorporated herein by reference.
2. With respect to the Owner, this obligation shall be null and void if the Contractor:
 - 2.1 Promptly makes payment, directly or indirectly, for all sums due Claimants; and

- 2.2 Defends, indemnifies and holds harmless the Owner from claims, demands, liens or suits by any person or entity whose claim, demand, lien or suit is for payment for labor, materials or equipment furnished for use in the performance of the Construction Contract, provided the Owner has promptly notified the Contractor and the Surety (at the address described in Paragraph 12) of any claims, demands, liens or suits and tendered defense of such claims, demands, liens or suits to the Contractor and the Surety, and provided there is no Owner Default.
3. With respect to Claimants, this obligation shall be null and void if the Contractor promptly makes payment, directly or indirectly, for all sums due.
4. The Surety shall have no obligation to Claimants under this Bond until:
 - 4.1 Claimants who are employed by or have a direct contract with the Contractor have given notice to the Surety (at the address described in Paragraph 12) and sent a copy, or notice thereof, to the Owner, stating a claim is being made under this Bond and, with substantial accuracy, the amount of claim.
 - 4.2 Claimants who do not have a direct contract with the Contractor:
 - 4.2.1 Have furnished written notice to the Contractor and sent a copy, or notice thereof, to the Owner, within 90 days after having last performed labor or last furnished materials or equipment included in the claim stating, with substantial accuracy, the amount of the claim and the name of the party to whom the materials were furnished or supplied or for whom the labor was performed; and
 - 4.2.2 Have either received a rejection in whole or in part from the Contractor, or not received within 30 days of furnishing the above notice, any communication from the Contractor by which the Contractor has indicated the claim will be paid directly or indirectly; and
 - 4.2.3 Not having been paid within 30 days, have sent a written notice to the Surety (at the address described in Paragraph 12) and sent a copy, or notice thereof, to the Owner, stating a claim is being made under this Bond and enclosing a copy of the previous written notice furnished to the Contractor.
5. Compliance shall be considered sufficient if a notice required by paragraph 4 is given by the Owner to the Contractor or to the Surety.
6. When the Claimant has satisfied the conditions of Paragraph 4, the Surety shall promptly and at the Surety's expense take the following actions:
 - 6.1 Send an answer to the Claimant, with a copy to the Owner, within 45 days after receipt of the claim stating the amounts undisputed and basis for challenging any amounts disputed.

- 6.2 Pay or arrange for payment of any undisputed amounts.
7. The Surety's total obligation shall not exceed the amount of this Bond, and the amount of this Bond shall be credited for any payments made in good faith by the Surety.
 8. Amounts owed by the Owner to the Contractor under the Construction Contract shall be used for the performance of the Construction Contract and to satisfy claims, if any, under any Construction Performance Bond. By the Contractor furnishing and the Owner accepting this Bond, they agree all funds earned by the Contractor in the performance of the Construction Contract are dedicated to satisfying obligations of the Contractor and the Surety under this Bond, subject to the Owner's priority to use the funds for the completion of the work.
 9. The Surety shall not be liable to the Owner, Claimants or others for obligations of the Contractor unrelated to the Construction Contract. The Owner shall not be liable for payment of any costs or expenses of any Claimant under this Bond, and shall have under this Bond no obligations to make payments to, give notices on behalf of, or otherwise have obligations to Claimants under this Bond.
 10. The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.
 11. No suit or action shall be commenced by a Claimant under this bond other than in a court of competent jurisdiction in the location in which the work or part of the work is located or after the expiration of one year from the date (1) on which the Claimant gave the notice required by Subparagraph 4.1 or Clause 4.2.3, or (2) on which the last labor or service was performed by anyone or the last materials or equipment were furnished by anyone under the Construction Contract, whichever of (1) or (2) first occurs. If the provisions of this paragraph are void or prohibited by law, the minimum period of limitation available to Sureties as a defense in the jurisdiction of the suit shall be applicable.
 12. Notice to the Surety, Owner or Contractor shall be mailed or delivered to the address shown on the signature page. Actual receipt of notice by the Surety, Owner, or Contractor, however accomplished, shall be sufficient compliance as of the date received at the address shown on the signature page.
 13. When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in the Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. The intent is this Bond shall be construed as a statutory bond and not as a common law bond.
 14. Upon request of any person or entity appearing to be a potential beneficiary of this Bond, the Contractor shall promptly furnish a copy of this Bond or shall permit a copy to be made.

15. DEFINITIONS:

- 15.1 Claimant: An individual or entity having a direct contract with the Contractor or with a Subcontractor of the Contractor to furnish labor, material, or equipment for use in the performance of the Contract. The intent of this Bond shall be to include without limitation in the terms "labor, materials or equipment," that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental equipment used in the Construction Contract, architectural and engineering services required for performance of the work of the Contractor and the Contractor's Subcontractors, and all other items for which a mechanic's lien may be asserted in the jurisdiction where the labor, materials or equipment were furnished.
- 15.2 Construction Contract: The agreement between the Owner and the Contractor identified on the signature page, including all Contract Documents and changes thereto.
- 15.3 Owner Default: Failure of the Owner, which has neither been remedied nor waived, to pay the Contractor as required by the Construction Contract or to perform and complete or comply with the other terms thereof.

IN WITNESS WHEREOF, this instrument is executed in six counterparts, each one of which shall be deemed an original, on this the ____ day of _____, 20__.

CONTRACTOR AS PRINCIPAL:

Principal

(Principal) Secretary

By: _____
(Signature & Title)

(SEAL)

Address

Witness as to Principal

Address

SURETY:

Surety (Company)

(Surety) Secretary

By: _____
Attorney-in-Fact

(SEAL)

Witness as to Surety

Address

Notes:

1. Date of Bond must not be prior to date of Contract. If Contractor is a Partnership, all partners should execute bond.
2. Bond must be countersigned by a South Carolina resident agent.
3. Surety companies executing bonds must appear on the Treasury Department's most current list (Circular 570 as amended) and be authorized to transact business in the state where the project is located.

SECTION 00631
NOTICE OF AWARD

Dated _____

TO: _____
(Bidder)

ADDRESS: _____

JOB NO.: J-28283.0000

PROJECT: Mass Grading Improvements for CUICAR Technology Neighborhood 3

CONTRACT FOR: Work includes clearing, earthwork, mass grading, installation of storm drainage, and erosion control improvements for approximately 23 acres.

You are notified your Bid dated _____, 2020, for the above Contract has been considered. You are the apparent successful bidder and have been awarded a contract for:

(Indicate total Work, alternates or sections of Work awarded)

The Contract Price of your contract is _____ Dollars (\$_____).

_____ copies of each of the proposed Contract Documents (except drawings) accompany this Notice of Award.

_____ sets of the Drawings will be delivered separately or otherwise made available to you immediately.

You must comply with the following conditions precedent within 15 days of this Notice of Award, which is by _____, 20_____.

1. You must deliver to the OWNER _____ fully executed counterparts of the Agreement including all the Contract Documents. Each of the Contract Documents must bear your signature on the page (pages _____.)
2. You must deliver with the executed Agreement the Contract Security (Bonds) as specified in the Instructions to Bidders (Article 8), General Conditions (paragraph 5.01) and Supplementary Conditions.
3. (List other conditions precedent)

Failure to comply with these conditions within the time specified will entitle OWNER to consider your bid in default, to annul this Notice of Award and to declare your Bid Security forfeited.

Within ten days after you comply with the above conditions, OWNER will return to you one fully signed counterpart of the Agreement with the Contract Documents attached.

OWNER

By: _____

(Title)

ACCEPTANCE OF AWARD

(Contractor)

By: _____
(Authorized Signature)

(Title)

(Date)

Section 00641
NOTICE TO PROCEED

Dated: _____

TO: _____
(Bidder)

ADDRESS: _____

JOB NO.: J- 28283.0000 _____

PROJECT: Mass Grading Improvements for CUICAR Technology Neighborhood 3 _____

CONTRACT
FOR: Work includes clearing, earthwork, mass grading, installation of storm drainage, and erosion control improvements for approximately 23 acres.

You are notified the Contract Times under the above contract will commence to run on _____, 2020. By such date, you are to start performing your obligations under the Contract Documents. In accordance with Article 3 of the Agreement the dates of Substantial Completion and completion and readiness for final payment are _____, 2020 and _____, 2020, respectively.

Before you may start any Work at the site, paragraph 2.01 of the General Conditions provides you and OWNER must each deliver to the other (with copies to ENGINEER and other identified additional insureds) certificates of insurance which each is required to purchase and maintain in accordance with the Contract Documents.

Before you may start any Work at the site, you must have submitted the following: Certificate of Insurance, Performance Bond, and Payment Bond.

OWNER

By: _____

(Title)

ACCEPTANCE OF NOTICE TO PROCEED

(Contractor)

By: _____
(Authorized Signature)

(Title)

(Date)

This document has important legal consequences; consultation with an attorney is encouraged with respect to its use or modification. This document should be adapted to the particular circumstances of the contemplated Project and the controlling Laws and Regulations.

STANDARD GENERAL CONDITIONS OF THE CONSTRUCTION CONTRACT

Prepared by

ENGINEERS JOINT CONTRACT DOCUMENTS COMMITTEE

and

Issued and Published Jointly by

ACEC

AMERICAN COUNCIL OF ENGINEERING COMPANIES



ASCE American Society
of Civil Engineers

PE National Society of
Professional Engineers
Professional Engineers in Private Practice

AMERICAN COUNCIL OF ENGINEERING COMPANIES

ASSOCIATED GENERAL CONTRACTORS OF AMERICA

AMERICAN SOCIETY OF CIVIL ENGINEERS

PROFESSIONAL ENGINEERS IN PRIVATE PRACTICE

A Practice Division of the

NATIONAL SOCIETY OF PROFESSIONAL ENGINEERS

Endorsed by



CONSTRUCTION SPECIFICATIONS INSTITUTE

These General Conditions have been prepared for use with the Suggested Forms of Agreement Between Owner and Contractor (EJCDC C-520 or C-525, 2007 Editions). Their provisions are interrelated and a change in one may necessitate a change in the other. Comments concerning their usage are contained in the Narrative Guide to the EJCDC Construction Documents (EJCDC C-001, 2007 Edition). For guidance in the preparation of Supplementary Conditions, see Guide to the Preparation of Supplementary Conditions (EJCDC C-800, 2007 Edition).

Copyright © 2007 National Society of Professional Engineers
1420 King Street, Alexandria, VA 22314-2794
(703) 684-2882
www.nspe.org

American Council of Engineering Companies
1015 15th Street N.W., Washington, DC 20005
(202) 347-7474
www.acec.org

American Society of Civil Engineers
1801 Alexander Bell Drive, Reston, VA 20191-4400
(800) 548-2723
www.asce.org

Associated General Contractors of America
2300 Wilson Boulevard, Suite 400, Arlington, VA 22201-3308
(703) 548-3118
www.agc.org

The copyright for this EJCDC document is owned jointly by the four EJCDC sponsoring organizations and held in trust for their benefit by NSPE.

**STANDARD GENERAL CONDITIONS OF THE
CONSTRUCTION CONTRACT**

TABLE OF CONTENTS

	Page
Article 1 – Definitions and Terminology	1
1.01 Defined Terms.....	1
1.02 Terminology	5
Article 2 – Preliminary Matters	6
2.01 Delivery of Bonds and Evidence of Insurance	6
2.02 Copies of Documents	6
2.03 Commencement of Contract Times; Notice to Proceed.....	6
2.04 Starting the Work	7
2.05 Before Starting Construction	7
2.06 Preconstruction Conference; Designation of Authorized Representatives	7
2.07 Initial Acceptance of Schedules	7
Article 3 – Contract Documents: Intent, Amending, Reuse	8
3.01 Intent.....	8
3.02 Reference Standards.....	8
3.03 Reporting and Resolving Discrepancies.....	9
3.04 Amending and Supplementing Contract Documents	9
3.05 Reuse of Documents	10
3.06 Electronic Data.....	10
Article 4 – Availability of Lands; Subsurface and Physical Conditions; Hazardous Environmental Conditions; Reference Points.....	11
4.01 Availability of Lands.....	11
4.02 Subsurface and Physical Conditions.....	11
4.03 Differing Subsurface or Physical Conditions	12
4.04 Underground Facilities.....	13
4.05 Reference Points.....	14
4.06 Hazardous Environmental Condition at Site	14
Article 5 – Bonds and Insurance.....	16
5.01 Performance, Payment, and Other Bonds.....	16
5.02 Licensed Sureties and Insurers.....	16
5.03 Certificates of Insurance	17
5.04 Contractor’s Insurance	17
5.05 Owner’s Liability Insurance.....	19
5.06 Property Insurance.....	19
5.07 Waiver of Rights	20
5.08 Receipt and Application of Insurance Proceeds	21

5.09	Acceptance of Bonds and Insurance; Option to Replace	21
5.10	Partial Utilization, Acknowledgment of Property Insurer.....	22
Article 6 – Contractor’s Responsibilities		22
6.01	Supervision and Superintendence.....	22
6.02	Labor; Working Hours	22
6.03	Services, Materials, and Equipment	22
6.04	Progress Schedule	23
6.05	Substitutes and “Or-Equals”	23
6.06	Concerning Subcontractors, Suppliers, and Others.....	25
6.07	Patent Fees and Royalties	27
6.08	Permits.....	27
6.09	Laws and Regulations	28
6.10	Taxes	28
6.11	Use of Site and Other Areas.....	28
6.12	Record Documents.....	29
6.13	Safety and Protection	29
6.14	Safety Representative.....	30
6.15	Hazard Communication Programs.....	30
6.16	Emergencies	30
6.17	Shop Drawings and Samples	31
6.18	Continuing the Work.....	32
6.19	Contractor’s General Warranty and Guarantee	33
6.20	Indemnification	33
6.21	Delegation of Professional Design Services.....	34
Article 7 – Other Work at the Site.....		35
7.01	Related Work at Site	35
7.02	Coordination.....	35
7.03	Legal Relationships.....	36
Article 8 – Owner’s Responsibilities.....		36
8.01	Communications to Contractor.....	36
8.02	Replacement of Engineer	36
8.03	Furnish Data	36
8.04	Pay When Due.....	36
8.05	Lands and Easements; Reports and Tests.....	36
8.06	Insurance.....	36
8.07	Change Orders.....	37
8.08	Inspections, Tests, and Approvals	37
8.09	Limitations on Owner’s Responsibilities	37
8.10	Undisclosed Hazardous Environmental Condition	37
8.11	Evidence of Financial Arrangements.....	37
8.12	Compliance with Safety Program.....	37
Article 9 – Engineer’s Status During Construction.....		37
9.01	Owner’s Representative	37

9.02	Visits to Site	37
9.03	Project Representative.....	38
9.04	Authorized Variations in Work	38
9.05	Rejecting Defective Work.....	38
9.06	Shop Drawings, Change Orders and Payments	39
9.07	Determinations for Unit Price Work	39
9.08	Decisions on Requirements of Contract Documents and Acceptability of Work	39
9.09	Limitations on Engineer’s Authority and Responsibilities	39
9.10	Compliance with Safety Program	40
Article 10 – Changes in the Work; Claims		40
10.01	Authorized Changes in the Work	40
10.02	Unauthorized Changes in the Work.....	41
10.03	Execution of Change Orders.....	41
10.04	Notification to Surety.....	41
10.05	Claims.....	41
Article 11 – Cost of the Work; Allowances; Unit Price Work		42
11.01	Cost of the Work	42
11.02	Allowances	45
11.03	Unit Price Work	45
Article 12 – Change of Contract Price; Change of Contract Times		46
12.01	Change of Contract Price	46
12.02	Change of Contract Times	47
12.03	Delays	47
Article 13 – Tests and Inspections; Correction, Removal or Acceptance of Defective Work.....		48
13.01	Notice of Defects.....	48
13.02	Access to Work	48
13.03	Tests and Inspections	49
13.04	Uncovering Work.....	49
13.05	Owner May Stop the Work.....	50
13.06	Correction or Removal of Defective Work	50
13.07	Correction Period	50
13.08	Acceptance of Defective Work.....	51
13.09	Owner May Correct Defective Work	52
Article 14 – Payments to Contractor and Completion		52
14.01	Schedule of Values.....	52
14.02	Progress Payments	52
14.03	Contractor’s Warranty of Title.....	55
14.04	Substantial Completion.....	55
14.05	Partial Utilization	56
14.06	Final Inspection	57
14.07	Final Payment.....	57
14.08	Final Completion Delayed	58

14.09 Waiver of Claims	58
Article 15 – Suspension of Work and Termination	59
15.01 Owner May Suspend Work.....	59
15.02 Owner May Terminate for Cause	59
15.03 Owner May Terminate For Convenience	60
15.04 Contractor May Stop Work or Terminate.....	60
Article 16 – Dispute Resolution	61
16.01 Methods and Procedures	61
Article 17 – Miscellaneous	61
17.01 Giving Notice	61
17.02 Computation of Times	62
17.03 Cumulative Remedies	62
17.04 Survival of Obligations	62
17.05 Controlling Law	62
17.06 Headings.....	62

ARTICLE 1 – DEFINITIONS AND TERMINOLOGY

1.01 *Defined Terms*

- A. Wherever used in the Bidding Requirements or Contract Documents and printed with initial capital letters, the terms listed below will have the meanings indicated which are applicable to both the singular and plural thereof. In addition to terms specifically defined, terms with initial capital letters in the Contract Documents include references to identified articles and paragraphs, and the titles of other documents or forms.
1. *Addenda*—Written or graphic instruments issued prior to the opening of Bids which clarify, correct, or change the Bidding Requirements or the proposed Contract Documents.
 2. *Agreement*—The written instrument which is evidence of the agreement between Owner and Contractor covering the Work.
 3. *Application for Payment*—The form acceptable to Engineer which is to be used by Contractor during the course of the Work in requesting progress or final payments and which is to be accompanied by such supporting documentation as is required by the Contract Documents.
 4. *Asbestos*—Any material that contains more than one percent asbestos and is friable or is releasing asbestos fibers into the air above current action levels established by the United States Occupational Safety and Health Administration.
 5. *Bid*—The offer or proposal of a Bidder submitted on the prescribed form setting forth the prices for the Work to be performed.
 6. *Bidder*—The individual or entity who submits a Bid directly to Owner.
 7. *Bidding Documents*—The Bidding Requirements and the proposed Contract Documents (including all Addenda).
 8. *Bidding Requirements*—The advertisement or invitation to bid, Instructions to Bidders, Bid security of acceptable form, if any, and the Bid Form with any supplements.
 9. *Change Order*—A document recommended by Engineer which is signed by Contractor and Owner and authorizes an addition, deletion, or revision in the Work or an adjustment in the Contract Price or the Contract Times, issued on or after the Effective Date of the Agreement.
 10. *Claim*—A demand or assertion by Owner or Contractor seeking an adjustment of Contract Price or Contract Times, or both, or other relief with respect to the terms of the Contract. A demand for money or services by a third party is not a Claim.
 11. *Contract*—The entire and integrated written agreement between the Owner and Contractor concerning the Work. The Contract supersedes prior negotiations, representations, or agreements, whether written or oral.

12. *Contract Documents*—Those items so designated in the Agreement. Only printed or hard copies of the items listed in the Agreement are Contract Documents. Approved Shop Drawings, other Contractor submittals, and the reports and drawings of subsurface and physical conditions are not Contract Documents.
13. *Contract Price*—The moneys payable by Owner to Contractor for completion of the Work in accordance with the Contract Documents as stated in the Agreement (subject to the provisions of Paragraph 11.03 in the case of Unit Price Work).
14. *Contract Times*—The number of days or the dates stated in the Agreement to: (i) achieve Milestones, if any; (ii) achieve Substantial Completion; and (iii) complete the Work so that it is ready for final payment as evidenced by Engineer's written recommendation of final payment.
15. *Contractor*—The individual or entity with whom Owner has entered into the Agreement.
16. *Cost of the Work*—See Paragraph 11.01 for definition.
17. *Drawings*—That part of the Contract Documents prepared or approved by Engineer which graphically shows the scope, extent, and character of the Work to be performed by Contractor. Shop Drawings and other Contractor submittals are not Drawings as so defined.
18. *Effective Date of the Agreement*—The date indicated in the Agreement on which it becomes effective, but if no such date is indicated, it means the date on which the Agreement is signed and delivered by the last of the two parties to sign and deliver.
19. *Engineer*—The individual or entity named as such in the Agreement.
20. *Field Order*—A written order issued by Engineer which requires minor changes in the Work but which does not involve a change in the Contract Price or the Contract Times.
21. *General Requirements*—Sections of Division 1 of the Specifications.
22. *Hazardous Environmental Condition*—The presence at the Site of Asbestos, PCBs, Petroleum, Hazardous Waste, or Radioactive Material in such quantities or circumstances that may present a substantial danger to persons or property exposed thereto.
23. *Hazardous Waste*—The term Hazardous Waste shall have the meaning provided in Section 1004 of the Solid Waste Disposal Act (42 USC Section 6903) as amended from time to time.
24. *Laws and Regulations; Laws or Regulations*—Any and all applicable laws, rules, regulations, ordinances, codes, and orders of any and all governmental bodies, agencies, authorities, and courts having jurisdiction.
25. *Liens*—Charges, security interests, or encumbrances upon Project funds, real property, or personal property.
26. *Milestone*—A principal event specified in the Contract Documents relating to an intermediate completion date or time prior to Substantial Completion of all the Work.

27. *Notice of Award*—The written notice by Owner to the Successful Bidder stating that upon timely compliance by the Successful Bidder with the conditions precedent listed therein, Owner will sign and deliver the Agreement.
28. *Notice to Proceed*—A written notice given by Owner to Contractor fixing the date on which the Contract Times will commence to run and on which Contractor shall start to perform the Work under the Contract Documents.
29. *Owner*—The individual or entity with whom Contractor has entered into the Agreement and for whom the Work is to be performed.
30. *PCBs*—Polychlorinated biphenyls.
31. *Petroleum*—Petroleum, including crude oil or any fraction thereof which is liquid at standard conditions of temperature and pressure (60 degrees Fahrenheit and 14.7 pounds per square inch absolute), such as oil, petroleum, fuel oil, oil sludge, oil refuse, gasoline, kerosene, and oil mixed with other non-Hazardous Waste and crude oils.
32. *Progress Schedule*—A schedule, prepared and maintained by Contractor, describing the sequence and duration of the activities comprising the Contractor's plan to accomplish the Work within the Contract Times.
33. *Project*—The total construction of which the Work to be performed under the Contract Documents may be the whole, or a part.
34. *Project Manual*—The bound documentary information prepared for bidding and constructing the Work. A listing of the contents of the Project Manual, which may be bound in one or more volumes, is contained in the table(s) of contents.
35. *Radioactive Material*—Source, special nuclear, or byproduct material as defined by the Atomic Energy Act of 1954 (42 USC Section 2011 et seq.) as amended from time to time.
36. *Resident Project Representative*—The authorized representative of Engineer who may be assigned to the Site or any part thereof.
37. *Samples*—Physical examples of materials, equipment, or workmanship that are representative of some portion of the Work and which establish the standards by which such portion of the Work will be judged.
38. *Schedule of Submittals*—A schedule, prepared and maintained by Contractor, of required submittals and the time requirements to support scheduled performance of related construction activities.
39. *Schedule of Values*—A schedule, prepared and maintained by Contractor, allocating portions of the Contract Price to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

40. *Shop Drawings*—All drawings, diagrams, illustrations, schedules, and other data or information which are specifically prepared or assembled by or for Contractor and submitted by Contractor to illustrate some portion of the Work.
41. *Site*—Lands or areas indicated in the Contract Documents as being furnished by Owner upon which the Work is to be performed, including rights-of-way and easements for access thereto, and such other lands furnished by Owner which are designated for the use of Contractor.
42. *Specifications*—That part of the Contract Documents consisting of written requirements for materials, equipment, systems, standards and workmanship as applied to the Work, and certain administrative requirements and procedural matters applicable thereto.
43. *Subcontractor*—An individual or entity having a direct contract with Contractor or with any other Subcontractor for the performance of a part of the Work at the Site.
44. *Substantial Completion*—The time at which the Work (or a specified part thereof) has progressed to the point where, in the opinion of Engineer, the Work (or a specified part thereof) is sufficiently complete, in accordance with the Contract Documents, so that the Work (or a specified part thereof) can be utilized for the purposes for which it is intended. The terms “substantially complete” and “substantially completed” as applied to all or part of the Work refer to Substantial Completion thereof.
45. *Successful Bidder*—The Bidder submitting a responsive Bid to whom Owner makes an award.
46. *Supplementary Conditions*—That part of the Contract Documents which amends or supplements these General Conditions.
47. *Supplier*—A manufacturer, fabricator, supplier, distributor, materialman, or vendor having a direct contract with Contractor or with any Subcontractor to furnish materials or equipment to be incorporated in the Work by Contractor or Subcontractor.
48. *Underground Facilities*—All underground pipelines, conduits, ducts, cables, wires, manholes, vaults, tanks, tunnels, or other such facilities or attachments, and any encasements containing such facilities, including those that convey electricity, gases, steam, liquid petroleum products, telephone or other communications, cable television, water, wastewater, storm water, other liquids or chemicals, or traffic or other control systems.
49. *Unit Price Work*—Work to be paid for on the basis of unit prices.
50. *Work*—The entire construction or the various separately identifiable parts thereof required to be provided under the Contract Documents. Work includes and is the result of performing or providing all labor, services, and documentation necessary to produce such construction, and furnishing, installing, and incorporating all materials and equipment into such construction, all as required by the Contract Documents.
51. *Work Change Directive*—A written statement to Contractor issued on or after the Effective Date of the Agreement and signed by Owner and recommended by Engineer ordering an

addition, deletion, or revision in the Work, or responding to differing or unforeseen subsurface or physical conditions under which the Work is to be performed or to emergencies. A Work Change Directive will not change the Contract Price or the Contract Times but is evidence that the parties expect that the change ordered or documented by a Work Change Directive will be incorporated in a subsequently issued Change Order following negotiations by the parties as to its effect, if any, on the Contract Price or Contract Times.

1.02 Terminology

A. The words and terms discussed in Paragraph 1.02.B through F are not defined but, when used in the Bidding Requirements or Contract Documents, have the indicated meaning.

B. *Intent of Certain Terms or Adjectives:*

1. The Contract Documents include the terms “as allowed,” “as approved,” “as ordered,” “as directed” or terms of like effect or import to authorize an exercise of professional judgment by Engineer. In addition, the adjectives “reasonable,” “suitable,” “acceptable,” “proper,” “satisfactory,” or adjectives of like effect or import are used to describe an action or determination of Engineer as to the Work. It is intended that such exercise of professional judgment, action, or determination will be solely to evaluate, in general, the Work for compliance with the information in the Contract Documents and with the design concept of the Project as a functioning whole as shown or indicated in the Contract Documents (unless there is a specific statement indicating otherwise). The use of any such term or adjective is not intended to and shall not be effective to assign to Engineer any duty or authority to supervise or direct the performance of the Work, or any duty or authority to undertake responsibility contrary to the provisions of Paragraph 9.09 or any other provision of the Contract Documents.

C. *Day:*

1. The word “day” means a calendar day of 24 hours measured from midnight to the next midnight.

D. *Defective:*

1. The word “defective,” when modifying the word “Work,” refers to Work that is unsatisfactory, faulty, or deficient in that it:
 - a. does not conform to the Contract Documents; or
 - b. does not meet the requirements of any applicable inspection, reference standard, test, or approval referred to in the Contract Documents; or
 - c. has been damaged prior to Engineer’s recommendation of final payment (unless responsibility for the protection thereof has been assumed by Owner at Substantial Completion in accordance with Paragraph 14.04 or 14.05).

E. *Furnish, Install, Perform, Provide:*

1. The word “furnish,” when used in connection with services, materials, or equipment, shall mean to supply and deliver said services, materials, or equipment to the Site (or some other specified location) ready for use or installation and in usable or operable condition.
2. The word “install,” when used in connection with services, materials, or equipment, shall mean to put into use or place in final position said services, materials, or equipment complete and ready for intended use.
3. The words “perform” or “provide,” when used in connection with services, materials, or equipment, shall mean to furnish and install said services, materials, or equipment complete and ready for intended use.
4. When “furnish,” “install,” “perform,” or “provide” is not used in connection with services, materials, or equipment in a context clearly requiring an obligation of Contractor, “provide” is implied.

F. Unless stated otherwise in the Contract Documents, words or phrases that have a well-known technical or construction industry or trade meaning are used in the Contract Documents in accordance with such recognized meaning.

ARTICLE 2 – PRELIMINARY MATTERS

2.01 Delivery of Bonds and Evidence of Insurance

- A. When Contractor delivers the executed counterparts of the Agreement to Owner, Contractor shall also deliver to Owner such bonds as Contractor may be required to furnish.
- B. *Evidence of Insurance:* Before any Work at the Site is started, Contractor and Owner shall each deliver to the other, with copies to each additional insured identified in the Supplementary Conditions, certificates of insurance (and other evidence of insurance which either of them or any additional insured may reasonably request) which Contractor and Owner respectively are required to purchase and maintain in accordance with Article 5.

2.02 Copies of Documents

- A. Owner shall furnish to Contractor up to ten printed or hard copies of the Drawings and Project Manual. Additional copies will be furnished upon request at the cost of reproduction.

2.03 Commencement of Contract Times; Notice to Proceed

- A. The Contract Times will commence to run on the thirtieth day after the Effective Date of the Agreement or, if a Notice to Proceed is given, on the day indicated in the Notice to Proceed. A Notice to Proceed may be given at any time within 30 days after the Effective Date of the Agreement. In no event will the Contract Times commence to run later than the sixtieth day after the day of Bid opening or the thirtieth day after the Effective Date of the Agreement, whichever date is earlier.

2.04 *Starting the Work*

- A. Contractor shall start to perform the Work on the date when the Contract Times commence to run. No Work shall be done at the Site prior to the date on which the Contract Times commence to run.

2.05 *Before Starting Construction*

- A. *Preliminary Schedules:* Within 10 days after the Effective Date of the Agreement (unless otherwise specified in the General Requirements), Contractor shall submit to Engineer for timely review:
 - 1. a preliminary Progress Schedule indicating the times (numbers of days or dates) for starting and completing the various stages of the Work, including any Milestones specified in the Contract Documents;
 - 2. a preliminary Schedule of Submittals; and
 - 3. a preliminary Schedule of Values for all of the Work which includes quantities and prices of items which when added together equal the Contract Price and subdivides the Work into component parts in sufficient detail to serve as the basis for progress payments during performance of the Work. Such prices will include an appropriate amount of overhead and profit applicable to each item of Work.

2.06 *Preconstruction Conference; Designation of Authorized Representatives*

- A. Before any Work at the Site is started, a conference attended by Owner, Contractor, Engineer, and others as appropriate will be held to establish a working understanding among the parties as to the Work and to discuss the schedules referred to in Paragraph 2.05.A, procedures for handling Shop Drawings and other submittals, processing Applications for Payment, and maintaining required records.
- B. At this conference Owner and Contractor each shall designate, in writing, a specific individual to act as its authorized representative with respect to the services and responsibilities under the Contract. Such individuals shall have the authority to transmit instructions, receive information, render decisions relative to the Contract, and otherwise act on behalf of each respective party.

2.07 *Initial Acceptance of Schedules*

- A. At least 10 days before submission of the first Application for Payment a conference attended by Contractor, Engineer, and others as appropriate will be held to review for acceptability to Engineer as provided below the schedules submitted in accordance with Paragraph 2.05.A. Contractor shall have an additional 10 days to make corrections and adjustments and to complete and resubmit the schedules. No progress payment shall be made to Contractor until acceptable schedules are submitted to Engineer.
 - 1. The Progress Schedule will be acceptable to Engineer if it provides an orderly progression of the Work to completion within the Contract Times. Such acceptance will not impose on

Engineer responsibility for the Progress Schedule, for sequencing, scheduling, or progress of the Work, nor interfere with or relieve Contractor from Contractor's full responsibility therefor.

2. Contractor's Schedule of Submittals will be acceptable to Engineer if it provides a workable arrangement for reviewing and processing the required submittals.
3. Contractor's Schedule of Values will be acceptable to Engineer as to form and substance if it provides a reasonable allocation of the Contract Price to component parts of the Work.

ARTICLE 3 – CONTRACT DOCUMENTS: INTENT, AMENDING, REUSE

3.01 *Intent*

- A. The Contract Documents are complementary; what is required by one is as binding as if required by all.
- B. It is the intent of the Contract Documents to describe a functionally complete project (or part thereof) to be constructed in accordance with the Contract Documents. Any labor, documentation, services, materials, or equipment that reasonably may be inferred from the Contract Documents or from prevailing custom or trade usage as being required to produce the indicated result will be provided whether or not specifically called for, at no additional cost to Owner.
- C. Clarifications and interpretations of the Contract Documents shall be issued by Engineer as provided in Article 9.

3.02 *Reference Standards*

- A. Standards, Specifications, Codes, Laws, and Regulations
 1. Reference to standards, specifications, manuals, or codes of any technical society, organization, or association, or to Laws or Regulations, whether such reference be specific or by implication, shall mean the standard, specification, manual, code, or Laws or Regulations in effect at the time of opening of Bids (or on the Effective Date of the Agreement if there were no Bids), except as may be otherwise specifically stated in the Contract Documents.
 2. No provision of any such standard, specification, manual, or code, or any instruction of a Supplier, shall be effective to change the duties or responsibilities of Owner, Contractor, or Engineer, or any of their subcontractors, consultants, agents, or employees, from those set forth in the Contract Documents. No such provision or instruction shall be effective to assign to Owner, Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors, any duty or authority to supervise or direct the performance of the Work or any duty or authority to undertake responsibility inconsistent with the provisions of the Contract Documents.

3.03 *Reporting and Resolving Discrepancies*

A. *Reporting Discrepancies:*

1. *Contractor's Review of Contract Documents Before Starting Work:* Before undertaking each part of the Work, Contractor shall carefully study and compare the Contract Documents and check and verify pertinent figures therein and all applicable field measurements. Contractor shall promptly report in writing to Engineer any conflict, error, ambiguity, or discrepancy which Contractor discovers, or has actual knowledge of, and shall obtain a written interpretation or clarification from Engineer before proceeding with any Work affected thereby.
2. *Contractor's Review of Contract Documents During Performance of Work:* If, during the performance of the Work, Contractor discovers any conflict, error, ambiguity, or discrepancy within the Contract Documents, or between the Contract Documents and (a) any applicable Law or Regulation, (b) any standard, specification, manual, or code, or (c) any instruction of any Supplier, then Contractor shall promptly report it to Engineer in writing. Contractor shall not proceed with the Work affected thereby (except in an emergency as required by Paragraph 6.16.A) until an amendment or supplement to the Contract Documents has been issued by one of the methods indicated in Paragraph 3.04.
3. Contractor shall not be liable to Owner or Engineer for failure to report any conflict, error, ambiguity, or discrepancy in the Contract Documents unless Contractor had actual knowledge thereof.

B. *Resolving Discrepancies:*

1. Except as may be otherwise specifically stated in the Contract Documents, the provisions of the Contract Documents shall take precedence in resolving any conflict, error, ambiguity, or discrepancy between the provisions of the Contract Documents and:
 - a. the provisions of any standard, specification, manual, or code, or the instruction of any Supplier (whether or not specifically incorporated by reference in the Contract Documents); or
 - b. the provisions of any Laws or Regulations applicable to the performance of the Work (unless such an interpretation of the provisions of the Contract Documents would result in violation of such Law or Regulation).

3.04 *Amending and Supplementing Contract Documents*

- A. The Contract Documents may be amended to provide for additions, deletions, and revisions in the Work or to modify the terms and conditions thereof by either a Change Order or a Work Change Directive.
- B. The requirements of the Contract Documents may be supplemented, and minor variations and deviations in the Work may be authorized, by one or more of the following ways:

1. A Field Order;
2. Engineer's approval of a Shop Drawing or Sample (subject to the provisions of Paragraph 6.17.D.3); or
3. Engineer's written interpretation or clarification.

3.05 *Reuse of Documents*

- A. Contractor and any Subcontractor or Supplier shall not:
1. have or acquire any title to or ownership rights in any of the Drawings, Specifications, or other documents (or copies of any thereof) prepared by or bearing the seal of Engineer or its consultants, including electronic media editions; or
 2. reuse any such Drawings, Specifications, other documents, or copies thereof on extensions of the Project or any other project without written consent of Owner and Engineer and specific written verification or adaptation by Engineer.
- B. The prohibitions of this Paragraph 3.05 will survive final payment, or termination of the Contract. Nothing herein shall preclude Contractor from retaining copies of the Contract Documents for record purposes.

3.06 *Electronic Data*

- A. Unless otherwise stated in the Supplementary Conditions, the data furnished by Owner or Engineer to Contractor, or by Contractor to Owner or Engineer, that may be relied upon are limited to the printed copies (also known as hard copies). Files in electronic media format of text, data, graphics, or other types are furnished only for the convenience of the receiving party. Any conclusion or information obtained or derived from such electronic files will be at the user's sole risk. If there is a discrepancy between the electronic files and the hard copies, the hard copies govern.
- B. Because data stored in electronic media format can deteriorate or be modified inadvertently or otherwise without authorization of the data's creator, the party receiving electronic files agrees that it will perform acceptance tests or procedures within 60 days, after which the receiving party shall be deemed to have accepted the data thus transferred. Any errors detected within the 60-day acceptance period will be corrected by the transferring party.
- C. When transferring documents in electronic media format, the transferring party makes no representations as to long term compatibility, usability, or readability of documents resulting from the use of software application packages, operating systems, or computer hardware differing from those used by the data's creator.

ARTICLE 4 – AVAILABILITY OF LANDS; SUBSURFACE AND PHYSICAL CONDITIONS; HAZARDOUS ENVIRONMENTAL CONDITIONS; REFERENCE POINTS

4.01 *Availability of Lands*

- A. Owner shall furnish the Site. Owner shall notify Contractor of any encumbrances or restrictions not of general application but specifically related to use of the Site with which Contractor must comply in performing the Work. Owner will obtain in a timely manner and pay for easements for permanent structures or permanent changes in existing facilities. If Contractor and Owner are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times, or both, as a result of any delay in Owner's furnishing the Site or a part thereof, Contractor may make a Claim therefor as provided in Paragraph 10.05.
- B. Upon reasonable written request, Owner shall furnish Contractor with a current statement of record legal title and legal description of the lands upon which the Work is to be performed and Owner's interest therein as necessary for giving notice of or filing a mechanic's or construction lien against such lands in accordance with applicable Laws and Regulations.
- C. Contractor shall provide for all additional lands and access thereto that may be required for temporary construction facilities or storage of materials and equipment.

4.02 *Subsurface and Physical Conditions*

- A. *Reports and Drawings:* The Supplementary Conditions identify:
 - 1. those reports known to Owner of explorations and tests of subsurface conditions at or contiguous to the Site; and
 - 2. those drawings known to Owner of physical conditions relating to existing surface or subsurface structures at the Site (except Underground Facilities).
- B. *Limited Reliance by Contractor on Technical Data Authorized:* Contractor may rely upon the accuracy of the "technical data" contained in such reports and drawings, but such reports and drawings are not Contract Documents. Such "technical data" is identified in the Supplementary Conditions. Except for such reliance on such "technical data," Contractor may not rely upon or make any claim against Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors with respect to:
 - 1. the completeness of such reports and drawings for Contractor's purposes, including, but not limited to, any aspects of the means, methods, techniques, sequences, and procedures of construction to be employed by Contractor, and safety precautions and programs incident thereto; or
 - 2. other data, interpretations, opinions, and information contained in such reports or shown or indicated in such drawings; or
 - 3. any Contractor interpretation of or conclusion drawn from any "technical data" or any such other data, interpretations, opinions, or information.

4.03 *Differing Subsurface or Physical Conditions*

- A. *Notice:* If Contractor believes that any subsurface or physical condition that is uncovered or revealed either:
1. is of such a nature as to establish that any “technical data” on which Contractor is entitled to rely as provided in Paragraph 4.02 is materially inaccurate; or
 2. is of such a nature as to require a change in the Contract Documents; or
 3. differs materially from that shown or indicated in the Contract Documents; or
 4. is of an unusual nature, and differs materially from conditions ordinarily encountered and generally recognized as inherent in work of the character provided for in the Contract Documents;

then Contractor shall, promptly after becoming aware thereof and before further disturbing the subsurface or physical conditions or performing any Work in connection therewith (except in an emergency as required by Paragraph 6.16.A), notify Owner and Engineer in writing about such condition. Contractor shall not further disturb such condition or perform any Work in connection therewith (except as aforesaid) until receipt of written order to do so.

- B. *Engineer’s Review:* After receipt of written notice as required by Paragraph 4.03.A, Engineer will promptly review the pertinent condition, determine the necessity of Owner’s obtaining additional exploration or tests with respect thereto, and advise Owner in writing (with a copy to Contractor) of Engineer’s findings and conclusions.

C. *Possible Price and Times Adjustments:*

1. The Contract Price or the Contract Times, or both, will be equitably adjusted to the extent that the existence of such differing subsurface or physical condition causes an increase or decrease in Contractor’s cost of, or time required for, performance of the Work; subject, however, to the following:
 - a. such condition must meet any one or more of the categories described in Paragraph 4.03.A; and
 - b. with respect to Work that is paid for on a unit price basis, any adjustment in Contract Price will be subject to the provisions of Paragraphs 9.07 and 11.03.
2. Contractor shall not be entitled to any adjustment in the Contract Price or Contract Times if:
 - a. Contractor knew of the existence of such conditions at the time Contractor made a final commitment to Owner with respect to Contract Price and Contract Times by the submission of a Bid or becoming bound under a negotiated contract; or
 - b. the existence of such condition could reasonably have been discovered or revealed as a result of any examination, investigation, exploration, test, or study of the Site and

contiguous areas required by the Bidding Requirements or Contract Documents to be conducted by or for Contractor prior to Contractor's making such final commitment; or

- c. Contractor failed to give the written notice as required by Paragraph 4.03.A.
3. If Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times, or both, a Claim may be made therefor as provided in Paragraph 10.05. However, neither Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors shall be liable to Contractor for any claims, costs, losses, or damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) sustained by Contractor on or in connection with any other project or anticipated project.

4.04 *Underground Facilities*

A. *Shown or Indicated:* The information and data shown or indicated in the Contract Documents with respect to existing Underground Facilities at or contiguous to the Site is based on information and data furnished to Owner or Engineer by the owners of such Underground Facilities, including Owner, or by others. Unless it is otherwise expressly provided in the Supplementary Conditions:

1. Owner and Engineer shall not be responsible for the accuracy or completeness of any such information or data provided by others; and
2. the cost of all of the following will be included in the Contract Price, and Contractor shall have full responsibility for:
 - a. reviewing and checking all such information and data;
 - b. locating all Underground Facilities shown or indicated in the Contract Documents;
 - c. coordination of the Work with the owners of such Underground Facilities, including Owner, during construction; and
 - d. the safety and protection of all such Underground Facilities and repairing any damage thereto resulting from the Work.

B. *Not Shown or Indicated:*

1. If an Underground Facility is uncovered or revealed at or contiguous to the Site which was not shown or indicated, or not shown or indicated with reasonable accuracy in the Contract Documents, Contractor shall, promptly after becoming aware thereof and before further disturbing conditions affected thereby or performing any Work in connection therewith (except in an emergency as required by Paragraph 6.16.A), identify the owner of such Underground Facility and give written notice to that owner and to Owner and Engineer. Engineer will promptly review the Underground Facility and determine the extent, if any, to which a change is required in the Contract Documents to reflect and document the

consequences of the existence or location of the Underground Facility. During such time, Contractor shall be responsible for the safety and protection of such Underground Facility.

2. If Engineer concludes that a change in the Contract Documents is required, a Work Change Directive or a Change Order will be issued to reflect and document such consequences. An equitable adjustment shall be made in the Contract Price or Contract Times, or both, to the extent that they are attributable to the existence or location of any Underground Facility that was not shown or indicated or not shown or indicated with reasonable accuracy in the Contract Documents and that Contractor did not know of and could not reasonably have been expected to be aware of or to have anticipated. If Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any such adjustment in Contract Price or Contract Times, Owner or Contractor may make a Claim therefor as provided in Paragraph 10.05.

4.05 *Reference Points*

- A. Owner shall provide engineering surveys to establish reference points for construction which in Engineer's judgment are necessary to enable Contractor to proceed with the Work. Contractor shall be responsible for laying out the Work, shall protect and preserve the established reference points and property monuments, and shall make no changes or relocations without the prior written approval of Owner. Contractor shall report to Engineer whenever any reference point or property monument is lost or destroyed or requires relocation because of necessary changes in grades or locations, and shall be responsible for the accurate replacement or relocation of such reference points or property monuments by professionally qualified personnel.

4.06 *Hazardous Environmental Condition at Site*

- A. *Reports and Drawings:* The Supplementary Conditions identify those reports and drawings known to Owner relating to Hazardous Environmental Conditions that have been identified at the Site.
- B. *Limited Reliance by Contractor on Technical Data Authorized:* Contractor may rely upon the accuracy of the "technical data" contained in such reports and drawings, but such reports and drawings are not Contract Documents. Such "technical data" is identified in the Supplementary Conditions. Except for such reliance on such "technical data," Contractor may not rely upon or make any claim against Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors with respect to:
 1. the completeness of such reports and drawings for Contractor's purposes, including, but not limited to, any aspects of the means, methods, techniques, sequences and procedures of construction to be employed by Contractor and safety precautions and programs incident thereto; or
 2. other data, interpretations, opinions and information contained in such reports or shown or indicated in such drawings; or
 3. any Contractor interpretation of or conclusion drawn from any "technical data" or any such other data, interpretations, opinions or information.

- C. Contractor shall not be responsible for any Hazardous Environmental Condition uncovered or revealed at the Site which was not shown or indicated in Drawings or Specifications or identified in the Contract Documents to be within the scope of the Work. Contractor shall be responsible for a Hazardous Environmental Condition created with any materials brought to the Site by Contractor, Subcontractors, Suppliers, or anyone else for whom Contractor is responsible.
- D. If Contractor encounters a Hazardous Environmental Condition or if Contractor or anyone for whom Contractor is responsible creates a Hazardous Environmental Condition, Contractor shall immediately: (i) secure or otherwise isolate such condition; (ii) stop all Work in connection with such condition and in any area affected thereby (except in an emergency as required by Paragraph 6.16.A); and (iii) notify Owner and Engineer (and promptly thereafter confirm such notice in writing). Owner shall promptly consult with Engineer concerning the necessity for Owner to retain a qualified expert to evaluate such condition or take corrective action, if any. Promptly after consulting with Engineer, Owner shall take such actions as are necessary to permit Owner to timely obtain required permits and provide Contractor the written notice required by Paragraph 4.06.E.
- E. Contractor shall not be required to resume Work in connection with such condition or in any affected area until after Owner has obtained any required permits related thereto and delivered written notice to Contractor: (i) specifying that such condition and any affected area is or has been rendered safe for the resumption of Work; or (ii) specifying any special conditions under which such Work may be resumed safely. If Owner and Contractor cannot agree as to entitlement to or on the amount or extent, if any, of any adjustment in Contract Price or Contract Times, or both, as a result of such Work stoppage or such special conditions under which Work is agreed to be resumed by Contractor, either party may make a Claim therefor as provided in Paragraph 10.05.
- F. If after receipt of such written notice Contractor does not agree to resume such Work based on a reasonable belief it is unsafe, or does not agree to resume such Work under such special conditions, then Owner may order the portion of the Work that is in the area affected by such condition to be deleted from the Work. If Owner and Contractor cannot agree as to entitlement to or on the amount or extent, if any, of an adjustment in Contract Price or Contract Times as a result of deleting such portion of the Work, then either party may make a Claim therefor as provided in Paragraph 10.05. Owner may have such deleted portion of the Work performed by Owner's own forces or others in accordance with Article 7.
- G. To the fullest extent permitted by Laws and Regulations, Owner shall indemnify and hold harmless Contractor, Subcontractors, and Engineer, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to a Hazardous Environmental Condition, provided that such Hazardous Environmental Condition: (i) was not shown or indicated in the Drawings or Specifications or identified in the Contract Documents to be included within the scope of the Work, and (ii) was not created by Contractor or by anyone for whom Contractor is responsible. Nothing in this Paragraph 4.06.G shall obligate Owner to indemnify any individual or entity from and against the consequences of that individual's or entity's own negligence.

- H. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to a Hazardous Environmental Condition created by Contractor or by anyone for whom Contractor is responsible. Nothing in this Paragraph 4.06.H shall obligate Contractor to indemnify any individual or entity from and against the consequences of that individual's or entity's own negligence.
- I. The provisions of Paragraphs 4.02, 4.03, and 4.04 do not apply to a Hazardous Environmental Condition uncovered or revealed at the Site.

ARTICLE 5 – BONDS AND INSURANCE

5.01 Performance, Payment, and Other Bonds

- A. Contractor shall furnish performance and payment bonds, each in an amount at least equal to the Contract Price as security for the faithful performance and payment of all of Contractor's obligations under the Contract Documents. These bonds shall remain in effect until one year after the date when final payment becomes due or until completion of the correction period specified in Paragraph 13.07, whichever is later, except as provided otherwise by Laws or Regulations or by the Contract Documents. Contractor shall also furnish such other bonds as are required by the Contract Documents.
- B. All bonds shall be in the form prescribed by the Contract Documents except as provided otherwise by Laws or Regulations, and shall be executed by such sureties as are named in the list of "Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies" as published in Circular 570 (amended) by the Financial Management Service, Surety Bond Branch, U.S. Department of the Treasury. All bonds signed by an agent or attorney-in-fact must be accompanied by a certified copy of that individual's authority to bind the surety. The evidence of authority shall show that it is effective on the date the agent or attorney-in-fact signed each bond.
- C. If the surety on any bond furnished by Contractor is declared bankrupt or becomes insolvent or its right to do business is terminated in any state where any part of the Project is located or it ceases to meet the requirements of Paragraph 5.01.B, Contractor shall promptly notify Owner and Engineer and shall, within 20 days after the event giving rise to such notification, provide another bond and surety, both of which shall comply with the requirements of Paragraphs 5.01.B and 5.02.

5.02 Licensed Sureties and Insurers

- A. All bonds and insurance required by the Contract Documents to be purchased and maintained by Owner or Contractor shall be obtained from surety or insurance companies that are duly licensed or authorized in the jurisdiction in which the Project is located to issue bonds or insurance policies for the limits and coverages so required. Such surety and insurance companies shall also

meet such additional requirements and qualifications as may be provided in the Supplementary Conditions.

5.03 *Certificates of Insurance*

- A. Contractor shall deliver to Owner, with copies to each additional insured and loss payee identified in the Supplementary Conditions, certificates of insurance (and other evidence of insurance requested by Owner or any other additional insured) which Contractor is required to purchase and maintain.
- B. Owner shall deliver to Contractor, with copies to each additional insured and loss payee identified in the Supplementary Conditions, certificates of insurance (and other evidence of insurance requested by Contractor or any other additional insured) which Owner is required to purchase and maintain.
- C. Failure of Owner to demand such certificates or other evidence of Contractor's full compliance with these insurance requirements or failure of Owner to identify a deficiency in compliance from the evidence provided shall not be construed as a waiver of Contractor's obligation to maintain such insurance.
- D. Owner does not represent that insurance coverage and limits established in this Contract necessarily will be adequate to protect Contractor.
- E. The insurance and insurance limits required herein shall not be deemed as a limitation on Contractor's liability under the indemnities granted to Owner in the Contract Documents.

5.04 *Contractor's Insurance*

- A. Contractor shall purchase and maintain such insurance as is appropriate for the Work being performed and as will provide protection from claims set forth below which may arise out of or result from Contractor's performance of the Work and Contractor's other obligations under the Contract Documents, whether it is to be performed by Contractor, any Subcontractor or Supplier, or by anyone directly or indirectly employed by any of them to perform any of the Work, or by anyone for whose acts any of them may be liable:
 - 1. claims under workers' compensation, disability benefits, and other similar employee benefit acts;
 - 2. claims for damages because of bodily injury, occupational sickness or disease, or death of Contractor's employees;
 - 3. claims for damages because of bodily injury, sickness or disease, or death of any person other than Contractor's employees;
 - 4. claims for damages insured by reasonably available personal injury liability coverage which are sustained:

- a. by any person as a result of an offense directly or indirectly related to the employment of such person by Contractor, or
 - b. by any other person for any other reason;
5. claims for damages, other than to the Work itself, because of injury to or destruction of tangible property wherever located, including loss of use resulting therefrom; and
 6. claims for damages because of bodily injury or death of any person or property damage arising out of the ownership, maintenance or use of any motor vehicle.
- B. The policies of insurance required by this Paragraph 5.04 shall:
1. with respect to insurance required by Paragraphs 5.04.A.3 through 5.04.A.6 inclusive, be written on an occurrence basis, include as additional insureds (subject to any customary exclusion regarding professional liability) Owner and Engineer, and any other individuals or entities identified in the Supplementary Conditions, all of whom shall be listed as additional insureds, and include coverage for the respective officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of all such additional insureds, and the insurance afforded to these additional insureds shall provide primary coverage for all claims covered thereby;
 2. include at least the specific coverages and be written for not less than the limits of liability provided in the Supplementary Conditions or required by Laws or Regulations, whichever is greater;
 3. include contractual liability insurance covering Contractor's indemnity obligations under Paragraphs 6.11 and 6.20;
 4. contain a provision or endorsement that the coverage afforded will not be canceled, materially changed or renewal refused until at least 30 days prior written notice has been given to Owner and Contractor and to each other additional insured identified in the Supplementary Conditions to whom a certificate of insurance has been issued (and the certificates of insurance furnished by the Contractor pursuant to Paragraph 5.03 will so provide);
 5. remain in effect at least until final payment and at all times thereafter when Contractor may be correcting, removing, or replacing defective Work in accordance with Paragraph 13.07; and
 6. include completed operations coverage:
 - a. Such insurance shall remain in effect for two years after final payment.
 - b. Contractor shall furnish Owner and each other additional insured identified in the Supplementary Conditions, to whom a certificate of insurance has been issued, evidence satisfactory to Owner and any such additional insured of continuation of such insurance at final payment and one year thereafter.

5.05 *Owner's Liability Insurance*

- A. In addition to the insurance required to be provided by Contractor under Paragraph 5.04, Owner, at Owner's option, may purchase and maintain at Owner's expense Owner's own liability insurance as will protect Owner against claims which may arise from operations under the Contract Documents.

5.06 *Property Insurance*

- A. Unless otherwise provided in the Supplementary Conditions, Owner shall purchase and maintain property insurance upon the Work at the Site in the amount of the full replacement cost thereof (subject to such deductible amounts as may be provided in the Supplementary Conditions or required by Laws and Regulations). This insurance shall:
1. include the interests of Owner, Contractor, Subcontractors, and Engineer, and any other individuals or entities identified in the Supplementary Conditions, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, each of whom is deemed to have an insurable interest and shall be listed as a loss payee;
 2. be written on a Builder's Risk "all-risk" policy form that shall at least include insurance for physical loss or damage to the Work, temporary buildings, falsework, and materials and equipment in transit, and shall insure against at least the following perils or causes of loss: fire, lightning, extended coverage, theft, vandalism and malicious mischief, earthquake, collapse, debris removal, demolition occasioned by enforcement of Laws and Regulations, water damage (other than that caused by flood), and such other perils or causes of loss as may be specifically required by the Supplementary Conditions.
 3. include expenses incurred in the repair or replacement of any insured property (including but not limited to fees and charges of engineers and architects);
 4. cover materials and equipment stored at the Site or at another location that was agreed to in writing by Owner prior to being incorporated in the Work, provided that such materials and equipment have been included in an Application for Payment recommended by Engineer;
 5. allow for partial utilization of the Work by Owner;
 6. include testing and startup; and
 7. be maintained in effect until final payment is made unless otherwise agreed to in writing by Owner, Contractor, and Engineer with 30 days written notice to each other loss payee to whom a certificate of insurance has been issued.
- B. Owner shall purchase and maintain such equipment breakdown insurance or additional property insurance as may be required by the Supplementary Conditions or Laws and Regulations which will include the interests of Owner, Contractor, Subcontractors, and Engineer, and any other individuals or entities identified in the Supplementary Conditions, and the officers, directors,

members, partners, employees, agents, consultants and subcontractors of each and any of them, each of whom is deemed to have an insurable interest and shall be listed as a loss payee.

- C. All the policies of insurance (and the certificates or other evidence thereof) required to be purchased and maintained in accordance with this Paragraph 5.06 will contain a provision or endorsement that the coverage afforded will not be canceled or materially changed or renewal refused until at least 30 days prior written notice has been given to Owner and Contractor and to each other loss payee to whom a certificate of insurance has been issued and will contain waiver provisions in accordance with Paragraph 5.07.
- D. Owner shall not be responsible for purchasing and maintaining any property insurance specified in this Paragraph 5.06 to protect the interests of Contractor, Subcontractors, or others in the Work to the extent of any deductible amounts that are identified in the Supplementary Conditions. The risk of loss within such identified deductible amount will be borne by Contractor, Subcontractors, or others suffering any such loss, and if any of them wishes property insurance coverage within the limits of such amounts, each may purchase and maintain it at the purchaser's own expense.
- E. If Contractor requests in writing that other special insurance be included in the property insurance policies provided under this Paragraph 5.06, Owner shall, if possible, include such insurance, and the cost thereof will be charged to Contractor by appropriate Change Order. Prior to commencement of the Work at the Site, Owner shall in writing advise Contractor whether or not such other insurance has been procured by Owner.

5.07 *Waiver of Rights*

- A. Owner and Contractor intend that all policies purchased in accordance with Paragraph 5.06 will protect Owner, Contractor, Subcontractors, and Engineer, and all other individuals or entities identified in the Supplementary Conditions as loss payees (and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them) in such policies and will provide primary coverage for all losses and damages caused by the perils or causes of loss covered thereby. All such policies shall contain provisions to the effect that in the event of payment of any loss or damage the insurers will have no rights of recovery against any of the insureds or loss payees thereunder. Owner and Contractor waive all rights against each other and their respective officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them for all losses and damages caused by, arising out of or resulting from any of the perils or causes of loss covered by such policies and any other property insurance applicable to the Work; and, in addition, waive all such rights against Subcontractors and Engineer, and all other individuals or entities identified in the Supplementary Conditions as loss payees (and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them) under such policies for losses and damages so caused. None of the above waivers shall extend to the rights that any party making such waiver may have to the proceeds of insurance held by Owner as trustee or otherwise payable under any policy so issued.
- B. Owner waives all rights against Contractor, Subcontractors, and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them for:

1. loss due to business interruption, loss of use, or other consequential loss extending beyond direct physical loss or damage to Owner's property or the Work caused by, arising out of, or resulting from fire or other perils whether or not insured by Owner; and
 2. loss or damage to the completed Project or part thereof caused by, arising out of, or resulting from fire or other insured peril or cause of loss covered by any property insurance maintained on the completed Project or part thereof by Owner during partial utilization pursuant to Paragraph 14.05, after Substantial Completion pursuant to Paragraph 14.04, or after final payment pursuant to Paragraph 14.07.
- C. Any insurance policy maintained by Owner covering any loss, damage or consequential loss referred to in Paragraph 5.07.B shall contain provisions to the effect that in the event of payment of any such loss, damage, or consequential loss, the insurers will have no rights of recovery against Contractor, Subcontractors, or Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them.

5.08 *Receipt and Application of Insurance Proceeds*

- A. Any insured loss under the policies of insurance required by Paragraph 5.06 will be adjusted with Owner and made payable to Owner as fiduciary for the loss payees, as their interests may appear, subject to the requirements of any applicable mortgage clause and of Paragraph 5.08.B. Owner shall deposit in a separate account any money so received and shall distribute it in accordance with such agreement as the parties in interest may reach. If no other special agreement is reached, the damaged Work shall be repaired or replaced, the moneys so received applied on account thereof, and the Work and the cost thereof covered by an appropriate Change Order.
- B. Owner as fiduciary shall have power to adjust and settle any loss with the insurers unless one of the parties in interest shall object in writing within 15 days after the occurrence of loss to Owner's exercise of this power. If such objection be made, Owner as fiduciary shall make settlement with the insurers in accordance with such agreement as the parties in interest may reach. If no such agreement among the parties in interest is reached, Owner as fiduciary shall adjust and settle the loss with the insurers and, if required in writing by any party in interest, Owner as fiduciary shall give bond for the proper performance of such duties.

5.09 *Acceptance of Bonds and Insurance; Option to Replace*

- A. If either Owner or Contractor has any objection to the coverage afforded by or other provisions of the bonds or insurance required to be purchased and maintained by the other party in accordance with Article 5 on the basis of non-conformance with the Contract Documents, the objecting party shall so notify the other party in writing within 10 days after receipt of the certificates (or other evidence requested) required by Paragraph 2.01.B. Owner and Contractor shall each provide to the other such additional information in respect of insurance provided as the other may reasonably request. If either party does not purchase or maintain all of the bonds and insurance required of such party by the Contract Documents, such party shall notify the other party in writing of such failure to purchase prior to the start of the Work, or of such failure to maintain prior to any change in the required coverage. Without prejudice to any other right or remedy, the other party may elect to obtain equivalent bonds or insurance to protect such other party's

interests at the expense of the party who was required to provide such coverage, and a Change Order shall be issued to adjust the Contract Price accordingly.

5.10 *Partial Utilization, Acknowledgment of Property Insurer*

- A. If Owner finds it necessary to occupy or use a portion or portions of the Work prior to Substantial Completion of all the Work as provided in Paragraph 14.05, no such use or occupancy shall commence before the insurers providing the property insurance pursuant to Paragraph 5.06 have acknowledged notice thereof and in writing effected any changes in coverage necessitated thereby. The insurers providing the property insurance shall consent by endorsement on the policy or policies, but the property insurance shall not be canceled or permitted to lapse on account of any such partial use or occupancy.

ARTICLE 6 – CONTRACTOR’S RESPONSIBILITIES

6.01 *Supervision and Superintendence*

- A. Contractor shall supervise, inspect, and direct the Work competently and efficiently, devoting such attention thereto and applying such skills and expertise as may be necessary to perform the Work in accordance with the Contract Documents. Contractor shall be solely responsible for the means, methods, techniques, sequences, and procedures of construction. Contractor shall not be responsible for the negligence of Owner or Engineer in the design or specification of a specific means, method, technique, sequence, or procedure of construction which is shown or indicated in and expressly required by the Contract Documents.
- B. At all times during the progress of the Work, Contractor shall assign a competent resident superintendent who shall not be replaced without written notice to Owner and Engineer except under extraordinary circumstances.

6.02 *Labor; Working Hours*

- A. Contractor shall provide competent, suitably qualified personnel to survey and lay out the Work and perform construction as required by the Contract Documents. Contractor shall at all times maintain good discipline and order at the Site.
- B. Except as otherwise required for the safety or protection of persons or the Work or property at the Site or adjacent thereto, and except as otherwise stated in the Contract Documents, all Work at the Site shall be performed during regular working hours. Contractor will not permit the performance of Work on a Saturday, Sunday, or any legal holiday without Owner’s written consent (which will not be unreasonably withheld) given after prior written notice to Engineer.

6.03 *Services, Materials, and Equipment*

- A. Unless otherwise specified in the Contract Documents, Contractor shall provide and assume full responsibility for all services, materials, equipment, labor, transportation, construction equipment and machinery, tools, appliances, fuel, power, light, heat, telephone, water, sanitary facilities, temporary facilities, and all other facilities and incidentals necessary for the performance, testing, start-up, and completion of the Work.

- B. All materials and equipment incorporated into the Work shall be as specified or, if not specified, shall be of good quality and new, except as otherwise provided in the Contract Documents. All special warranties and guarantees required by the Specifications shall expressly run to the benefit of Owner. If required by Engineer, Contractor shall furnish satisfactory evidence (including reports of required tests) as to the source, kind, and quality of materials and equipment.
- C. All materials and equipment shall be stored, applied, installed, connected, erected, protected, used, cleaned, and conditioned in accordance with instructions of the applicable Supplier, except as otherwise may be provided in the Contract Documents.

6.04 *Progress Schedule*

- A. Contractor shall adhere to the Progress Schedule established in accordance with Paragraph 2.07 as it may be adjusted from time to time as provided below.
 - 1. Contractor shall submit to Engineer for acceptance (to the extent indicated in Paragraph 2.07) proposed adjustments in the Progress Schedule that will not result in changing the Contract Times. Such adjustments will comply with any provisions of the General Requirements applicable thereto.
 - 2. Proposed adjustments in the Progress Schedule that will change the Contract Times shall be submitted in accordance with the requirements of Article 12. Adjustments in Contract Times may only be made by a Change Order.

6.05 *Substitutes and "Or-Equals"*

- A. Whenever an item of material or equipment is specified or described in the Contract Documents by using the name of a proprietary item or the name of a particular Supplier, the specification or description is intended to establish the type, function, appearance, and quality required. Unless the specification or description contains or is followed by words reading that no like, equivalent, or "or-equal" item or no substitution is permitted, other items of material or equipment or material or equipment of other Suppliers may be submitted to Engineer for review under the circumstances described below.
 - 1. "*Or-Equal*" Items: If in Engineer's sole discretion an item of material or equipment proposed by Contractor is functionally equal to that named and sufficiently similar so that no change in related Work will be required, it may be considered by Engineer as an "or-equal" item, in which case review and approval of the proposed item may, in Engineer's sole discretion, be accomplished without compliance with some or all of the requirements for approval of proposed substitute items. For the purposes of this Paragraph 6.05.A.1, a proposed item of material or equipment will be considered functionally equal to an item so named if:
 - a. in the exercise of reasonable judgment Engineer determines that:
 - 1) it is at least equal in materials of construction, quality, durability, appearance, strength, and design characteristics;

- 2) it will reliably perform at least equally well the function and achieve the results imposed by the design concept of the completed Project as a functioning whole; and
 - 3) it has a proven record of performance and availability of responsive service.
- b. Contractor certifies that, if approved and incorporated into the Work:
- 1) there will be no increase in cost to the Owner or increase in Contract Times; and
 - 2) it will conform substantially to the detailed requirements of the item named in the Contract Documents.

2. *Substitute Items:*

- a. If in Engineer's sole discretion an item of material or equipment proposed by Contractor does not qualify as an "or-equal" item under Paragraph 6.05.A.1, it will be considered a proposed substitute item.
- b. Contractor shall submit sufficient information as provided below to allow Engineer to determine if the item of material or equipment proposed is essentially equivalent to that named and an acceptable substitute therefor. Requests for review of proposed substitute items of material or equipment will not be accepted by Engineer from anyone other than Contractor.
- c. The requirements for review by Engineer will be as set forth in Paragraph 6.05.A.2.d, as supplemented by the General Requirements, and as Engineer may decide is appropriate under the circumstances.
- d. Contractor shall make written application to Engineer for review of a proposed substitute item of material or equipment that Contractor seeks to furnish or use. The application:
 - 1) shall certify that the proposed substitute item will:
 - a) perform adequately the functions and achieve the results called for by the general design,
 - b) be similar in substance to that specified, and
 - c) be suited to the same use as that specified;
 - 2) will state:
 - a) the extent, if any, to which the use of the proposed substitute item will prejudice Contractor's achievement of Substantial Completion on time,
 - b) whether use of the proposed substitute item in the Work will require a change in any of the Contract Documents (or in the provisions of any other direct contract with Owner for other work on the Project) to adapt the design to the proposed substitute item, and

- c) whether incorporation or use of the proposed substitute item in connection with the Work is subject to payment of any license fee or royalty;
 - 3) will identify:
 - a) all variations of the proposed substitute item from that specified, and
 - b) available engineering, sales, maintenance, repair, and replacement services; and
 - 4) shall contain an itemized estimate of all costs or credits that will result directly or indirectly from use of such substitute item, including costs of redesign and claims of other contractors affected by any resulting change.
- B. *Substitute Construction Methods or Procedures:* If a specific means, method, technique, sequence, or procedure of construction is expressly required by the Contract Documents, Contractor may furnish or utilize a substitute means, method, technique, sequence, or procedure of construction approved by Engineer. Contractor shall submit sufficient information to allow Engineer, in Engineer's sole discretion, to determine that the substitute proposed is equivalent to that expressly called for by the Contract Documents. The requirements for review by Engineer will be similar to those provided in Paragraph 6.05.A.2.
- C. *Engineer's Evaluation:* Engineer will be allowed a reasonable time within which to evaluate each proposal or submittal made pursuant to Paragraphs 6.05.A and 6.05.B. Engineer may require Contractor to furnish additional data about the proposed substitute item. Engineer will be the sole judge of acceptability. No "or equal" or substitute will be ordered, installed or utilized until Engineer's review is complete, which will be evidenced by a Change Order in the case of a substitute and an approved Shop Drawing for an "or equal." Engineer will advise Contractor in writing of any negative determination.
- D. *Special Guarantee:* Owner may require Contractor to furnish at Contractor's expense a special performance guarantee or other surety with respect to any substitute.
- E. *Engineer's Cost Reimbursement:* Engineer will record Engineer's costs in evaluating a substitute proposed or submitted by Contractor pursuant to Paragraphs 6.05.A.2 and 6.05.B. Whether or not Engineer approves a substitute so proposed or submitted by Contractor, Contractor shall reimburse Owner for the reasonable charges of Engineer for evaluating each such proposed substitute. Contractor shall also reimburse Owner for the reasonable charges of Engineer for making changes in the Contract Documents (or in the provisions of any other direct contract with Owner) resulting from the acceptance of each proposed substitute.
- F. *Contractor's Expense:* Contractor shall provide all data in support of any proposed substitute or "or-equal" at Contractor's expense.

6.06 *Concerning Subcontractors, Suppliers, and Others*

- A. Contractor shall not employ any Subcontractor, Supplier, or other individual or entity (including those acceptable to Owner as indicated in Paragraph 6.06.B), whether initially or as a replacement, against whom Owner may have reasonable objection. Contractor shall not be

required to employ any Subcontractor, Supplier, or other individual or entity to furnish or perform any of the Work against whom Contractor has reasonable objection.

- B. If the Supplementary Conditions require the identity of certain Subcontractors, Suppliers, or other individuals or entities to be submitted to Owner in advance for acceptance by Owner by a specified date prior to the Effective Date of the Agreement, and if Contractor has submitted a list thereof in accordance with the Supplementary Conditions, Owner's acceptance (either in writing or by failing to make written objection thereto by the date indicated for acceptance or objection in the Bidding Documents or the Contract Documents) of any such Subcontractor, Supplier, or other individual or entity so identified may be revoked on the basis of reasonable objection after due investigation. Contractor shall submit an acceptable replacement for the rejected Subcontractor, Supplier, or other individual or entity, and the Contract Price will be adjusted by the difference in the cost occasioned by such replacement, and an appropriate Change Order will be issued. No acceptance by Owner of any such Subcontractor, Supplier, or other individual or entity, whether initially or as a replacement, shall constitute a waiver of any right of Owner or Engineer to reject defective Work.
- C. Contractor shall be fully responsible to Owner and Engineer for all acts and omissions of the Subcontractors, Suppliers, and other individuals or entities performing or furnishing any of the Work just as Contractor is responsible for Contractor's own acts and omissions. Nothing in the Contract Documents:
1. shall create for the benefit of any such Subcontractor, Supplier, or other individual or entity any contractual relationship between Owner or Engineer and any such Subcontractor, Supplier or other individual or entity; nor
 2. shall create any obligation on the part of Owner or Engineer to pay or to see to the payment of any moneys due any such Subcontractor, Supplier, or other individual or entity except as may otherwise be required by Laws and Regulations.
- D. Contractor shall be solely responsible for scheduling and coordinating the Work of Subcontractors, Suppliers, and other individuals or entities performing or furnishing any of the Work under a direct or indirect contract with Contractor.
- E. Contractor shall require all Subcontractors, Suppliers, and such other individuals or entities performing or furnishing any of the Work to communicate with Engineer through Contractor.
- F. The divisions and sections of the Specifications and the identifications of any Drawings shall not control Contractor in dividing the Work among Subcontractors or Suppliers or delineating the Work to be performed by any specific trade.
- G. All Work performed for Contractor by a Subcontractor or Supplier will be pursuant to an appropriate agreement between Contractor and the Subcontractor or Supplier which specifically binds the Subcontractor or Supplier to the applicable terms and conditions of the Contract Documents for the benefit of Owner and Engineer. Whenever any such agreement is with a Subcontractor or Supplier who is listed as a loss payee on the property insurance provided in Paragraph 5.06, the agreement between the Contractor and the Subcontractor or Supplier will contain provisions whereby the Subcontractor or Supplier waives all rights against Owner,

Contractor, Engineer, and all other individuals or entities identified in the Supplementary Conditions to be listed as insureds or loss payees (and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them) for all losses and damages caused by, arising out of, relating to, or resulting from any of the perils or causes of loss covered by such policies and any other property insurance applicable to the Work. If the insurers on any such policies require separate waiver forms to be signed by any Subcontractor or Supplier, Contractor will obtain the same.

6.07 *Patent Fees and Royalties*

- A. Contractor shall pay all license fees and royalties and assume all costs incident to the use in the performance of the Work or the incorporation in the Work of any invention, design, process, product, or device which is the subject of patent rights or copyrights held by others. If a particular invention, design, process, product, or device is specified in the Contract Documents for use in the performance of the Work and if, to the actual knowledge of Owner or Engineer, its use is subject to patent rights or copyrights calling for the payment of any license fee or royalty to others, the existence of such rights shall be disclosed by Owner in the Contract Documents.
- B. To the fullest extent permitted by Laws and Regulations, Owner shall indemnify and hold harmless Contractor, and its officers, directors, members, partners, employees, agents, consultants, and subcontractors from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals, and all court or arbitration or other dispute resolution costs) arising out of or relating to any infringement of patent rights or copyrights incident to the use in the performance of the Work or resulting from the incorporation in the Work of any invention, design, process, product, or device specified in the Contract Documents, but not identified as being subject to payment of any license fee or royalty to others required by patent rights or copyrights.
- C. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to any infringement of patent rights or copyrights incident to the use in the performance of the Work or resulting from the incorporation in the Work of any invention, design, process, product, or device not specified in the Contract Documents.

6.08 *Permits*

- A. Unless otherwise provided in the Supplementary Conditions, Contractor shall obtain and pay for all construction permits and licenses. Owner shall assist Contractor, when necessary, in obtaining such permits and licenses. Contractor shall pay all governmental charges and inspection fees necessary for the prosecution of the Work which are applicable at the time of opening of Bids, or, if there are no Bids, on the Effective Date of the Agreement. Owner shall pay all charges of utility owners for connections for providing permanent service to the Work.

6.09 *Laws and Regulations*

- A. Contractor shall give all notices required by and shall comply with all Laws and Regulations applicable to the performance of the Work. Except where otherwise expressly required by applicable Laws and Regulations, neither Owner nor Engineer shall be responsible for monitoring Contractor's compliance with any Laws or Regulations.
- B. If Contractor performs any Work knowing or having reason to know that it is contrary to Laws or Regulations, Contractor shall bear all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such Work. However, it shall not be Contractor's responsibility to make certain that the Specifications and Drawings are in accordance with Laws and Regulations, but this shall not relieve Contractor of Contractor's obligations under Paragraph 3.03.
- C. Changes in Laws or Regulations not known at the time of opening of Bids (or, on the Effective Date of the Agreement if there were no Bids) having an effect on the cost or time of performance of the Work shall be the subject of an adjustment in Contract Price or Contract Times. If Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any such adjustment, a Claim may be made therefor as provided in Paragraph 10.05.

6.10 *Taxes*

- A. Contractor shall pay all sales, consumer, use, and other similar taxes required to be paid by Contractor in accordance with the Laws and Regulations of the place of the Project which are applicable during the performance of the Work.

6.11 *Use of Site and Other Areas*

A. *Limitation on Use of Site and Other Areas:*

1. Contractor shall confine construction equipment, the storage of materials and equipment, and the operations of workers to the Site and other areas permitted by Laws and Regulations, and shall not unreasonably encumber the Site and other areas with construction equipment or other materials or equipment. Contractor shall assume full responsibility for any damage to any such land or area, or to the owner or occupant thereof, or of any adjacent land or areas resulting from the performance of the Work.
2. Should any claim be made by any such owner or occupant because of the performance of the Work, Contractor shall promptly settle with such other party by negotiation or otherwise resolve the claim by arbitration or other dispute resolution proceeding or at law.
3. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to any claim or action, legal or equitable, brought

by any such owner or occupant against Owner, Engineer, or any other party indemnified hereunder to the extent caused by or based upon Contractor's performance of the Work.

- B. *Removal of Debris During Performance of the Work:* During the progress of the Work Contractor shall keep the Site and other areas free from accumulations of waste materials, rubbish, and other debris. Removal and disposal of such waste materials, rubbish, and other debris shall conform to applicable Laws and Regulations.
- C. *Cleaning:* Prior to Substantial Completion of the Work Contractor shall clean the Site and the Work and make it ready for utilization by Owner. At the completion of the Work Contractor shall remove from the Site all tools, appliances, construction equipment and machinery, and surplus materials and shall restore to original condition all property not designated for alteration by the Contract Documents.
- D. *Loading Structures:* Contractor shall not load nor permit any part of any structure to be loaded in any manner that will endanger the structure, nor shall Contractor subject any part of the Work or adjacent property to stresses or pressures that will endanger it.

6.12 *Record Documents*

- A. Contractor shall maintain in a safe place at the Site one record copy of all Drawings, Specifications, Addenda, Change Orders, Work Change Directives, Field Orders, and written interpretations and clarifications in good order and annotated to show changes made during construction. These record documents together with all approved Samples and a counterpart of all approved Shop Drawings will be available to Engineer for reference. Upon completion of the Work, these record documents, Samples, and Shop Drawings will be delivered to Engineer for Owner.

6.13 *Safety and Protection*

- A. Contractor shall be solely responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the Work. Such responsibility does not relieve Subcontractors of their responsibility for the safety of persons or property in the performance of their work, nor for compliance with applicable safety Laws and Regulations. Contractor shall take all necessary precautions for the safety of, and shall provide the necessary protection to prevent damage, injury or loss to:
 - 1. all persons on the Site or who may be affected by the Work;
 - 2. all the Work and materials and equipment to be incorporated therein, whether in storage on or off the Site; and
 - 3. other property at the Site or adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures, utilities, and Underground Facilities not designated for removal, relocation, or replacement in the course of construction.
- B. Contractor shall comply with all applicable Laws and Regulations relating to the safety of persons or property, or to the protection of persons or property from damage, injury, or loss; and

shall erect and maintain all necessary safeguards for such safety and protection. Contractor shall notify owners of adjacent property and of Underground Facilities and other utility owners when prosecution of the Work may affect them, and shall cooperate with them in the protection, removal, relocation, and replacement of their property.

- C. Contractor shall comply with the applicable requirements of Owner's safety programs, if any. The Supplementary Conditions identify any Owner's safety programs that are applicable to the Work.
- D. Contractor shall inform Owner and Engineer of the specific requirements of Contractor's safety program with which Owner's and Engineer's employees and representatives must comply while at the Site.
- E. All damage, injury, or loss to any property referred to in Paragraph 6.13.A.2 or 6.13.A.3 caused, directly or indirectly, in whole or in part, by Contractor, any Subcontractor, Supplier, or any other individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable, shall be remedied by Contractor (except damage or loss attributable to the fault of Drawings or Specifications or to the acts or omissions of Owner or Engineer or anyone employed by any of them, or anyone for whose acts any of them may be liable, and not attributable, directly or indirectly, in whole or in part, to the fault or negligence of Contractor or any Subcontractor, Supplier, or other individual or entity directly or indirectly employed by any of them).
- F. Contractor's duties and responsibilities for safety and for protection of the Work shall continue until such time as all the Work is completed and Engineer has issued a notice to Owner and Contractor in accordance with Paragraph 14.07.B that the Work is acceptable (except as otherwise expressly provided in connection with Substantial Completion).

6.14 *Safety Representative*

- A. Contractor shall designate a qualified and experienced safety representative at the Site whose duties and responsibilities shall be the prevention of accidents and the maintaining and supervising of safety precautions and programs.

6.15 *Hazard Communication Programs*

- A. Contractor shall be responsible for coordinating any exchange of material safety data sheets or other hazard communication information required to be made available to or exchanged between or among employers at the Site in accordance with Laws or Regulations.

6.16 *Emergencies*

- A. In emergencies affecting the safety or protection of persons or the Work or property at the Site or adjacent thereto, Contractor is obligated to act to prevent threatened damage, injury, or loss. Contractor shall give Engineer prompt written notice if Contractor believes that any significant changes in the Work or variations from the Contract Documents have been caused thereby or are required as a result thereof. If Engineer determines that a change in the Contract Documents is

required because of the action taken by Contractor in response to such an emergency, a Work Change Directive or Change Order will be issued.

6.17 *Shop Drawings and Samples*

A. Contractor shall submit Shop Drawings and Samples to Engineer for review and approval in accordance with the accepted Schedule of Submittals (as required by Paragraph 2.07). Each submittal will be identified as Engineer may require.

1. *Shop Drawings:*

- a. Submit number of copies specified in the General Requirements.
- b. Data shown on the Shop Drawings will be complete with respect to quantities, dimensions, specified performance and design criteria, materials, and similar data to show Engineer the services, materials, and equipment Contractor proposes to provide and to enable Engineer to review the information for the limited purposes required by Paragraph 6.17.D.

2. *Samples:*

- a. Submit number of Samples specified in the Specifications.
- b. Clearly identify each Sample as to material, Supplier, pertinent data such as catalog numbers, the use for which intended and other data as Engineer may require to enable Engineer to review the submittal for the limited purposes required by Paragraph 6.17.D.

B. Where a Shop Drawing or Sample is required by the Contract Documents or the Schedule of Submittals, any related Work performed prior to Engineer's review and approval of the pertinent submittal will be at the sole expense and responsibility of Contractor.

C. *Submittal Procedures:*

1. Before submitting each Shop Drawing or Sample, Contractor shall have:

- a. reviewed and coordinated each Shop Drawing or Sample with other Shop Drawings and Samples and with the requirements of the Work and the Contract Documents;
- b. determined and verified all field measurements, quantities, dimensions, specified performance and design criteria, installation requirements, materials, catalog numbers, and similar information with respect thereto;
- c. determined and verified the suitability of all materials offered with respect to the indicated application, fabrication, shipping, handling, storage, assembly, and installation pertaining to the performance of the Work; and
- d. determined and verified all information relative to Contractor's responsibilities for means, methods, techniques, sequences, and procedures of construction, and safety precautions and programs incident thereto.

2. Each submittal shall bear a stamp or specific written certification that Contractor has satisfied Contractor's obligations under the Contract Documents with respect to Contractor's review and approval of that submittal.
3. With each submittal, Contractor shall give Engineer specific written notice of any variations that the Shop Drawing or Sample may have from the requirements of the Contract Documents. This notice shall be both a written communication separate from the Shop Drawings or Sample submittal; and, in addition, by a specific notation made on each Shop Drawing or Sample submitted to Engineer for review and approval of each such variation.

D. *Engineer's Review:*

1. Engineer will provide timely review of Shop Drawings and Samples in accordance with the Schedule of Submittals acceptable to Engineer. Engineer's review and approval will be only to determine if the items covered by the submittals will, after installation or incorporation in the Work, conform to the information given in the Contract Documents and be compatible with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents.
2. Engineer's review and approval will not extend to means, methods, techniques, sequences, or procedures of construction (except where a particular means, method, technique, sequence, or procedure of construction is specifically and expressly called for by the Contract Documents) or to safety precautions or programs incident thereto. The review and approval of a separate item as such will not indicate approval of the assembly in which the item functions.
3. Engineer's review and approval shall not relieve Contractor from responsibility for any variation from the requirements of the Contract Documents unless Contractor has complied with the requirements of Paragraph 6.17.C.3 and Engineer has given written approval of each such variation by specific written notation thereof incorporated in or accompanying the Shop Drawing or Sample. Engineer's review and approval shall not relieve Contractor from responsibility for complying with the requirements of Paragraph 6.17.C.1.

E. *Resubmittal Procedures:*

1. Contractor shall make corrections required by Engineer and shall return the required number of corrected copies of Shop Drawings and submit, as required, new Samples for review and approval. Contractor shall direct specific attention in writing to revisions other than the corrections called for by Engineer on previous submittals.

6.18 *Continuing the Work*

- A. Contractor shall carry on the Work and adhere to the Progress Schedule during all disputes or disagreements with Owner. No Work shall be delayed or postponed pending resolution of any disputes or disagreements, except as permitted by Paragraph 15.04 or as Owner and Contractor may otherwise agree in writing.

6.19 *Contractor's General Warranty and Guarantee*

- A. Contractor warrants and guarantees to Owner that all Work will be in accordance with the Contract Documents and will not be defective. Engineer and its officers, directors, members, partners, employees, agents, consultants, and subcontractors shall be entitled to rely on representation of Contractor's warranty and guarantee.
- B. Contractor's warranty and guarantee hereunder excludes defects or damage caused by:
 - 1. abuse, modification, or improper maintenance or operation by persons other than Contractor, Subcontractors, Suppliers, or any other individual or entity for whom Contractor is responsible; or
 - 2. normal wear and tear under normal usage.
- C. Contractor's obligation to perform and complete the Work in accordance with the Contract Documents shall be absolute. None of the following will constitute an acceptance of Work that is not in accordance with the Contract Documents or a release of Contractor's obligation to perform the Work in accordance with the Contract Documents:
 - 1. observations by Engineer;
 - 2. recommendation by Engineer or payment by Owner of any progress or final payment;
 - 3. the issuance of a certificate of Substantial Completion by Engineer or any payment related thereto by Owner;
 - 4. use or occupancy of the Work or any part thereof by Owner;
 - 5. any review and approval of a Shop Drawing or Sample submittal or the issuance of a notice of acceptability by Engineer;
 - 6. any inspection, test, or approval by others; or
 - 7. any correction of defective Work by Owner.

6.20 *Indemnification*

- A. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to the performance of the Work, provided that any such claim, cost, loss, or damage is attributable to bodily injury, sickness, disease, or death, or to injury to or destruction of tangible property (other than the Work itself), including the loss of use resulting therefrom but only to the extent caused by any negligent act or omission of Contractor, any Subcontractor, any Supplier, or any individual or entity directly or indirectly employed by any of them to perform any of the Work or anyone for whose acts any of them may be liable .

- B. In any and all claims against Owner or Engineer or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors by any employee (or the survivor or personal representative of such employee) of Contractor, any Subcontractor, any Supplier, or any individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable, the indemnification obligation under Paragraph 6.20.A shall not be limited in any way by any limitation on the amount or type of damages, compensation, or benefits payable by or for Contractor or any such Subcontractor, Supplier, or other individual or entity under workers' compensation acts, disability benefit acts, or other employee benefit acts.
- C. The indemnification obligations of Contractor under Paragraph 6.20.A shall not extend to the liability of Engineer and Engineer's officers, directors, members, partners, employees, agents, consultants and subcontractors arising out of:
 - 1. the preparation or approval of, or the failure to prepare or approve maps, Drawings, opinions, reports, surveys, Change Orders, designs, or Specifications; or
 - 2. giving directions or instructions, or failing to give them, if that is the primary cause of the injury or damage.

6.21 *Delegation of Professional Design Services*

- A. Contractor will not be required to provide professional design services unless such services are specifically required by the Contract Documents for a portion of the Work or unless such services are required to carry out Contractor's responsibilities for construction means, methods, techniques, sequences and procedures. Contractor shall not be required to provide professional services in violation of applicable law.
- B. If professional design services or certifications by a design professional related to systems, materials or equipment are specifically required of Contractor by the Contract Documents, Owner and Engineer will specify all performance and design criteria that such services must satisfy. Contractor shall cause such services or certifications to be provided by a properly licensed professional, whose signature and seal shall appear on all drawings, calculations, specifications, certifications, Shop Drawings and other submittals prepared by such professional. Shop Drawings and other submittals related to the Work designed or certified by such professional, if prepared by others, shall bear such professional's written approval when submitted to Engineer.
- C. Owner and Engineer shall be entitled to rely upon the adequacy, accuracy and completeness of the services, certifications or approvals performed by such design professionals, provided Owner and Engineer have specified to Contractor all performance and design criteria that such services must satisfy.
- D. Pursuant to this Paragraph 6.21, Engineer's review and approval of design calculations and design drawings will be only for the limited purpose of checking for conformance with performance and design criteria given and the design concept expressed in the Contract Documents. Engineer's review and approval of Shop Drawings and other submittals (except design calculations and design drawings) will be only for the purpose stated in Paragraph 6.17.D.1.

- E. Contractor shall not be responsible for the adequacy of the performance or design criteria required by the Contract Documents.

ARTICLE 7 – OTHER WORK AT THE SITE

7.01 Related Work at Site

- A. Owner may perform other work related to the Project at the Site with Owner’s employees, or through other direct contracts therefor, or have other work performed by utility owners. If such other work is not noted in the Contract Documents, then:
 - 1. written notice thereof will be given to Contractor prior to starting any such other work; and
 - 2. if Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times that should be allowed as a result of such other work, a Claim may be made therefor as provided in Paragraph 10.05.
- B. Contractor shall afford each other contractor who is a party to such a direct contract, each utility owner, and Owner, if Owner is performing other work with Owner’s employees, proper and safe access to the Site, provide a reasonable opportunity for the introduction and storage of materials and equipment and the execution of such other work, and properly coordinate the Work with theirs. Contractor shall do all cutting, fitting, and patching of the Work that may be required to properly connect or otherwise make its several parts come together and properly integrate with such other work. Contractor shall not endanger any work of others by cutting, excavating, or otherwise altering such work; provided, however, that Contractor may cut or alter others' work with the written consent of Engineer and the others whose work will be affected. The duties and responsibilities of Contractor under this Paragraph are for the benefit of such utility owners and other contractors to the extent that there are comparable provisions for the benefit of Contractor in said direct contracts between Owner and such utility owners and other contractors.
- C. If the proper execution or results of any part of Contractor’s Work depends upon work performed by others under this Article 7, Contractor shall inspect such other work and promptly report to Engineer in writing any delays, defects, or deficiencies in such other work that render it unavailable or unsuitable for the proper execution and results of Contractor’s Work. Contractor’s failure to so report will constitute an acceptance of such other work as fit and proper for integration with Contractor’s Work except for latent defects and deficiencies in such other work.

7.02 Coordination

- A. If Owner intends to contract with others for the performance of other work on the Project at the Site, the following will be set forth in Supplementary Conditions:
 - 1. the individual or entity who will have authority and responsibility for coordination of the activities among the various contractors will be identified;
 - 2. the specific matters to be covered by such authority and responsibility will be itemized; and
 - 3. the extent of such authority and responsibilities will be provided.

- B. Unless otherwise provided in the Supplementary Conditions, Owner shall have sole authority and responsibility for such coordination.

7.03 *Legal Relationships*

- A. Paragraphs 7.01.A and 7.02 are not applicable for utilities not under the control of Owner.
- B. Each other direct contract of Owner under Paragraph 7.01.A shall provide that the other contractor is liable to Owner and Contractor for the reasonable direct delay and disruption costs incurred by Contractor as a result of the other contractor's wrongful actions or inactions.
- C. Contractor shall be liable to Owner and any other contractor under direct contract to Owner for the reasonable direct delay and disruption costs incurred by such other contractor as a result of Contractor's wrongful action or inactions.

ARTICLE 8 – OWNER'S RESPONSIBILITIES

8.01 *Communications to Contractor*

- A. Except as otherwise provided in these General Conditions, Owner shall issue all communications to Contractor through Engineer.

8.02 *Replacement of Engineer*

- A. In case of termination of the employment of Engineer, Owner shall appoint an engineer to whom Contractor makes no reasonable objection, whose status under the Contract Documents shall be that of the former Engineer.

8.03 *Furnish Data*

- A. Owner shall promptly furnish the data required of Owner under the Contract Documents.

8.04 *Pay When Due*

- A. Owner shall make payments to Contractor when they are due as provided in Paragraphs 14.02.C and 14.07.C.

8.05 *Lands and Easements; Reports and Tests*

- A. Owner's duties with respect to providing lands and easements and providing engineering surveys to establish reference points are set forth in Paragraphs 4.01 and 4.05. Paragraph 4.02 refers to Owner's identifying and making available to Contractor copies of reports of explorations and tests of subsurface conditions and drawings of physical conditions relating to existing surface or subsurface structures at the Site.

8.06 *Insurance*

- A. Owner's responsibilities, if any, with respect to purchasing and maintaining liability and property insurance are set forth in Article 5.

8.07 *Change Orders*

A. Owner is obligated to execute Change Orders as indicated in Paragraph 10.03.

8.08 *Inspections, Tests, and Approvals*

A. Owner's responsibility with respect to certain inspections, tests, and approvals is set forth in Paragraph 13.03.B.

8.09 *Limitations on Owner's Responsibilities*

A. The Owner shall not supervise, direct, or have control or authority over, nor be responsible for, Contractor's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of Contractor to comply with Laws and Regulations applicable to the performance of the Work. Owner will not be responsible for Contractor's failure to perform the Work in accordance with the Contract Documents.

8.10 *Undisclosed Hazardous Environmental Condition*

A. Owner's responsibility in respect to an undisclosed Hazardous Environmental Condition is set forth in Paragraph 4.06.

8.11 *Evidence of Financial Arrangements*

A. Upon request of Contractor, Owner shall furnish Contractor reasonable evidence that financial arrangements have been made to satisfy Owner's obligations under the Contract Documents.

8.12 *Compliance with Safety Program*

A. While at the Site, Owner's employees and representatives shall comply with the specific applicable requirements of Contractor's safety programs of which Owner has been informed pursuant to Paragraph 6.13.D.

ARTICLE 9 – ENGINEER'S STATUS DURING CONSTRUCTION

9.01 *Owner's Representative*

A. Engineer will be Owner's representative during the construction period. The duties and responsibilities and the limitations of authority of Engineer as Owner's representative during construction are set forth in the Contract Documents.

9.02 *Visits to Site*

A. Engineer will make visits to the Site at intervals appropriate to the various stages of construction as Engineer deems necessary in order to observe as an experienced and qualified design professional the progress that has been made and the quality of the various aspects of Contractor's executed Work. Based on information obtained during such visits and observations, Engineer, for the benefit of Owner, will determine, in general, if the Work is proceeding in accordance with the Contract Documents. Engineer will not be required to make exhaustive or

continuous inspections on the Site to check the quality or quantity of the Work. Engineer's efforts will be directed toward providing for Owner a greater degree of confidence that the completed Work will conform generally to the Contract Documents. On the basis of such visits and observations, Engineer will keep Owner informed of the progress of the Work and will endeavor to guard Owner against defective Work.

- B. Engineer's visits and observations are subject to all the limitations on Engineer's authority and responsibility set forth in Paragraph 9.09. Particularly, but without limitation, during or as a result of Engineer's visits or observations of Contractor's Work, Engineer will not supervise, direct, control, or have authority over or be responsible for Contractor's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of Contractor to comply with Laws and Regulations applicable to the performance of the Work.

9.03 *Project Representative*

- A. If Owner and Engineer agree, Engineer will furnish a Resident Project Representative to assist Engineer in providing more extensive observation of the Work. The authority and responsibilities of any such Resident Project Representative and assistants will be as provided in the Supplementary Conditions, and limitations on the responsibilities thereof will be as provided in Paragraph 9.09. If Owner designates another representative or agent to represent Owner at the Site who is not Engineer's consultant, agent or employee, the responsibilities and authority and limitations thereon of such other individual or entity will be as provided in the Supplementary Conditions.

9.04 *Authorized Variations in Work*

- A. Engineer may authorize minor variations in the Work from the requirements of the Contract Documents which do not involve an adjustment in the Contract Price or the Contract Times and are compatible with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents. These may be accomplished by a Field Order and will be binding on Owner and also on Contractor, who shall perform the Work involved promptly. If Owner or Contractor believes that a Field Order justifies an adjustment in the Contract Price or Contract Times, or both, and the parties are unable to agree on entitlement to or on the amount or extent, if any, of any such adjustment, a Claim may be made therefor as provided in Paragraph 10.05.

9.05 *Rejecting Defective Work*

- A. Engineer will have authority to reject Work which Engineer believes to be defective, or that Engineer believes will not produce a completed Project that conforms to the Contract Documents or that will prejudice the integrity of the design concept of the completed Project as a functioning whole as indicated by the Contract Documents. Engineer will also have authority to require special inspection or testing of the Work as provided in Paragraph 13.04, whether or not the Work is fabricated, installed, or completed.

9.06 *Shop Drawings, Change Orders and Payments*

- A. In connection with Engineer's authority, and limitations thereof, as to Shop Drawings and Samples, see Paragraph 6.17.
- B. In connection with Engineer's authority, and limitations thereof, as to design calculations and design drawings submitted in response to a delegation of professional design services, if any, see Paragraph 6.21.
- C. In connection with Engineer's authority as to Change Orders, see Articles 10, 11, and 12.
- D. In connection with Engineer's authority as to Applications for Payment, see Article 14.

9.07 *Determinations for Unit Price Work*

- A. Engineer will determine the actual quantities and classifications of Unit Price Work performed by Contractor. Engineer will review with Contractor the Engineer's preliminary determinations on such matters before rendering a written decision thereon (by recommendation of an Application for Payment or otherwise). Engineer's written decision thereon will be final and binding (except as modified by Engineer to reflect changed factual conditions or more accurate data) upon Owner and Contractor, subject to the provisions of Paragraph 10.05.

9.08 *Decisions on Requirements of Contract Documents and Acceptability of Work*

- A. Engineer will be the initial interpreter of the requirements of the Contract Documents and judge of the acceptability of the Work thereunder. All matters in question and other matters between Owner and Contractor arising prior to the date final payment is due relating to the acceptability of the Work, and the interpretation of the requirements of the Contract Documents pertaining to the performance of the Work, will be referred initially to Engineer in writing within 30 days of the event giving rise to the question.
- B. Engineer will, with reasonable promptness, render a written decision on the issue referred. If Owner or Contractor believes that any such decision entitles them to an adjustment in the Contract Price or Contract Times or both, a Claim may be made under Paragraph 10.05. The date of Engineer's decision shall be the date of the event giving rise to the issues referenced for the purposes of Paragraph 10.05.B.
- C. Engineer's written decision on the issue referred will be final and binding on Owner and Contractor, subject to the provisions of Paragraph 10.05.
- D. When functioning as interpreter and judge under this Paragraph 9.08, Engineer will not show partiality to Owner or Contractor and will not be liable in connection with any interpretation or decision rendered in good faith in such capacity.

9.09 *Limitations on Engineer's Authority and Responsibilities*

- A. Neither Engineer's authority or responsibility under this Article 9 or under any other provision of the Contract Documents nor any decision made by Engineer in good faith either to exercise

or not exercise such authority or responsibility or the undertaking, exercise, or performance of any authority or responsibility by Engineer shall create, impose, or give rise to any duty in contract, tort, or otherwise owed by Engineer to Contractor, any Subcontractor, any Supplier, any other individual or entity, or to any surety for or employee or agent of any of them.

- B. Engineer will not supervise, direct, control, or have authority over or be responsible for Contractor's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of Contractor to comply with Laws and Regulations applicable to the performance of the Work. Engineer will not be responsible for Contractor's failure to perform the Work in accordance with the Contract Documents.
- C. Engineer will not be responsible for the acts or omissions of Contractor or of any Subcontractor, any Supplier, or of any other individual or entity performing any of the Work.
- D. Engineer's review of the final Application for Payment and accompanying documentation and all maintenance and operating instructions, schedules, guarantees, bonds, certificates of inspection, tests and approvals, and other documentation required to be delivered by Paragraph 14.07.A will only be to determine generally that their content complies with the requirements of, and in the case of certificates of inspections, tests, and approvals that the results certified indicate compliance with, the Contract Documents.
- E. The limitations upon authority and responsibility set forth in this Paragraph 9.09 shall also apply to the Resident Project Representative, if any, and assistants, if any.

9.10 *Compliance with Safety Program*

- A. While at the Site, Engineer's employees and representatives shall comply with the specific applicable requirements of Contractor's safety programs of which Engineer has been informed pursuant to Paragraph 6.13.D.

ARTICLE 10 – CHANGES IN THE WORK; CLAIMS

10.01 *Authorized Changes in the Work*

- A. Without invalidating the Contract and without notice to any surety, Owner may, at any time or from time to time, order additions, deletions, or revisions in the Work by a Change Order, or a Work Change Directive. Upon receipt of any such document, Contractor shall promptly proceed with the Work involved which will be performed under the applicable conditions of the Contract Documents (except as otherwise specifically provided).
- B. If Owner and Contractor are unable to agree on entitlement to, or on the amount or extent, if any, of an adjustment in the Contract Price or Contract Times, or both, that should be allowed as a result of a Work Change Directive, a Claim may be made therefor as provided in Paragraph 10.05.

10.02 *Unauthorized Changes in the Work*

- A. Contractor shall not be entitled to an increase in the Contract Price or an extension of the Contract Times with respect to any work performed that is not required by the Contract Documents as amended, modified, or supplemented as provided in Paragraph 3.04, except in the case of an emergency as provided in Paragraph 6.16 or in the case of uncovering Work as provided in Paragraph 13.04.D.

10.03 *Execution of Change Orders*

- A. Owner and Contractor shall execute appropriate Change Orders recommended by Engineer covering:
 - 1. changes in the Work which are: (i) ordered by Owner pursuant to Paragraph 10.01.A, (ii) required because of acceptance of defective Work under Paragraph 13.08.A or Owner's correction of defective Work under Paragraph 13.09, or (iii) agreed to by the parties;
 - 2. changes in the Contract Price or Contract Times which are agreed to by the parties, including any undisputed sum or amount of time for Work actually performed in accordance with a Work Change Directive; and
 - 3. changes in the Contract Price or Contract Times which embody the substance of any written decision rendered by Engineer pursuant to Paragraph 10.05; provided that, in lieu of executing any such Change Order, an appeal may be taken from any such decision in accordance with the provisions of the Contract Documents and applicable Laws and Regulations, but during any such appeal, Contractor shall carry on the Work and adhere to the Progress Schedule as provided in Paragraph 6.18.A.

10.04 *Notification to Surety*

- A. If the provisions of any bond require notice to be given to a surety of any change affecting the general scope of the Work or the provisions of the Contract Documents (including, but not limited to, Contract Price or Contract Times), the giving of any such notice will be Contractor's responsibility. The amount of each applicable bond will be adjusted to reflect the effect of any such change.

10.05 *Claims*

- A. *Engineer's Decision Required:* All Claims, except those waived pursuant to Paragraph 14.09, shall be referred to the Engineer for decision. A decision by Engineer shall be required as a condition precedent to any exercise by Owner or Contractor of any rights or remedies either may otherwise have under the Contract Documents or by Laws and Regulations in respect of such Claims.
- B. *Notice:* Written notice stating the general nature of each Claim shall be delivered by the claimant to Engineer and the other party to the Contract promptly (but in no event later than 30 days) after the start of the event giving rise thereto. The responsibility to substantiate a Claim shall rest with the party making the Claim. Notice of the amount or extent of the Claim, with supporting data

shall be delivered to the Engineer and the other party to the Contract within 60 days after the start of such event (unless Engineer allows additional time for claimant to submit additional or more accurate data in support of such Claim). A Claim for an adjustment in Contract Price shall be prepared in accordance with the provisions of Paragraph 12.01.B. A Claim for an adjustment in Contract Times shall be prepared in accordance with the provisions of Paragraph 12.02.B. Each Claim shall be accompanied by claimant's written statement that the adjustment claimed is the entire adjustment to which the claimant believes it is entitled as a result of said event. The opposing party shall submit any response to Engineer and the claimant within 30 days after receipt of the claimant's last submittal (unless Engineer allows additional time).

- C. *Engineer's Action:* Engineer will review each Claim and, within 30 days after receipt of the last submittal of the claimant or the last submittal of the opposing party, if any, take one of the following actions in writing:
1. deny the Claim in whole or in part;
 2. approve the Claim; or
 3. notify the parties that the Engineer is unable to resolve the Claim if, in the Engineer's sole discretion, it would be inappropriate for the Engineer to do so. For purposes of further resolution of the Claim, such notice shall be deemed a denial.
- D. In the event that Engineer does not take action on a Claim within said 30 days, the Claim shall be deemed denied.
- E. Engineer's written action under Paragraph 10.05.C or denial pursuant to Paragraphs 10.05.C.3 or 10.05.D will be final and binding upon Owner and Contractor, unless Owner or Contractor invoke the dispute resolution procedure set forth in Article 16 within 30 days of such action or denial.
- F. No Claim for an adjustment in Contract Price or Contract Times will be valid if not submitted in accordance with this Paragraph 10.05.

ARTICLE 11 – COST OF THE WORK; ALLOWANCES; UNIT PRICE WORK

11.01 *Cost of the Work*

- A. *Costs Included:* The term Cost of the Work means the sum of all costs, except those excluded in Paragraph 11.01.B, necessarily incurred and paid by Contractor in the proper performance of the Work. When the value of any Work covered by a Change Order or when a Claim for an adjustment in Contract Price is determined on the basis of Cost of the Work, the costs to be reimbursed to Contractor will be only those additional or incremental costs required because of the change in the Work or because of the event giving rise to the Claim. Except as otherwise may be agreed to in writing by Owner, such costs shall be in amounts no higher than those prevailing in the locality of the Project, shall not include any of the costs itemized in Paragraph 11.01.B, and shall include only the following items:

1. Payroll costs for employees in the direct employ of Contractor in the performance of the Work under schedules of job classifications agreed upon by Owner and Contractor. Such employees shall include, without limitation, superintendents, foremen, and other personnel employed full time on the Work. Payroll costs for employees not employed full time on the Work shall be apportioned on the basis of their time spent on the Work. Payroll costs shall include, but not be limited to, salaries and wages plus the cost of fringe benefits, which shall include social security contributions, unemployment, excise, and payroll taxes, workers' compensation, health and retirement benefits, bonuses, sick leave, vacation and holiday pay applicable thereto. The expenses of performing Work outside of regular working hours, on Saturday, Sunday, or legal holidays, shall be included in the above to the extent authorized by Owner.
2. Cost of all materials and equipment furnished and incorporated in the Work, including costs of transportation and storage thereof, and Suppliers' field services required in connection therewith. All cash discounts shall accrue to Contractor unless Owner deposits funds with Contractor with which to make payments, in which case the cash discounts shall accrue to Owner. All trade discounts, rebates and refunds and returns from sale of surplus materials and equipment shall accrue to Owner, and Contractor shall make provisions so that they may be obtained.
3. Payments made by Contractor to Subcontractors for Work performed by Subcontractors. If required by Owner, Contractor shall obtain competitive bids from subcontractors acceptable to Owner and Contractor and shall deliver such bids to Owner, who will then determine, with the advice of Engineer, which bids, if any, will be acceptable. If any subcontract provides that the Subcontractor is to be paid on the basis of Cost of the Work plus a fee, the Subcontractor's Cost of the Work and fee shall be determined in the same manner as Contractor's Cost of the Work and fee as provided in this Paragraph 11.01.
4. Costs of special consultants (including but not limited to engineers, architects, testing laboratories, surveyors, attorneys, and accountants) employed for services specifically related to the Work.
5. Supplemental costs including the following:
 - a. The proportion of necessary transportation, travel, and subsistence expenses of Contractor's employees incurred in discharge of duties connected with the Work.
 - b. Cost, including transportation and maintenance, of all materials, supplies, equipment, machinery, appliances, office, and temporary facilities at the Site, and hand tools not owned by the workers, which are consumed in the performance of the Work, and cost, less market value, of such items used but not consumed which remain the property of Contractor.
 - c. Rentals of all construction equipment and machinery, and the parts thereof whether rented from Contractor or others in accordance with rental agreements approved by Owner with the advice of Engineer, and the costs of transportation, loading, unloading, assembly, dismantling, and removal thereof. All such costs shall be in accordance with the terms of

said rental agreements. The rental of any such equipment, machinery, or parts shall cease when the use thereof is no longer necessary for the Work.

- d. Sales, consumer, use, and other similar taxes related to the Work, and for which Contractor is liable, as imposed by Laws and Regulations.
- e. Deposits lost for causes other than negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable, and royalty payments and fees for permits and licenses.
- f. Losses and damages (and related expenses) caused by damage to the Work, not compensated by insurance or otherwise, sustained by Contractor in connection with the performance of the Work (except losses and damages within the deductible amounts of property insurance established in accordance with Paragraph 5.06.D), provided such losses and damages have resulted from causes other than the negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable. Such losses shall include settlements made with the written consent and approval of Owner. No such losses, damages, and expenses shall be included in the Cost of the Work for the purpose of determining Contractor's fee.
- g. The cost of utilities, fuel, and sanitary facilities at the Site.
- h. Minor expenses such as telegrams, long distance telephone calls, telephone service at the Site, express and courier services, and similar petty cash items in connection with the Work.
- i. The costs of premiums for all bonds and insurance Contractor is required by the Contract Documents to purchase and maintain.

B. *Costs Excluded:* The term Cost of the Work shall not include any of the following items:

1. Payroll costs and other compensation of Contractor's officers, executives, principals (of partnerships and sole proprietorships), general managers, safety managers, engineers, architects, estimators, attorneys, auditors, accountants, purchasing and contracting agents, expeditors, timekeepers, clerks, and other personnel employed by Contractor, whether at the Site or in Contractor's principal or branch office for general administration of the Work and not specifically included in the agreed upon schedule of job classifications referred to in Paragraph 11.01.A.1 or specifically covered by Paragraph 11.01.A.4, all of which are to be considered administrative costs covered by the Contractor's fee.
2. Expenses of Contractor's principal and branch offices other than Contractor's office at the Site.
3. Any part of Contractor's capital expenses, including interest on Contractor's capital employed for the Work and charges against Contractor for delinquent payments.
4. Costs due to the negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable, including but not

limited to, the correction of defective Work, disposal of materials or equipment wrongly supplied, and making good any damage to property.

5. Other overhead or general expense costs of any kind and the costs of any item not specifically and expressly included in Paragraphs 11.01.A.
- C. *Contractor's Fee:* When all the Work is performed on the basis of cost-plus, Contractor's fee shall be determined as set forth in the Agreement. When the value of any Work covered by a Change Order or when a Claim for an adjustment in Contract Price is determined on the basis of Cost of the Work, Contractor's fee shall be determined as set forth in Paragraph 12.01.C.
- D. *Documentation:* Whenever the Cost of the Work for any purpose is to be determined pursuant to Paragraphs 11.01.A and 11.01.B, Contractor will establish and maintain records thereof in accordance with generally accepted accounting practices and submit in a form acceptable to Engineer an itemized cost breakdown together with supporting data.

11.02 Allowances

- A. It is understood that Contractor has included in the Contract Price all allowances so named in the Contract Documents and shall cause the Work so covered to be performed for such sums and by such persons or entities as may be acceptable to Owner and Engineer.
- B. *Cash Allowances:*
 1. Contractor agrees that:
 - a. the cash allowances include the cost to Contractor (less any applicable trade discounts) of materials and equipment required by the allowances to be delivered at the Site, and all applicable taxes; and
 - b. Contractor's costs for unloading and handling on the Site, labor, installation, overhead, profit, and other expenses contemplated for the cash allowances have been included in the Contract Price and not in the allowances, and no demand for additional payment on account of any of the foregoing will be valid.
- C. *Contingency Allowance:*
 1. Contractor agrees that a contingency allowance, if any, is for the sole use of Owner to cover unanticipated costs.
- D. Prior to final payment, an appropriate Change Order will be issued as recommended by Engineer to reflect actual amounts due Contractor on account of Work covered by allowances, and the Contract Price shall be correspondingly adjusted.

11.03 Unit Price Work

- A. Where the Contract Documents provide that all or part of the Work is to be Unit Price Work, initially the Contract Price will be deemed to include for all Unit Price Work an amount equal to

the sum of the unit price for each separately identified item of Unit Price Work times the estimated quantity of each item as indicated in the Agreement.

- B. The estimated quantities of items of Unit Price Work are not guaranteed and are solely for the purpose of comparison of Bids and determining an initial Contract Price. Determinations of the actual quantities and classifications of Unit Price Work performed by Contractor will be made by Engineer subject to the provisions of Paragraph 9.07.
- C. Each unit price will be deemed to include an amount considered by Contractor to be adequate to cover Contractor's overhead and profit for each separately identified item.
- D. Owner or Contractor may make a Claim for an adjustment in the Contract Price in accordance with Paragraph 10.05 if:
 - 1. the quantity of any item of Unit Price Work performed by Contractor differs materially and significantly from the estimated quantity of such item indicated in the Agreement; and
 - 2. there is no corresponding adjustment with respect to any other item of Work; and
 - 3. Contractor believes that Contractor is entitled to an increase in Contract Price as a result of having incurred additional expense or Owner believes that Owner is entitled to a decrease in Contract Price and the parties are unable to agree as to the amount of any such increase or decrease.

ARTICLE 12 – CHANGE OF CONTRACT PRICE; CHANGE OF CONTRACT TIMES

12.01 Change of Contract Price

- A. The Contract Price may only be changed by a Change Order. Any Claim for an adjustment in the Contract Price shall be based on written notice submitted by the party making the Claim to the Engineer and the other party to the Contract in accordance with the provisions of Paragraph 10.05.
- B. The value of any Work covered by a Change Order or of any Claim for an adjustment in the Contract Price will be determined as follows:
 - 1. where the Work involved is covered by unit prices contained in the Contract Documents, by application of such unit prices to the quantities of the items involved (subject to the provisions of Paragraph 11.03); or
 - 2. where the Work involved is not covered by unit prices contained in the Contract Documents, by a mutually agreed lump sum (which may include an allowance for overhead and profit not necessarily in accordance with Paragraph 12.01.C.2); or
 - 3. where the Work involved is not covered by unit prices contained in the Contract Documents and agreement to a lump sum is not reached under Paragraph 12.01.B.2, on the basis of the Cost of the Work (determined as provided in Paragraph 11.01) plus a Contractor's fee for overhead and profit (determined as provided in Paragraph 12.01.C).

C. *Contractor's Fee*: The Contractor's fee for overhead and profit shall be determined as follows:

1. a mutually acceptable fixed fee; or
2. if a fixed fee is not agreed upon, then a fee based on the following percentages of the various portions of the Cost of the Work:
 - a. for costs incurred under Paragraphs 11.01.A.1 and 11.01.A.2, the Contractor's fee shall be 15 percent;
 - b. for costs incurred under Paragraph 11.01.A.3, the Contractor's fee shall be five percent;
 - c. where one or more tiers of subcontracts are on the basis of Cost of the Work plus a fee and no fixed fee is agreed upon, the intent of Paragraphs 12.01.C.2.a and 12.01.C.2.b is that the Subcontractor who actually performs the Work, at whatever tier, will be paid a fee of 15 percent of the costs incurred by such Subcontractor under Paragraphs 11.01.A.1 and 11.01.A.2 and that any higher tier Subcontractor and Contractor will each be paid a fee of five percent of the amount paid to the next lower tier Subcontractor;
 - d. no fee shall be payable on the basis of costs itemized under Paragraphs 11.01.A.4, 11.01.A.5, and 11.01.B;
 - e. the amount of credit to be allowed by Contractor to Owner for any change which results in a net decrease in cost will be the amount of the actual net decrease in cost plus a deduction in Contractor's fee by an amount equal to five percent of such net decrease; and
 - f. when both additions and credits are involved in any one change, the adjustment in Contractor's fee shall be computed on the basis of the net change in accordance with Paragraphs 12.01.C.2.a through 12.01.C.2.e, inclusive.

12.02 *Change of Contract Times*

- A. The Contract Times may only be changed by a Change Order. Any Claim for an adjustment in the Contract Times shall be based on written notice submitted by the party making the Claim to the Engineer and the other party to the Contract in accordance with the provisions of Paragraph 10.05.
- B. Any adjustment of the Contract Times covered by a Change Order or any Claim for an adjustment in the Contract Times will be determined in accordance with the provisions of this Article 12.

12.03 *Delays*

- A. Where Contractor is prevented from completing any part of the Work within the Contract Times due to delay beyond the control of Contractor, the Contract Times will be extended in an amount equal to the time lost due to such delay if a Claim is made therefor as provided in Paragraph 12.02.A. Delays beyond the control of Contractor shall include, but not be limited to, acts or

neglect by Owner, acts or neglect of utility owners or other contractors performing other work as contemplated by Article 7, fires, floods, epidemics, abnormal weather conditions, or acts of God.

- B. If Owner, Engineer, or other contractors or utility owners performing other work for Owner as contemplated by Article 7, or anyone for whom Owner is responsible, delays, disrupts, or interferes with the performance or progress of the Work, then Contractor shall be entitled to an equitable adjustment in the Contract Price or the Contract Times, or both. Contractor's entitlement to an adjustment of the Contract Times is conditioned on such adjustment being essential to Contractor's ability to complete the Work within the Contract Times.
- C. If Contractor is delayed in the performance or progress of the Work by fire, flood, epidemic, abnormal weather conditions, acts of God, acts or failures to act of utility owners not under the control of Owner, or other causes not the fault of and beyond control of Owner and Contractor, then Contractor shall be entitled to an equitable adjustment in Contract Times, if such adjustment is essential to Contractor's ability to complete the Work within the Contract Times. Such an adjustment shall be Contractor's sole and exclusive remedy for the delays described in this Paragraph 12.03.C.
- D. Owner, Engineer, and their officers, directors, members, partners, employees, agents, consultants, or subcontractors shall not be liable to Contractor for any claims, costs, losses, or damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) sustained by Contractor on or in connection with any other project or anticipated project.
- E. Contractor shall not be entitled to an adjustment in Contract Price or Contract Times for delays within the control of Contractor. Delays attributable to and within the control of a Subcontractor or Supplier shall be deemed to be delays within the control of Contractor.

ARTICLE 13 – TESTS AND INSPECTIONS; CORRECTION, REMOVAL OR ACCEPTANCE OF DEFECTIVE WORK

13.01 Notice of Defects

- A. Prompt notice of all defective Work of which Owner or Engineer has actual knowledge will be given to Contractor. Defective Work may be rejected, corrected, or accepted as provided in this Article 13.

13.02 Access to Work

- A. Owner, Engineer, their consultants and other representatives and personnel of Owner, independent testing laboratories, and governmental agencies with jurisdictional interests will have access to the Site and the Work at reasonable times for their observation, inspection, and testing. Contractor shall provide them proper and safe conditions for such access and advise them of Contractor's safety procedures and programs so that they may comply therewith as applicable.

13.03 *Tests and Inspections*

- A. Contractor shall give Engineer timely notice of readiness of the Work for all required inspections, tests, or approvals and shall cooperate with inspection and testing personnel to facilitate required inspections or tests.
- B. Owner shall employ and pay for the services of an independent testing laboratory to perform all inspections, tests, or approvals required by the Contract Documents except:
 - 1. for inspections, tests, or approvals covered by Paragraphs 13.03.C and 13.03.D below;
 - 2. that costs incurred in connection with tests or inspections conducted pursuant to Paragraph 13.04.B shall be paid as provided in Paragraph 13.04.C; and
 - 3. as otherwise specifically provided in the Contract Documents.
- C. If Laws or Regulations of any public body having jurisdiction require any Work (or part thereof) specifically to be inspected, tested, or approved by an employee or other representative of such public body, Contractor shall assume full responsibility for arranging and obtaining such inspections, tests, or approvals, pay all costs in connection therewith, and furnish Engineer the required certificates of inspection or approval.
- D. Contractor shall be responsible for arranging and obtaining and shall pay all costs in connection with any inspections, tests, or approvals required for Owner's and Engineer's acceptance of materials or equipment to be incorporated in the Work; or acceptance of materials, mix designs, or equipment submitted for approval prior to Contractor's purchase thereof for incorporation in the Work. Such inspections, tests, or approvals shall be performed by organizations acceptable to Owner and Engineer.
- E. If any Work (or the work of others) that is to be inspected, tested, or approved is covered by Contractor without written concurrence of Engineer, Contractor shall, if requested by Engineer, uncover such Work for observation.
- F. Uncovering Work as provided in Paragraph 13.03.E shall be at Contractor's expense unless Contractor has given Engineer timely notice of Contractor's intention to cover the same and Engineer has not acted with reasonable promptness in response to such notice.

13.04 *Uncovering Work*

- A. If any Work is covered contrary to the written request of Engineer, it must, if requested by Engineer, be uncovered for Engineer's observation and replaced at Contractor's expense.
- B. If Engineer considers it necessary or advisable that covered Work be observed by Engineer or inspected or tested by others, Contractor, at Engineer's request, shall uncover, expose, or otherwise make available for observation, inspection, or testing as Engineer may require, that portion of the Work in question, furnishing all necessary labor, material, and equipment.

- C. If it is found that the uncovered Work is defective, Contractor shall pay all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such uncovering, exposure, observation, inspection, and testing, and of satisfactory replacement or reconstruction (including but not limited to all costs of repair or replacement of work of others); and Owner shall be entitled to an appropriate decrease in the Contract Price. If the parties are unable to agree as to the amount thereof, Owner may make a Claim therefor as provided in Paragraph 10.05.
- D. If the uncovered Work is not found to be defective, Contractor shall be allowed an increase in the Contract Price or an extension of the Contract Times, or both, directly attributable to such uncovering, exposure, observation, inspection, testing, replacement, and reconstruction. If the parties are unable to agree as to the amount or extent thereof, Contractor may make a Claim therefor as provided in Paragraph 10.05.

13.05 *Owner May Stop the Work*

- A. If the Work is defective, or Contractor fails to supply sufficient skilled workers or suitable materials or equipment, or fails to perform the Work in such a way that the completed Work will conform to the Contract Documents, Owner may order Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, this right of Owner to stop the Work shall not give rise to any duty on the part of Owner to exercise this right for the benefit of Contractor, any Subcontractor, any Supplier, any other individual or entity, or any surety for, or employee or agent of any of them.

13.06 *Correction or Removal of Defective Work*

- A. Promptly after receipt of written notice, Contractor shall correct all defective Work, whether or not fabricated, installed, or completed, or, if the Work has been rejected by Engineer, remove it from the Project and replace it with Work that is not defective. Contractor shall pay all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such correction or removal (including but not limited to all costs of repair or replacement of work of others).
- B. When correcting defective Work under the terms of this Paragraph 13.06 or Paragraph 13.07, Contractor shall take no action that would void or otherwise impair Owner's special warranty and guarantee, if any, on said Work.

13.07 *Correction Period*

- A. If within one year after the date of Substantial Completion (or such longer period of time as may be prescribed by the terms of any applicable special guarantee required by the Contract Documents) or by any specific provision of the Contract Documents, any Work is found to be defective, or if the repair of any damages to the land or areas made available for Contractor's use by Owner or permitted by Laws and Regulations as contemplated in Paragraph 6.11.A is found to be defective, Contractor shall promptly, without cost to Owner and in accordance with Owner's written instructions:

1. repair such defective land or areas; or
 2. correct such defective Work; or
 3. if the defective Work has been rejected by Owner, remove it from the Project and replace it with Work that is not defective, and
 4. satisfactorily correct or repair or remove and replace any damage to other Work, to the work of others or other land or areas resulting therefrom.
- B. If Contractor does not promptly comply with the terms of Owner's written instructions, or in an emergency where delay would cause serious risk of loss or damage, Owner may have the defective Work corrected or repaired or may have the rejected Work removed and replaced. All claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such correction or repair or such removal and replacement (including but not limited to all costs of repair or replacement of work of others) will be paid by Contractor.
- C. In special circumstances where a particular item of equipment is placed in continuous service before Substantial Completion of all the Work, the correction period for that item may start to run from an earlier date if so provided in the Specifications.
- D. Where defective Work (and damage to other Work resulting therefrom) has been corrected or removed and replaced under this Paragraph 13.07, the correction period hereunder with respect to such Work will be extended for an additional period of one year after such correction or removal and replacement has been satisfactorily completed.
- E. Contractor's obligations under this Paragraph 13.07 are in addition to any other obligation or warranty. The provisions of this Paragraph 13.07 shall not be construed as a substitute for, or a waiver of, the provisions of any applicable statute of limitation or repose.

13.08 *Acceptance of Defective Work*

- A. If, instead of requiring correction or removal and replacement of defective Work, Owner (and, prior to Engineer's recommendation of final payment, Engineer) prefers to accept it, Owner may do so. Contractor shall pay all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) attributable to Owner's evaluation of and determination to accept such defective Work (such costs to be approved by Engineer as to reasonableness) and for the diminished value of the Work to the extent not otherwise paid by Contractor pursuant to this sentence. If any such acceptance occurs prior to Engineer's recommendation of final payment, a Change Order will be issued incorporating the necessary revisions in the Contract Documents with respect to the Work, and Owner shall be entitled to an appropriate decrease in the Contract Price, reflecting the diminished value of Work so accepted. If the parties are unable to agree as to the amount thereof, Owner may make a Claim therefor as provided in Paragraph 10.05. If the acceptance occurs after such recommendation, an appropriate amount will be paid by Contractor to Owner.

13.09 *Owner May Correct Defective Work*

- A. If Contractor fails within a reasonable time after written notice from Engineer to correct defective Work, or to remove and replace rejected Work as required by Engineer in accordance with Paragraph 13.06.A, or if Contractor fails to perform the Work in accordance with the Contract Documents, or if Contractor fails to comply with any other provision of the Contract Documents, Owner may, after seven days written notice to Contractor, correct, or remedy any such deficiency.
- B. In exercising the rights and remedies under this Paragraph 13.09, Owner shall proceed expeditiously. In connection with such corrective or remedial action, Owner may exclude Contractor from all or part of the Site, take possession of all or part of the Work and suspend Contractor's services related thereto, take possession of Contractor's tools, appliances, construction equipment and machinery at the Site, and incorporate in the Work all materials and equipment stored at the Site or for which Owner has paid Contractor but which are stored elsewhere. Contractor shall allow Owner, Owner's representatives, agents and employees, Owner's other contractors, and Engineer and Engineer's consultants access to the Site to enable Owner to exercise the rights and remedies under this Paragraph.
- C. All claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) incurred or sustained by Owner in exercising the rights and remedies under this Paragraph 13.09 will be charged against Contractor, and a Change Order will be issued incorporating the necessary revisions in the Contract Documents with respect to the Work; and Owner shall be entitled to an appropriate decrease in the Contract Price. If the parties are unable to agree as to the amount of the adjustment, Owner may make a Claim therefor as provided in Paragraph 10.05. Such claims, costs, losses and damages will include but not be limited to all costs of repair, or replacement of work of others destroyed or damaged by correction, removal, or replacement of Contractor's defective Work.
- D. Contractor shall not be allowed an extension of the Contract Times because of any delay in the performance of the Work attributable to the exercise by Owner of Owner's rights and remedies under this Paragraph 13.09.

ARTICLE 14 – PAYMENTS TO CONTRACTOR AND COMPLETION

14.01 *Schedule of Values*

- A. The Schedule of Values established as provided in Paragraph 2.07.A will serve as the basis for progress payments and will be incorporated into a form of Application for Payment acceptable to Engineer. Progress payments on account of Unit Price Work will be based on the number of units completed.

14.02 *Progress Payments*

A. *Applications for Payments:*

1. At least 20 days before the date established in the Agreement for each progress payment (but not more often than once a month), Contractor shall submit to Engineer for review an

Application for Payment filled out and signed by Contractor covering the Work completed as of the date of the Application and accompanied by such supporting documentation as is required by the Contract Documents. If payment is requested on the basis of materials and equipment not incorporated in the Work but delivered and suitably stored at the Site or at another location agreed to in writing, the Application for Payment shall also be accompanied by a bill of sale, invoice, or other documentation warranting that Owner has received the materials and equipment free and clear of all Liens and evidence that the materials and equipment are covered by appropriate property insurance or other arrangements to protect Owner's interest therein, all of which must be satisfactory to Owner.

2. Beginning with the second Application for Payment, each Application shall include an affidavit of Contractor stating that all previous progress payments received on account of the Work have been applied on account to discharge Contractor's legitimate obligations associated with prior Applications for Payment.
3. The amount of retainage with respect to progress payments will be as stipulated in the Agreement.

B. Review of Applications:

1. Engineer will, within 10 days after receipt of each Application for Payment, either indicate in writing a recommendation of payment and present the Application to Owner or return the Application to Contractor indicating in writing Engineer's reasons for refusing to recommend payment. In the latter case, Contractor may make the necessary corrections and resubmit the Application.
2. Engineer's recommendation of any payment requested in an Application for Payment will constitute a representation by Engineer to Owner, based on Engineer's observations of the executed Work as an experienced and qualified design professional, and on Engineer's review of the Application for Payment and the accompanying data and schedules, that to the best of Engineer's knowledge, information and belief:
 - a. the Work has progressed to the point indicated;
 - b. the quality of the Work is generally in accordance with the Contract Documents (subject to an evaluation of the Work as a functioning whole prior to or upon Substantial Completion, the results of any subsequent tests called for in the Contract Documents, a final determination of quantities and classifications for Unit Price Work under Paragraph 9.07, and any other qualifications stated in the recommendation); and
 - c. the conditions precedent to Contractor's being entitled to such payment appear to have been fulfilled in so far as it is Engineer's responsibility to observe the Work.
3. By recommending any such payment Engineer will not thereby be deemed to have represented that:
 - a. inspections made to check the quality or the quantity of the Work as it has been performed have been exhaustive, extended to every aspect of the Work in progress, or

involved detailed inspections of the Work beyond the responsibilities specifically assigned to Engineer in the Contract Documents; or

- b. there may not be other matters or issues between the parties that might entitle Contractor to be paid additionally by Owner or entitle Owner to withhold payment to Contractor.
4. Neither Engineer's review of Contractor's Work for the purposes of recommending payments nor Engineer's recommendation of any payment, including final payment, will impose responsibility on Engineer:
 - a. to supervise, direct, or control the Work, or
 - b. for the means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or
 - c. for Contractor's failure to comply with Laws and Regulations applicable to Contractor's performance of the Work, or
 - d. to make any examination to ascertain how or for what purposes Contractor has used the moneys paid on account of the Contract Price, or
 - e. to determine that title to any of the Work, materials, or equipment has passed to Owner free and clear of any Liens.
 5. Engineer may refuse to recommend the whole or any part of any payment if, in Engineer's opinion, it would be incorrect to make the representations to Owner stated in Paragraph 14.02.B.2. Engineer may also refuse to recommend any such payment or, because of subsequently discovered evidence or the results of subsequent inspections or tests, revise or revoke any such payment recommendation previously made, to such extent as may be necessary in Engineer's opinion to protect Owner from loss because:
 - a. the Work is defective, or completed Work has been damaged, requiring correction or replacement;
 - b. the Contract Price has been reduced by Change Orders;
 - c. Owner has been required to correct defective Work or complete Work in accordance with Paragraph 13.09; or
 - d. Engineer has actual knowledge of the occurrence of any of the events enumerated in Paragraph 15.02.A.

C. Payment Becomes Due:

1. Ten days after presentation of the Application for Payment to Owner with Engineer's recommendation, the amount recommended will (subject to the provisions of Paragraph 14.02.D) become due, and when due will be paid by Owner to Contractor.

D. *Reduction in Payment:*

1. Owner may refuse to make payment of the full amount recommended by Engineer because:
 - a. claims have been made against Owner on account of Contractor's performance or furnishing of the Work;
 - b. Liens have been filed in connection with the Work, except where Contractor has delivered a specific bond satisfactory to Owner to secure the satisfaction and discharge of such Liens;
 - c. there are other items entitling Owner to a set-off against the amount recommended; or
 - d. Owner has actual knowledge of the occurrence of any of the events enumerated in Paragraphs 14.02.B.5.a through 14.02.B.5.c or Paragraph 15.02.A.
2. If Owner refuses to make payment of the full amount recommended by Engineer, Owner will give Contractor immediate written notice (with a copy to Engineer) stating the reasons for such action and promptly pay Contractor any amount remaining after deduction of the amount so withheld. Owner shall promptly pay Contractor the amount so withheld, or any adjustment thereto agreed to by Owner and Contractor, when Contractor remedies the reasons for such action.
3. Upon a subsequent determination that Owner's refusal of payment was not justified, the amount wrongfully withheld shall be treated as an amount due as determined by Paragraph 14.02.C.1 and subject to interest as provided in the Agreement.

14.03 *Contractor's Warranty of Title*

- A. Contractor warrants and guarantees that title to all Work, materials, and equipment covered by any Application for Payment, whether incorporated in the Project or not, will pass to Owner no later than the time of payment free and clear of all Liens.

14.04 *Substantial Completion*

- A. When Contractor considers the entire Work ready for its intended use Contractor shall notify Owner and Engineer in writing that the entire Work is substantially complete (except for items specifically listed by Contractor as incomplete) and request that Engineer issue a certificate of Substantial Completion.
- B. Promptly after Contractor's notification, Owner, Contractor, and Engineer shall make an inspection of the Work to determine the status of completion. If Engineer does not consider the Work substantially complete, Engineer will notify Contractor in writing giving the reasons therefor.
- C. If Engineer considers the Work substantially complete, Engineer will deliver to Owner a tentative certificate of Substantial Completion which shall fix the date of Substantial Completion. There shall be attached to the certificate a tentative list of items to be completed or corrected before

final payment. Owner shall have seven days after receipt of the tentative certificate during which to make written objection to Engineer as to any provisions of the certificate or attached list. If, after considering such objections, Engineer concludes that the Work is not substantially complete, Engineer will, within 14 days after submission of the tentative certificate to Owner, notify Contractor in writing, stating the reasons therefor. If, after consideration of Owner's objections, Engineer considers the Work substantially complete, Engineer will, within said 14 days, execute and deliver to Owner and Contractor a definitive certificate of Substantial Completion (with a revised tentative list of items to be completed or corrected) reflecting such changes from the tentative certificate as Engineer believes justified after consideration of any objections from Owner.

- D. At the time of delivery of the tentative certificate of Substantial Completion, Engineer will deliver to Owner and Contractor a written recommendation as to division of responsibilities pending final payment between Owner and Contractor with respect to security, operation, safety, and protection of the Work, maintenance, heat, utilities, insurance, and warranties and guarantees. Unless Owner and Contractor agree otherwise in writing and so inform Engineer in writing prior to Engineer's issuing the definitive certificate of Substantial Completion, Engineer's aforesaid recommendation will be binding on Owner and Contractor until final payment.
- E. Owner shall have the right to exclude Contractor from the Site after the date of Substantial Completion subject to allowing Contractor reasonable access to remove its property and complete or correct items on the tentative list.

14.05 *Partial Utilization*

- A. Prior to Substantial Completion of all the Work, Owner may use or occupy any substantially completed part of the Work which has specifically been identified in the Contract Documents, or which Owner, Engineer, and Contractor agree constitutes a separately functioning and usable part of the Work that can be used by Owner for its intended purpose without significant interference with Contractor's performance of the remainder of the Work, subject to the following conditions:
 - 1. Owner at any time may request Contractor in writing to permit Owner to use or occupy any such part of the Work which Owner believes to be ready for its intended use and substantially complete. If and when Contractor agrees that such part of the Work is substantially complete, Contractor, Owner, and Engineer will follow the procedures of Paragraph 14.04.A through D for that part of the Work.
 - 2. Contractor at any time may notify Owner and Engineer in writing that Contractor considers any such part of the Work ready for its intended use and substantially complete and request Engineer to issue a certificate of Substantial Completion for that part of the Work.
 - 3. Within a reasonable time after either such request, Owner, Contractor, and Engineer shall make an inspection of that part of the Work to determine its status of completion. If Engineer does not consider that part of the Work to be substantially complete, Engineer will notify Owner and Contractor in writing giving the reasons therefor. If Engineer considers that part of the Work to be substantially complete, the provisions of Paragraph 14.04 will apply with respect to certification of Substantial Completion of that part of the Work and the division of responsibility in respect thereof and access thereto.

4. No use or occupancy or separate operation of part of the Work may occur prior to compliance with the requirements of Paragraph 5.10 regarding property insurance.

14.06 *Final Inspection*

- A. Upon written notice from Contractor that the entire Work or an agreed portion thereof is complete, Engineer will promptly make a final inspection with Owner and Contractor and will notify Contractor in writing of all particulars in which this inspection reveals that the Work is incomplete or defective. Contractor shall immediately take such measures as are necessary to complete such Work or remedy such deficiencies.

14.07 *Final Payment*

A. *Application for Payment:*

1. After Contractor has, in the opinion of Engineer, satisfactorily completed all corrections identified during the final inspection and has delivered, in accordance with the Contract Documents, all maintenance and operating instructions, schedules, guarantees, bonds, certificates or other evidence of insurance, certificates of inspection, marked-up record documents (as provided in Paragraph 6.12), and other documents, Contractor may make application for final payment following the procedure for progress payments.
2. The final Application for Payment shall be accompanied (except as previously delivered) by:
 - a. all documentation called for in the Contract Documents, including but not limited to the evidence of insurance required by Paragraph 5.04.B.6;
 - b. consent of the surety, if any, to final payment;
 - c. a list of all Claims against Owner that Contractor believes are unsettled; and
 - d. complete and legally effective releases or waivers (satisfactory to Owner) of all Lien rights arising out of or Liens filed in connection with the Work.
3. In lieu of the releases or waivers of Liens specified in Paragraph 14.07.A.2 and as approved by Owner, Contractor may furnish receipts or releases in full and an affidavit of Contractor that: (i) the releases and receipts include all labor, services, material, and equipment for which a Lien could be filed; and (ii) all payrolls, material and equipment bills, and other indebtedness connected with the Work for which Owner might in any way be responsible, or which might in any way result in liens or other burdens on Owner's property, have been paid or otherwise satisfied. If any Subcontractor or Supplier fails to furnish such a release or receipt in full, Contractor may furnish a bond or other collateral satisfactory to Owner to indemnify Owner against any Lien.

B. *Engineer's Review of Application and Acceptance:*

1. If, on the basis of Engineer's observation of the Work during construction and final inspection, and Engineer's review of the final Application for Payment and accompanying

documentation as required by the Contract Documents, Engineer is satisfied that the Work has been completed and Contractor's other obligations under the Contract Documents have been fulfilled, Engineer will, within ten days after receipt of the final Application for Payment, indicate in writing Engineer's recommendation of payment and present the Application for Payment to Owner for payment. At the same time Engineer will also give written notice to Owner and Contractor that the Work is acceptable subject to the provisions of Paragraph 14.09. Otherwise, Engineer will return the Application for Payment to Contractor, indicating in writing the reasons for refusing to recommend final payment, in which case Contractor shall make the necessary corrections and resubmit the Application for Payment.

C. *Payment Becomes Due:*

1. Thirty days after the presentation to Owner of the Application for Payment and accompanying documentation, the amount recommended by Engineer, less any sum Owner is entitled to set off against Engineer's recommendation, including but not limited to liquidated damages, will become due and will be paid by Owner to Contractor.

14.08 *Final Completion Delayed*

- A. If, through no fault of Contractor, final completion of the Work is significantly delayed, and if Engineer so confirms, Owner shall, upon receipt of Contractor's final Application for Payment (for Work fully completed and accepted) and recommendation of Engineer, and without terminating the Contract, make payment of the balance due for that portion of the Work fully completed and accepted. If the remaining balance to be held by Owner for Work not fully completed or corrected is less than the retainage stipulated in the Agreement, and if bonds have been furnished as required in Paragraph 5.01, the written consent of the surety to the payment of the balance due for that portion of the Work fully completed and accepted shall be submitted by Contractor to Engineer with the Application for such payment. Such payment shall be made under the terms and conditions governing final payment, except that it shall not constitute a waiver of Claims.

14.09 *Waiver of Claims*

- A. The making and acceptance of final payment will constitute:
 1. a waiver of all Claims by Owner against Contractor, except Claims arising from unsettled Liens, from defective Work appearing after final inspection pursuant to Paragraph 14.06, from failure to comply with the Contract Documents or the terms of any special guarantees specified therein, or from Contractor's continuing obligations under the Contract Documents; and
 2. a waiver of all Claims by Contractor against Owner other than those previously made in accordance with the requirements herein and expressly acknowledged by Owner in writing as still unsettled.

ARTICLE 15 – SUSPENSION OF WORK AND TERMINATION

15.01 *Owner May Suspend Work*

- A. At any time and without cause, Owner may suspend the Work or any portion thereof for a period of not more than 90 consecutive days by notice in writing to Contractor and Engineer which will fix the date on which Work will be resumed. Contractor shall resume the Work on the date so fixed. Contractor shall be granted an adjustment in the Contract Price or an extension of the Contract Times, or both, directly attributable to any such suspension if Contractor makes a Claim therefor as provided in Paragraph 10.05.

15.02 *Owner May Terminate for Cause*

- A. The occurrence of any one or more of the following events will justify termination for cause:
1. Contractor's persistent failure to perform the Work in accordance with the Contract Documents (including, but not limited to, failure to supply sufficient skilled workers or suitable materials or equipment or failure to adhere to the Progress Schedule established under Paragraph 2.07 as adjusted from time to time pursuant to Paragraph 6.04);
 2. Contractor's disregard of Laws or Regulations of any public body having jurisdiction;
 3. Contractor's repeated disregard of the authority of Engineer; or
 4. Contractor's violation in any substantial way of any provisions of the Contract Documents.
- B. If one or more of the events identified in Paragraph 15.02.A occur, Owner may, after giving Contractor (and surety) seven days written notice of its intent to terminate the services of Contractor:
1. exclude Contractor from the Site, and take possession of the Work and of all Contractor's tools, appliances, construction equipment, and machinery at the Site, and use the same to the full extent they could be used by Contractor (without liability to Contractor for trespass or conversion);
 2. incorporate in the Work all materials and equipment stored at the Site or for which Owner has paid Contractor but which are stored elsewhere; and
 3. complete the Work as Owner may deem expedient.
- C. If Owner proceeds as provided in Paragraph 15.02.B, Contractor shall not be entitled to receive any further payment until the Work is completed. If the unpaid balance of the Contract Price exceeds all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) sustained by Owner arising out of or relating to completing the Work, such excess will be paid to Contractor. If such claims, costs, losses, and damages exceed such unpaid balance, Contractor shall pay the difference to Owner. Such claims, costs, losses, and damages incurred by Owner will be reviewed by Engineer as to their reasonableness and, when

so approved by Engineer, incorporated in a Change Order. When exercising any rights or remedies under this Paragraph, Owner shall not be required to obtain the lowest price for the Work performed.

- D. Notwithstanding Paragraphs 15.02.B and 15.02.C, Contractor's services will not be terminated if Contractor begins within seven days of receipt of notice of intent to terminate to correct its failure to perform and proceeds diligently to cure such failure within no more than 30 days of receipt of said notice.
- E. Where Contractor's services have been so terminated by Owner, the termination will not affect any rights or remedies of Owner against Contractor then existing or which may thereafter accrue. Any retention or payment of moneys due Contractor by Owner will not release Contractor from liability.
- F. If and to the extent that Contractor has provided a performance bond under the provisions of Paragraph 5.01.A, the termination procedures of that bond shall supersede the provisions of Paragraphs 15.02.B and 15.02.C.

15.03 *Owner May Terminate For Convenience*

- A. Upon seven days written notice to Contractor and Engineer, Owner may, without cause and without prejudice to any other right or remedy of Owner, terminate the Contract. In such case, Contractor shall be paid for (without duplication of any items):
 - 1. completed and acceptable Work executed in accordance with the Contract Documents prior to the effective date of termination, including fair and reasonable sums for overhead and profit on such Work;
 - 2. expenses sustained prior to the effective date of termination in performing services and furnishing labor, materials, or equipment as required by the Contract Documents in connection with uncompleted Work, plus fair and reasonable sums for overhead and profit on such expenses;
 - 3. all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) incurred in settlement of terminated contracts with Subcontractors, Suppliers, and others; and
 - 4. reasonable expenses directly attributable to termination.
- B. Contractor shall not be paid on account of loss of anticipated profits or revenue or other economic loss arising out of or resulting from such termination.

15.04 *Contractor May Stop Work or Terminate*

- A. If, through no act or fault of Contractor, (i) the Work is suspended for more than 90 consecutive days by Owner or under an order of court or other public authority, or (ii) Engineer fails to act on any Application for Payment within 30 days after it is submitted, or (iii) Owner fails for 30 days

to pay Contractor any sum finally determined to be due, then Contractor may, upon seven days written notice to Owner and Engineer, and provided Owner or Engineer do not remedy such suspension or failure within that time, terminate the Contract and recover from Owner payment on the same terms as provided in Paragraph 15.03.

- B. In lieu of terminating the Contract and without prejudice to any other right or remedy, if Engineer has failed to act on an Application for Payment within 30 days after it is submitted, or Owner has failed for 30 days to pay Contractor any sum finally determined to be due, Contractor may, seven days after written notice to Owner and Engineer, stop the Work until payment is made of all such amounts due Contractor, including interest thereon. The provisions of this Paragraph 15.04 are not intended to preclude Contractor from making a Claim under Paragraph 10.05 for an adjustment in Contract Price or Contract Times or otherwise for expenses or damage directly attributable to Contractor's stopping the Work as permitted by this Paragraph.

ARTICLE 16 – DISPUTE RESOLUTION

16.01 Methods and Procedures

- A. Either Owner or Contractor may request mediation of any Claim submitted to Engineer for a decision under Paragraph 10.05 before such decision becomes final and binding. The mediation will be governed by the Construction Industry Mediation Rules of the American Arbitration Association in effect as of the Effective Date of the Agreement. The request for mediation shall be submitted in writing to the American Arbitration Association and the other party to the Contract. Timely submission of the request shall stay the effect of Paragraph 10.05.E.
- B. Owner and Contractor shall participate in the mediation process in good faith. The process shall be concluded within 60 days of filing of the request. The date of termination of the mediation shall be determined by application of the mediation rules referenced above.
- C. If the Claim is not resolved by mediation, Engineer's action under Paragraph 10.05.C or a denial pursuant to Paragraphs 10.05.C.3 or 10.05.D shall become final and binding 30 days after termination of the mediation unless, within that time period, Owner or Contractor:
1. elects in writing to invoke any dispute resolution process provided for in the Supplementary Conditions; or
 2. agrees with the other party to submit the Claim to another dispute resolution process; or
 3. gives written notice to the other party of the intent to submit the Claim to a court of competent jurisdiction.

ARTICLE 17 – MISCELLANEOUS

17.01 Giving Notice

- A. Whenever any provision of the Contract Documents requires the giving of written notice, it will be deemed to have been validly given if:

1. delivered in person to the individual or to a member of the firm or to an officer of the corporation for whom it is intended; or
2. delivered at or sent by registered or certified mail, postage prepaid, to the last business address known to the giver of the notice.

17.02 *Computation of Times*

- A. When any period of time is referred to in the Contract Documents by days, it will be computed to exclude the first and include the last day of such period. If the last day of any such period falls on a Saturday or Sunday or on a day made a legal holiday by the law of the applicable jurisdiction, such day will be omitted from the computation.

17.03 *Cumulative Remedies*

- A. The duties and obligations imposed by these General Conditions and the rights and remedies available hereunder to the parties hereto are in addition to, and are not to be construed in any way as a limitation of, any rights and remedies available to any or all of them which are otherwise imposed or available by Laws or Regulations, by special warranty or guarantee, or by other provisions of the Contract Documents. The provisions of this Paragraph will be as effective as if repeated specifically in the Contract Documents in connection with each particular duty, obligation, right, and remedy to which they apply.

17.04 *Survival of Obligations*

- A. All representations, indemnifications, warranties, and guarantees made in, required by, or given in accordance with the Contract Documents, as well as all continuing obligations indicated in the Contract Documents, will survive final payment, completion, and acceptance of the Work or termination or completion of the Contract or termination of the services of Contractor.

17.05 *Controlling Law*

- A. This Contract is to be governed by the law of the state in which the Project is located.

17.06 *Headings*

- A. Article and paragraph headings are inserted for convenience only and do not constitute parts of these General Conditions.

DOCUMENT 00710**SPECIAL CONDITIONS**

SC-1 DESCRIPTION OF THE WORK: The work consists of clearing, earthwork, mass grading, installation of storm drainage, and erosion control improvements for approximately 23 acres.

SC-2 COMMENCEMENT AND COMPLETION OF WORK: The Contractor shall commence work within 15 days after Notice to Proceed is issued. Work shall be completed within 122 calendar days.

If the Contractor fails to prosecute the work with such diligence as will insure the completion of each portion of the work within the time shown on the above schedule, plus any extensions made in accordance with Article 12 of the General Conditions; and, if the Owner does not exercise reservations as set forth in Article 13 of the General Conditions, the Contractor shall continue the work in which event liquidated damages for the delay will be impossible to determine. In lieu thereof, liquidated damages in the amount of \$500.00 per each day of delay of the work until the work is completed.

SC-3 DRAWINGS: The work shall conform to the following drawings, all of which form a part of, and are included in, these specifications and are available in the office of Thomas & Hutton Engineering Co., 501 River Street, Suite 200 Greenville, SC 29601.

Sheet	Description	Job No.	P.E. Signature Date
CO	Cover Sheet	28283.0000	04/21/2020
G1.1	General Notes and Legend	28283.0000	04/21/2020
G1.2	Sheet Index	28283.0000	04/21/2020
EX1.1	Existing Conditions	28283.0000	04/21/2020
EX1.2	Existing Conditions	28283.0000	04/21/2020
DM1.1	Demolition Plan	28283.0000	04/21/2020
DM1.2	Demolition Plan	28283.0000	04/21/2020
EC0.1	Erosion Control Notes	28283.0000	04/21/2020
EC0.2	Erosion Control Notes	28283.0000	04/21/2020
EC1.1	Erosion Control Plan-Land Disturbance	28283.0000	04/21/2020
EC1.2	Erosion Control Plan-Land Disturbance	28283.0000	04/21/2020
EC2.1	Erosion Control Plan-Construction	28283.0000	04/21/2020
EC2.2	Erosion Control Plan-Construction	28283.0000	04/21/2020
EC3.1	Erosion Control Plan-Stabilization	28283.0000	04/21/2020
EC3.2	Erosion Control Plan-Stabilization	28283.0000	04/21/2020
EC4.1	Erosion Control Details	28283.0000	04/21/2020
EC4.2	Erosion Control Details	28283.0000	04/21/2020
EC4.3	Erosion Control Details	28283.0000	04/21/2020
C1.1	Grading and Drainage Plan	28283.0000	04/21/2020
C1.2	Grading and Drainage Plan	28283.0000	04/21/2020
C1.3	Drainage Profiles	28283.0000	04/21/2020
C1.4	Grading and Drainage Details	28283.0000	04/21/2020

- SC-4 LAYOUT OF WORK:** Control lines and master benchmarks will be furnished by the Owner. The Contractor will lay out work and will be responsible for all measurements in connection therewith.
- SC-5 OBSERVATIONS AND TESTS:** Before acceptance of the whole or any part of the work, it shall be subjected to observation and tests to determine it is in accordance with the plans and specifications. The Contractor will be required to maintain all work in a first-class condition for a 30-day operating period after the same has been completed as a whole and the Engineer has notified the Contractor in writing the work has been finished. The Owner shall pay for all initial testing. The Contractor shall pay for retesting of failed tests and shall engage a mutually acceptable laboratory or qualified individual to conduct the tests in accordance with these specifications. No portion of the work will be accepted until tests prove it has been satisfactorily completed. The Contractor shall give the Project Engineer or Project Representative a minimum of 48 hours notice for all required observations or tests.
- SC-6 BONDS:** The Performance Bonds in the amount of 100% of the contract amount and Payment Bonds in the amount of 100% of the contract amounts shall be furnished in accordance with Article 5 of the General Conditions.
- SC-7 CONTRACTOR'S AND SUBCONTRACTOR'S INSURANCE:** The Contractor shall not commence work under this contract until obtaining all the insurance required under this paragraph and such insurance has been accepted by the Owner, nor shall the Contractor allow any Subcontractor to commence work on a subcontract until the insurance required of the Subcontractor has been so obtained and accepted.
- a. Compensation and Employer's Liability Insurance: The Contractor shall take out and maintain during the life of the contract the statutory Worker's Compensation and Employer's Liability Insurance for all of its employees to be engaged in work on the project under the contract and, in case and such work is sublet, the Contractor should require the Subcontractor similarly to provide Worker's Compensation and Employer's Liability Insurance for all the latter's employees to be engaged in such work.
 - b. Bodily Injury Liability and Property Damage Liability Insurance: The Contractor shall take out and maintain during the life of the contract Bodily Injury Liability and Property Damage Liability Insurance to protect itself and any Subcontractor performing work covered by the contract from claims for damages or personal injury, including accidental death, as well as from claims for property damage, which may arise from operations under the contract, whether such operations be by the Contractor, Subcontractor, or anyone directly or indirectly employed by either of them and the amount of such insurance should be not less than:
 - (1) Bodily Injury Liability Insurance, in an amount not less than \$1,000,000.00 for injuries, including wrongful death to any one person and subject to the same limit for each person in an amount not less than \$2,000,000.00 on account of one accident. Contractual liability should be endorsed on the policy.

(2) Property Damage Insurance in an amount not less than \$1,000,000.00 for damages on account of any one accident, and in an amount not less than \$2,000,000.00 for damages on account of all accidents.

- c. Builder's Risk Insurance (Fire and Extended Coverage): The Contractor shall have adequate fire and standard extended coverage, with a company or companies acceptable to the Owner, in force on the project.

The provisions with respect to Builder's Risk Insurance shall in no way relieve the Contractor of its obligation of completing the work covered by the Contract.

- d. Proof of Carriage of Insurance: The Contractor shall furnish the Owner with certificates showing the type, amount, class of operations, effective dates, and date of expiration of policies. Such certificates shall contain substantially the following statement: "The insurance covered by this certification shall not be cancelled or materially altered, except after ten (10) days written notice has been received by the Owner."

SC-8 HOLD HARMLESS CLAUSE: The Contractor agrees to hold harmless, indemnify and defend the Owner and its agents, architects, engineers and employees from and against any and all claims, losses, damages, demands, causes of action and any an all related costs and expenses, of every kind and character, growing out of, incidental to, or resulting directly or indirectly from the Contractor's performance of the work described herein, whether such loss, damage, injury, or liability is contributed to by the negligence of the Owner, its agents, architects, engineers, or employees, except the Contractor shall have no liability for damages or the costs incidental thereto caused by the sole negligence of the Owner, its agents, architects, engineers, or employees. The Contractor will require any and all subcontractors to conform with the provisions of this clause prior to commencing any work and agrees to ensure this clause is in conformity with the insurance provisions of the contract.

SC-9 CONTRACTOR'S STATUS: It is agreed the Contractor shall occupy the status of an Independent Contractor and the Contractor's employees are not employees of the Owner.

SC-10 CONTRACTOR'S AFFIDAVIT: Upon completion of the work and prior to final payment and settlement of all sums due hereunder, Contractor will furnish to Owner a Contractor's Affidavit in the usual form submitted by Contractor under the laws of the State of South Carolina to the effect all bills for labor, materials and services in connection with said contract have been paid in full, acknowledging receipt of the contract price and averring there are no outstanding claims under said contract which could become a lien on the real estate arising out of said contract.

SC-11 RESIDENT PROJECT ENGINEER: The Owner reserves the right to furnish a Resident Project Engineer as deemed necessary to insure the Project quality control and conformance to Plans and Specifications, who will act as the Owner's Representative on the Project and will have the authority of the Engineer as set forth in the Contract Documents.

SC-12 BARRICADES, DANGER AND WARNING SIGNS: The Contractor shall install and maintain barricades, suitable and sufficient lights, danger signals, signs, and other traffic control devices and shall take all necessary precautions for the protection of the work and safety of the public. Lanes closed to traffic shall be protected by effective barricades, lighted during

hours of darkness. Suitable warning signs shall be provided to control, direct traffic, and warn pedestrians. Upon completion all barricades, signs and the like shall be removed.

SC-13 TOOLS, PLANT AND EQUIPMENT: If at any time before the commencement or during the progress of the work, tools, plant or equipment appear to the Engineer to be insufficient, inefficient or inappropriate to secure the quality of the work required or the proper rate of progress, the Engineer may order the Contractor to increase their efficiency, to improve their character, to augment their number, or to substitute new tools, plant, or equipment, as the case may be, and the Contractor must conform to such order; but a failure of the Engineer to demand such increase of efficiency, number, or improvement shall not relieve the Contractor of its obligation to secure the quality of work and the rate of progress necessary to complete the work within the time required by the contract to the satisfaction of the Owner.

SC-14 ACCIDENTS: The Contractor shall provide, at the site, such equipment and medical facilities as are necessary to supply first-aid service to anyone who may be injured in connection with the work. The Contractor must report in writing to the Engineer all accidents whatsoever arising out of, or in connection with, the performance of the work, whether on or adjacent to the site, which causes death, personal injury or property damages, giving full details and statement of witnesses. In addition, if death or serious injuries or serious damages are caused, the accident shall be reported immediately by telephone or messenger to both the Contractor and any subcontractor on account of any accident, the Contractor shall promptly report the facts to the Engineer, giving full details in writing of the claim. The Contractor shall advise its superintendent and foreman, who are on the site of the work, the name of the hospital and phone number and the name and phone number of the doctor to use in case of an accident.

SC-15 SANITARY PROVISIONS: The Contractor shall provide temporary sanitary facilities for the use of the workmen during the progress of the work. The sanitary facilities shall conform to the requirements of the County health Engineer. All facilities shall be removed at the completion of the contract.

SC-16 MODIFICATION OF QUANTITIES: The itemized quantities shall be considered by the Contractor as the quantities required to complete the work for the purpose of bidding. Should actual quantities required in the construction of the work be greater or less than the quantities shown on the items, an amount equal to the difference in quantities at the unit prices for the item will be added to or deducted from the contract price.

When itemized quantities are not given in the Proposal, the work shown on the plans or specified shall be considered by the Contractor to be included in the contract for the lump sum prices bid.

SC-17 RESPONSIBILITY REGARDING EXISTING UTILITIES AND STRUCTURES: The existence and location of underground utilities will be investigated and verified in the field by the Contractor before starting work. The Contractor shall call for underground utility locations. Underground utilities location service can be contacted at 1-888-721-7877 (SC). The location of all known interferences based on the best information available has been shown on the drawings, but this information may not be complete. Excavation in the vicinity of existing structures and utilities shall be carefully done by hand. The Contractor shall be held responsible for any damage to and for maintenance and protection of existing utilities and structures. The Contractor is responsible for coordinating with the utility companies any relocation, adjustment, or replacement of utility facilities.

SC-18 INTERRUPTION OF UTILITY SERVICE: The Contractor's operations shall be conducted to interfere as little as possible with utility services. Any proposed interruption by the Contractor must be accepted in advance by the Engineer.

SC-19 OMISSION: The drawings and specifications shall both be considered as a part of the contract. Any work and material shown in the one and omitted in the other, or described in the one and not shown in the other, or which may fairly be implied by both or either, shall be furnished and performed as though shown in both, in order to give a complete and first class job.

SC-20 MEASUREMENT AND PAYMENT: Measurement and payment shall be made for the units and at the lump sum contract prices shown on the Bid Schedule. Direct payment shall only be made for those items or work specifically listed in the proposal and the cost of any other work must be included in the contract price for the applicable items to which it relates.

SC-21 "OR EQUIVALENT," CLAUSE: Although the plans and specifications make reference to particular manufacturers and model numbers for various products, such reference is made only to establish function and quality of such products. If it is desired to use materials or equipment of trade names or of manufacturer's names that are different from those mentioned in the contract documents, information pertaining to such items must reach the hands of the Engineer at least 10 days prior to the date set for the opening of bids. The burden of proving equality of a proposed substitute to an item designated by trade name or by manufacturer's name in the contract document rests on the party submitting the request for acceptance. The written application for review of a proposed substitute must be accompanied by technical data that the party requesting review desires to submit in support of its application. The Engineer will give consideration to reports from reputable independent testing laboratories, verified experience records showing the reputation of the proposed product with previous users or any other written information that is reasonable in the circumstances. The application to the Engineer for review of a proposed substitute must be accompanied by a schedule setting forth in what respects the material or equipment submitted for consideration differs from the materials or equipment designated in the contract documents. The degree of proof required for acceptance of a proposed substitute as equivalent to a named product is the amount of proof necessary to convince the Engineer beyond all doubt. To be acceptable, a proposed substitute must, in addition, meet or exceed all express requirements of the contract documents.

If submittal is accepted by the Engineer, an addendum will be issued to all prospective bidders at least five days prior to the date set for the opening of bids.

The Engineer shall be the final judge on questions of similarity and equality.

SC-22 SAFETY AND HEALTH REGULATIONS: The Contractor shall comply with the Department of Labor Safety and Health Regulations for Construction promulgated under the Occupational Safety and Health Act of 1970 as amended through January 1, 2004 (PL 91-596) and under Section 107 of the Contract Work and Safety Standards Act (PL 91-54). The regulations are administered by the Department of Labor and the Contractor shall allow access to the project to personnel from that Department.

SC-23 RECORD DATA AND DRAWINGS: The Contractor shall keep accurate, legible records of the locations, types, and sizes of sanitary lines, service laterals, manholes, cleanouts, water lines, fittings, valves, hydrants, drainage pipes, drainage structures, and other related work

performed under this project. Where proposed and existing utilities cross, the Contractor shall measure and record the horizontal location and vertical separation between each crossing. Separation shall be measured between exteriors of pipes. On a set of project prints provided by the Owner, the Contractor shall prepare a set of "record" drawings from the data stated above.

The horizontal locations of all portions of items installed on this project shall be accurately tied down to features that are physical and visible, such as property corner markers and/or permanent type structures. Invert elevations of all manholes, storm sewers and structures, sanitary sewers and lift stations shall be clearly indicated. These "record" drawings shall be kept clean and dry and maintained in a current state with the progress of the work. If at any time, a copy of this plan or portion of it is requested by the Owner, such copy shall be made available within 24 hours after the request is made.

Before final acceptance of the completed installation and final payment by the Owner, the Contractor shall deliver to the Engineer, four sets of "Record" Drawings accurately depicting the horizontal and vertical as-built data described in the above paragraph. "Record" drawings for the items installed on this project shall be certified by a licensed surveyor registered in Georgia. The size of the drawings shall be 24" x 36". The "Record" drawings shall have a coordinate system based on the South Carolina State Plane Coordinate System, East Zone, North American Datum of 1983 (NAD83). Elevations shall be based on the North American Vertical Datum of 1988 (NAVD 88). All measurements and coordinates shown shall use the U.S. Survey flood definition. Coordinates shall be shown on all drainage structures, sanitary sewer manholes, storm manholes/boxes, valve boxes/vaults, valve manholes, valves, fire hydrants, fittings, and all other related work performed under this contract. Vertical data including but not limited to, structure and manhole frame and inverts, pipe inverts, lift station frame, inverts, control levels, bottom, site grading, and as-built grading shall be shown. In addition to the "Record" drawings, Contractor shall deliver to Engineer electronic AutoCAD (v. 14 or later) files of all the data described above on a CD-ROM.

SC-24 PROPERTY CORNERS: The Contractor shall be responsible for restoring any property corners or monuments disturbed during construction. They shall be restored by a professional surveyor registered in the State of South Carolina.

SC-25 VIDEO: A video showing existing site conditions shall be made by the Contractor prior to start of construction. Contractor shall provide Owner and Engineer a copy of the video. Contractor is encouraged to record any existing damaged facilities that could be questioned later by property owners. A written or recorded narrative shall be provided with the video. Engineer shall be notified 72 hours in advance making the video. Contractor is responsible for all costs associated with video and shall be considered a subsidiary part of the contract.

DOCUMENT 00815

SUPPLEMENTARY CONDITIONS

These Supplementary Conditions amend or supplement the Standard General Conditions of the Construction Contract (EJCDC C-700, 2007 Edition) and other provisions of the Contract Documents as indicated below. All provisions that are not so amended or supplemented remain in full force and effect.

SC-1 The terms used in these Supplementary Conditions which are defined in the Standard General Conditions of the Construction Contract (EJCDC C-700, 2007 Edition) have the meanings assigned to them in the General Conditions.

SC-2.05.A.4 Add the following new paragraph to the General Conditions after paragraph 2.05.A.3:

4. "A schedule of anticipated shipping dates for materials and equipment. It is intended that equipment and materials be so scheduled as to arrive at the job site just prior to time for installation to prevent excessive materials on hand for inventory and necessity for extensive storage facilities at the job site."

SC-5.04.B.7 Add the following new paragraph to the General Conditions after paragraph 5.04.B.6:

7. Bonding surety shall be located in the state in which the work is being performed.

The Contractor shall not commence work under this contract until it has obtained all the insurance required under this paragraph and such insurance has been accepted by the Owner, nor shall the Contractor allow any Subcontractor to commence work on its subcontract until the insurance required of the Subcontractor has been so obtained and accepted.

a. Compensation and Employer's Liability Insurance: The Contractor shall take out and maintain during the life of the contract, the statutory Worker's Compensation and Employer's Liability Insurance for all of its employees to be engaged in work on the project under the contract and, in case such work is sublet, the Contractor should require the Subcontractor similarly to provide Worker's Compensation and Employer's Liability Insurance for all the latter's employees to be engaged in such work.

b. Bodily Injury Liability and Property Damage Liability Insurance: The Contractor shall take out and maintain during the life of the contract, Bodily Injury Liability and Property Damage Liability Insurance. The policy shall protect Contractor and any Subcontractor performing work covered by the contract from claims for damages or personal injury, including accidental death, a well as from claims for property damage, which may arise from

operations under the contract, whether such operations be by Contractor, Subcontractor, or by anyone directly or indirectly employed by either of them and the amount of such insurance should be not less than:

- (1) Bodily Injury Liability Insurance, in an amount not less than \$1,000,000.00 for injuries, including wrongful death to any one person and subject to the same limit for each person in an amount not less than \$2,000,000.00 on account of one accident. Contractual liability should be endorsed on the policy.
- (2) Property Damage Insurance in an amount not less than \$1,000,000.00 for damages on account of any one accident, and in an amount not less than \$2,000,000.00 for damages on account of all accidents.

- c. Builder's Risk Insurance (Fire and Extended Coverage): The Contractor shall have adequate fire and standard extended coverage, with a company or companies acceptable to the Owner, in force on the project.

The provisions with respect to Builder's Risk Insurance shall in no way relieve the Contractor of its obligation of completing the work covered by the Contract.

- d. Proof of Carriage of Insurance: The Contractor shall furnish the Owner with certificates showing the type, amount, class of operations, effective dates, and date of expiration of policies. Such certificates shall contain substantially the following statement: "The insurance covered by this certification shall not be canceled or materially altered, except after 10 days written notice has been received by the Owner."

SC-6.02.B Add the following:

The Contractor shall provide in writing any requests to work on weekends. Requests shall be submitted to the Owner and Engineer for consideration a minimum of 48 hours prior to the requested weekend.

SC-6.05.E Replace with the following:

Engineer's Cost Reimbursement: Engineer will record Engineer's costs in evaluating a substitute proposed or submitted by Contractor pursuant to Paragraphs 6.05.A.2 and 6.05.B. Whether or not Engineer approves a substitute so proposed or submitted by Contractor, Contractor shall reimburse Owner and Owner shall pay Engineer for the reasonable charges of Engineer for evaluating each such proposed substitute. Contractor shall also reimburse Owner and Owner shall pay Engineer for the reasonable charges of Engineer for making changes in the Contract Documents (or in the provisions of any other direct contract with Owner) resulting from the acceptance of each proposed substitute.

SC-6.08 Add the following:

The Contractor shall not proceed until all encroachment permits, curb cut permits, highway crossing permits, and railroad crossing permits have been secured. Contact Owner to ascertain status of permits.

SC-6.09.D Add a new paragraph after paragraph 6.09.C of the General Conditions that reads as follows:

"D. The Contractor shall comply with the Department of Labor Safety and Health Regulations for Construction promulgated under the Occupational Safety and Health Act of 1970 as amended through January 1, 2004 (PL 91-596) and under Section 107 of the Contract Work and Safety Standards Act (PL 91-54). The regulations are administered by the Department of Labor and the Contractor shall allow access to the project to personnel from that Department.

The Bidder's attention is directed to the fact all applicable State laws, municipal ordinances, and the rules and regulations of all authorities having jurisdiction over construction of the project shall apply to the contract throughout and they will be deemed to be included in the contract the same as though herein written in full.

The Contractor shall keep fully informed of all laws, ordinances and regulations of Federal, State, City and County, in any manner affecting those engaged or employed in the work, or the materials used in the work, or in any way affecting the conduct of the work, and of all orders and decrees of bodies or tribunals having any jurisdiction or authority over same. Contractor shall at all times, observe and comply with all such existing and future laws, ordinances, and regulations."

SC-6.12.B Add a new paragraph after paragraph 6.12.A of the General Conditions that is to read as follows:

"B. Record Data Drawings:

1. The Contractor shall keep accurate, legible records of the elevations, locations, types, and sizes of sanitary sewage lines, service laterals, manholes, cleanouts, water lines, fittings, valves, hydrants, drainage pipes, drainage structures, and other related work performed under this project. Where proposed and existing utilities cross, the Contractor shall measure and record the horizontal location and vertical separation between each crossing. Separation shall be measured between exteriors of pipes. On a set of project prints provided by the Owner, the Contractor shall prepare a set of "record" drawings from the data stated above. The horizontal locations of all portions of items installed on this project shall be accurately tied down to [features that are physical and visible, such as property corner markers and/or permanent type structures] [the State Plane Coordinate System]. Invert and frame elevations of all manholes, storm sewers and structures, sanitary sewers and lift stations shall be clearly indicated.

These "record" drawings shall be kept clean and dry and maintained in a current state with the progress of the work. If at any time, a copy of this plan or portion of it is requested by the Owner, such copy shall be made available within 24 hours after the request is made.

2. Before final acceptance of the completed installation and before final payment by the Owner, the Contractor shall deliver to the Engineer a completed set of "record" drawings accurately depicting the data described above. The horizontal and vertical locations as shown on the "record" drawings for the items installed on this project shall be certified by a licensed surveyor, other than Thomas & Hutton, registered in the State in which the project is located. "Record" Drawings shall be submitted on a marked up set of project construction prints or electronically. Thomas & Hutton shall prepare original "record" drawings from the submitted data. When completed, Thomas & Hutton shall have the licensed surveyor stamp and sign the original "record" drawings before making copies available to the Owner or other appropriate agencies."

SC-6.13.A.3 Add the following:

"Safely guard the Owner's property from damages, injury, or loss in connection with this contract. Contractor shall at all times guard and protect its own work and all materials of every description both before and after being used in the work.

Contractor shall provide any enclosing or special protection from weather deemed necessary by Engineer without additional cost to the Owner. Partial payments under the contract will not relieve the Contractor from responsibility for protection of material, work, and property."

SC-9.02.C Add a new paragraph after paragraph 9.02.B of the General Conditions that is to read as follows:

"C. If at any time before the commencement or during the progress of the work, tools, plant or equipment appear to the Engineer to be insufficient, inefficient, or inappropriate to secure the quality of the work required or the proper rate of progress, the Engineer may order the Contractor to increase their efficiency, to improve their character, to augment their number, or to substitute new tools, plant or equipment as the case may be, and the Contractor must conform to such order; but a failure of the Engineer to demand such increase or efficiency, number, or improvements, shall not relieve the Contractor's obligation to secure the quality of work and the rate of progress necessary to complete the work within the time required by this contract to the satisfaction of the Owner."

SC-9.05 Add the following sentence at the end of paragraph 9.05 of the General Conditions:

"Owner and Engineer have the right to reject defective materials. Defective materials shall not be used in the work."

SC-13.03.A Add the following sentences to paragraph 13.03.A of the General Conditions:

“The Contractor will be required to maintain all work in a condition acceptable to the Engineer for a 30 day operating period after the same has been completed as a whole, and the Engineer has notified the Contractor in writing that the work has been finished. The Contractor shall give the Project Engineer or Project Representative a minimum of 48 hours notice for all required observations and tests.”

END OF SUPPLEMENTARY CONDITIONS

INDEX TO
SECTION 01011
SUMMARY OF WORK

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Section Includes	01011-1
1.2	Contract Description	01011-1
1.3	Work Required	01011-1
1.4	Contract Drawings	01011-1
1.5	Contract Technical Specifications	01011-2
1.6	Work Schedule [Optional]	01011-2

PART 2 – PRODUCTS

Not Used

PART 3 – EXECUTION

Not Used

SECTION 01011
SUMMARY OF WORK

PART 1 – GENERAL

1.1 SECTION INCLUDES

- A. Contract Description.
- B. Work required by Contract.
- C. Contract Drawings.
- D. Contract Technical Specifications.
- E. Work Schedule
- F. Owner Occupancy

1.2 CONTRACT DESCRIPTION

- A. Contract Type: 00506 – Agreement

1.3 WORK REQUIRED

- A. Consists of Contractor furnishing all labor, materials, tools, equipment and incidentals to complete the Work generally described below:

Work includes clearing, earthwork, rough grading, stormwater and erosion control improvements for approximately 23 acres.

- B. All work shall be performed as shown on the Drawings and as described in the Contract Documents and Technical Specifications.
- C. All work shall comply with standards described by the Department of Labor, Occupational Safety and Health Administration, 29 CFR Part 1926, Subpart P, latest revision.

1.4 CONTRACT DRAWINGS

Sheet	Description	Job No.	P.E. Signature Date
CO	Cover Sheet	28283.0000	04/21/2020
G1.1	General Notes and Legend	28283.0000	04/21/2020
G1.2	Sheet Index	28283.0000	04/21/2020
EX1.1	Existing Conditions	28283.0000	04/21/2020
EX1.2	Existing Conditions	28283.0000	04/21/2020
DM1.1	Demolition Plan	28283.0000	04/21/2020
DM1.2	Demolition Plan	28283.0000	04/21/2020

Sheet	Description	Job No.	P.E. Signature Date
EC0.1	Erosion Control Notes	28283.0000	04/21/2020
EC0.2	Erosion Control Notes	28283.0000	04/21/2020
EC1.1	Erosion Control Plan-Land Disturbance	28283.0000	04/21/2020
EC1.2	Erosion Control Plan-Land Disturbance	28283.0000	04/21/2020
EC2.1	Erosion Control Plan-Construction	28283.0000	04/21/2020
EC2.2	Erosion Control Plan-Construction	28283.0000	04/21/2020
EC3.1	Erosion Control Plan-Stabilization	28283.0000	04/21/2020
EC3.2	Erosion Control Plan-Stabilization	28283.0000	04/21/2020
EC4.1	Erosion Control Details	28283.0000	04/21/2020
EC4.2	Erosion Control Details	28283.0000	04/21/2020
EC4.3	Erosion Control Details	28283.0000	04/21/2020
C1.1	Grading and Drainage Plan	28283.0000	04/21/2020
C1.2	Grading and Drainage Plan	28283.0000	04/21/2020
C1.3	Drainage Profiles	28283.0000	04/21/2020
C1.4	Grading and Drainage Details	28283.0000	04/21/2020

1.5 CONTRACT TECHNICAL SPECIFICATIONS

SECTION NO.	TITLE
02070	Selective Demolition
02110	Site Clearing
02204	Earthwork
02210	Soil Erosion Control
02275	Rip Rap
02720	Storm Drainage
02902	Grassing

1.6 WORK SCHEDULE

- A. Construct Work in stages to accommodate Owner's requirements during the construction period, coordinate construction schedule and operations with Owner and Engineer.

PART 2 – PRODUCTS

Not used

PART 3 – EXECUTION

Not used

END OF SECTION

SECTION 01012

SOIL INVESTIGATION DATA FOR BIDDERS

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Description	01012-1
1.2	Soil Investigation Data	01012-1

PART 2 – PRODUCTS

See attached report.

PART 3 – EXECUTION

None in this Section

SECTION 01012**SOIL INVESTIGATION DATA FOR BIDDERS****PART 1 – GENERAL****1.1 DESCRIPTION**

- A. This section includes subsurface data logs for information only.

1.2 SOIL INVESTIGATION DATA

- A. Subsurface data logs are available for information only. Actual conditions may vary. If bidders are not satisfied with accuracy and completeness of all available data, they are at liberty to make borings or perform soil investigation work for their own use at their expense. If Contractor chooses to perform their own investigation, work shall be coordinated with the Engineer. Any results from Contractor's investigation shall be shared promptly with the Engineer. Owner reserves the right to share Contractor's investigation data with other potential bidders if information could affect bidding process.
- B. The boring logs and test results are for Contractor's information. Owner and Engineer assume no responsibility for the information.

PART 2 – PRODUCTS

See attached report.

PART 3 – EXECUTION

None this Section.

END OF SECTION

REPORT OF PRELIMINARY GEOTECHNICAL EXPLORATION

ICAR TN2, TN3, AND TN5
GREENVILLE, SOUTH CAROLINA

Prepared For:

Clemson University ICAR
5 Research Drive
Greenville, SC 29607

BLE Project Number J19-9630-87

July 30, 2019



**BUNNELL
LAMMONS
ENGINEERING**

July 30, 2019

Clemson University ICAR
5 Research Drive
Greenville, SC 29607

Attention: Mr. Mike Davis (john@clermson.edu)
Facilities Manager

Subject: **Report of Preliminary Geotechnical Exploration
ICAR TN2, TN3, and TN5
Greenville, South Carolina
BLE Project No. J19-9630-87**

Gentlemen:

Bunnell-Lammons Engineering, Incorporated (BLE) is pleased to present this report of preliminary geotechnical exploration for new technology centers at the existing International Center for Automotive Research (ICAR) in Greenville, South Carolina. This exploration was performed generally as described in Bunnell-Lammons Engineering (BLE) Proposal No. P19-0531 dated May 21, 2019. The exploration was authorized on May 22, 2019 by the signature of Mr. Mike Davis on our Proposal Acceptance Sheet.

Sincerely,

BUNNELL LAMMONS ENGINEERING INC.

Jason Jansante /KH

Jason C. Jansante, P.E.
Project Engineer
Registered, South Carolina #34614

William Mathews

William A. Mathews, P.E.
Chief Engineer
Registered, South Carolina #14039







TABLE OF CONTENTS

1.0	AUTHORIZATION.....	1
2.0	SCOPE OF EXPLORATION.....	1
3.0	PROJECT INFORMATION.....	1
4.0	FIELD EXPLORATION.....	1
5.0	SITE GEOLOGY.....	2
6.0	SUBSURFACE CONDITIONS.....	2
7.0	ANALYSIS AND PRELIMINARY DESIGN RECOMMENDATIONS.....	3
7.1	Foundations.....	3
7.2	Settlement.....	4
7.3	Lateral Earth Pressure.....	4
7.4	Seismic Site Classification.....	5
7.5	Grade Slabs.....	5
7.6	Secondary Design Considerations.....	5
8.0	PRELIMINARY CONSTRUCTION RECOMMENDATIONS.....	6
8.1	Clearing and Grubbing.....	6
8.2	Drainage.....	6
8.3	Difficult Excavation Conditions.....	6
8.4	Proofrolling.....	6
8.5	Engineered Fill.....	7
8.6	Slopes.....	7
9.0	BASIS OF PRELIMINARY RECOMMENDATIONS.....	8

Appendix

Appendix A	Figures
Appendix B	Field Exploration Procedures
Appendix C	Boring Logs
Appendix D	A Key to Soil Classifications



1.0 AUTHORIZATION

A preliminary geotechnical exploration for new technology centers TN2, TN3 and TN5 at the existing Clemson University International Center for Automotive Research (ICAR) in Greenville, South Carolina was performed generally as described in Bunnell-Lammons Engineering (BLE) Proposal No. P19-0531 dated May 21, 2019. The exploration was authorized on May 22, 2019 by the signature of Mr. Mike Davis on our Proposal Acceptance Sheet.

2.0 SCOPE OF EXPLORATION

This report details the findings of the preliminary geotechnical exploration performed for the proposed technology centers at the ICAR campus in Greenville, South Carolina (reference Figure 1 in Appendix A). The intent of this exploration was to evaluate the subsurface soil and groundwater conditions at the site and provide detailed geotechnical recommendations for design of the foundations, floor slabs and associated project elements. We have also included a discussion of secondary design considerations and provided geotechnical related construction recommendations.

3.0 PROJECT INFORMATION

The following project information was provided in a meeting between Mr. Davis, Mr. Scott May of LS3P, and our Mr. Jim Ernst. The existing ICAR campus consists of five separate Technology Neighborhoods identified as TN1 through TN5. We have been requested to conduct a preliminary geotechnical exploration in three of the Technology Neighborhoods that are currently undeveloped (TN2, TN3, and TN5). The purpose of the preliminary geotechnical exploration is to collect limited subsurface data to facilitate future development.

For the purpose of this preliminary exploration, we have assumed that the planned development in each Technology Neighborhood will include buildings with maximum individual column and continuous wall loads that will not exceed 250 kips and 5 kips per linear foot, respectively. We have also assumed that site grading operations will result in a maximum of approximately 10 feet of earthwork cut or fill within any given building footprint.

4.0 FIELD EXPLORATION

The site was explored by drilling thirteen soil test borings (ASTM D1586) at the technology neighborhoods noted in the table below. The approximate boring locations are shown on the attached Boring Location Plan (reference Figure 2 in Appendix A). Boring Logs are presented as Appendix C. The borings were located in the field by our Mr. John Horner by referencing the provided site plan and identifiable site landmarks. The boring locations shown in Appendix A should be considered approximate. A description of our field procedures is also included as Appendix B.

Project Area	Borings	Boring Depth (ft.)
TN2	B-1 through B-5	20 - 50
TN3	B-6 through B-9	20 - 43
TN5	B-10 through B-13	9 - 19

5.0 SITE GEOLOGY

The project site is located in the Piedmont Physiographic Province, an area underlain by ancient igneous and metamorphic rocks. The virgin soils encountered in this area are the residual product of in-place chemical weathering of the rock. In areas not altered by erosion, previous construction or other human activities, the typical residual soil profile consists of clayey soils near the surface where soil weathering is more advanced. The near surface clayey soils are typically underlain by sandy silts and silty sands.

The boundary between soil and rock is not sharply defined. This transitional zone is termed partially weathered rock (PWR) and is normally found overlying the parent bedrock. For engineering purposes, partially weathered rock is defined as residual material with a standard penetration resistance of at least 100 blows per foot. Weathering is facilitated by fractures, joints, and the presence of less resistant rock types. As a result, the profile of the partially weathered rock and hard rock is quite irregular and erratic, even over short horizontal distances. Also, it is not unusual to find lenses and boulders of hard rock and zones of partially weathered rock within the soil mantle, well above the general bedrock level.

6.0 SUBSURFACE CONDITIONS

Beneath a surficial layer of topsoil (3 to 8 inches), the borings drilled for this exploration encountered residual soils, partially weathered rock, and hard rock (as indicated by auger refusal). The residual soils consist generally of firm to dense clayey sand (SC) and firm to very dense silty sand (SM). Some of the soils were noted to be micaceous. The letters in parentheses represent a visual classification of the soils in accordance with the Unified Soil Classification System. A key to symbols and classification is included as Appendix D.

Intermittent to continuous partially weathered rock, hard rock (as indicated by auger refusal) and groundwater were noted in the borings as indicated in the following table.

Boring No.	Location	Depth to PWR ⁽¹⁾ (feet)	Depth to Auger Refusal (feet)	Depth to Groundwater (feet)	
				TOB ⁽²⁾	After 24 hours
B-1	TN2	5.5 (i)	NE	NE	NE
B-2		37 (i)	NE	30	28.3
B-3		NE ⁽³⁾	NE	NE	NE
B-4		5.5 (i)	NE	NE	NE
B-5		NE	NE	NE	NE
B-6	TN3	12 (i)	NE	NE	NE
B-7		17 (c)	NE	NE	NE
B-8		3 (i)	43	32	30.8
B-9		NE	NE	NE	NE
B-10	TN5	8 (i)	19	NE	NE
B-11		Surface (i)	9	NE	NE
B-12		3 (i)	13	NE	NE
B-13		NE	NE	NE	NE

Notes:

1. Partially weathered rock (PWR) is either intermittent (i) or continuous (c) below this depth
2. TOB = Time of Boring
3. NE = Not Encountered

It should be noted that groundwater levels may fluctuate several feet with seasonal and rainfall variations and with changes in the water level in adjacent drainage features. Normally, the highest groundwater levels occur in late winter and spring and the lowest levels occur in late summer and fall.

The above descriptions provide a general summary of the subsurface conditions encountered. The Boring Logs included as Appendix C contain detailed information recorded at each boring location. The Boring Logs represent our interpretation of the field logs based on engineering examination of the field samples. The lines designating the interfaces between various strata represent approximate boundaries and the transition between strata may be gradual. It should be noted that the soil conditions will vary between boring locations.

7.0 ANALYSIS AND PRELIMINARY DESIGN RECOMMENDATIONS

7.1 Foundations

Based on the boring data and our experience with similar soil conditions, the residual soils encountered at each of the Technology Neighborhoods are suitable for shallow foundation support of the proposed construction. Satisfactory performance of the shallow foundations is subject to the criteria and site preparation recommendations contained in this report.

Foundations bearing in the residual soils may be sized for an allowable bearing pressure of 3,000 pounds per square foot (psf). Considerably higher allowable foundation bearing pressures are available in some of the residual soils and partially weathered rock. An evaluation of the potential use of higher bearing pressures should be performed as part of a detailed geotechnical exploration once the building location(s) and foundation loads for each Technology Neighborhood are developed. Foundations bearing on new engineered fill compacted to at least 95 percent of the standard Proctor maximum dry density (ASTM D698), as recommended later in this report, may also be sized for an allowable bearing pressure of 3,000 psf.

We recommend that the minimum widths for individual column and continuous wall footings be 24 and 18 inches, respectively. The minimum widths will provide a margin of safety against a local or punching shear failure of the foundation soils. Footings should bear at least 18 inches below final grade to provide frost protection and protective embedment. We recommend that walls be provided with movement joints to accommodate some possible differential settlement.

Exposure to the environment may weaken the soils at the foundation bearing level if the foundation excavations remain open for long periods of time. Therefore, we recommend that once each foundation excavation is extended to final grade, the foundation be constructed as soon as possible to minimize the potential damage to bearing soils. The foundation bearing area should be level or benched and free of loose soil, ponded water and debris. Foundation concrete should not be placed on soils that have been disturbed by seepage. If the bearing soils are softened by surface water intrusion or exposure, the softened soils must be removed from the foundation excavation bottom prior to placement of concrete. If the excavation must remain open overnight or if rainfall becomes imminent while the bearing soils are exposed, we recommend that a 2 to 4-inch thick "mud-mat" of "lean" (2,000 psi) concrete be placed on the bearing soils for protection before the placement of reinforcing steel.

To verify that the soils encountered in footing excavations are similar to those encountered by the soil test borings, we recommend that foundation excavations be examined. Part of this examination should include checking the bearing soils with a dynamic cone penetrometer performed by an experienced engineering technician working under the direction of the geotechnical engineer.

7.2 Settlement

We conducted preliminary settlement estimates assuming conventional shallow foundations were used to support the structures and the sustained loading on the individual column foundations are equal to 80 percent of the estimated total load. We have estimated a preliminary maximum total column load of 250 kips, which would result in a sustained load of 200 kips. Based on these assumptions and assuming foundations are designed and constructed in accordance with the recommendations presented in this report, we estimate the total foundation settlement to be approximately 1 inch or less. Maximum differential settlement between adjacent similarly loaded foundations is estimated to be approximately $\frac{3}{4}$ inch or less. Please note that these settlement estimates are based on the limited project information available at the time this preliminary exploration was performed. Detailed settlement estimates should be developed as part of additional geotechnical exploration that will be required for each Technology Neighborhood once project details are developed.

7.3 Lateral Earth Pressure

Retaining walls must be capable of resisting the lateral earth pressures that will be imposed on them. Walls which will be permitted to rotate at the top, such as cantilever retaining walls, may be designed to resist the active earth pressure. The active earth pressure coefficient is designated as K_a . Typically, a top rotation of about 1 inch per 10 feet height of wall is sufficient to develop active pressure conditions in soils similar to those encountered at the site. We recommend a K_a value of 0.33 for the soils encountered at this site when placed in accordance with the requirements for engineered fill.

Walls which will be prevented from rotating such as laterally braced retaining walls should be designed to resist the at-rest lateral earth pressure. The at-rest earth pressure coefficient is designated as K_o . We recommend a K_o value of 0.5 for the soils encountered at this site when placed in accordance with the requirements for engineered fill.

The passive earth pressure may be considered as the pressure exerted on the side of a foundation which aids in resisting sliding of the foundation. The passive earth pressure coefficient is designated as K_p . Friction resistance along the base of the foundation may also be used to resist sliding. The coefficient of frictional resistance is designated as f_s . We recommend a f_s value of 0.4 and a K_p value of 3.0 for the soils encountered at this site. Consideration should be given to dividing the passive earth pressure coefficient by a safety factor of 2 to limit the amount of lateral deformation required to mobilize the passive resistance. Published documentation¹ indicates that very little horizontal compression (approximately 0.5% relative to wall height) is required to develop one-half of the available passive resistance, hence the suggested safety factor of 2. However, depending on soil type and relative density it may take 2 to 15% horizontal compression to develop the full passive resistance.

The values presented above assume that the ground surface is level. Sloping backfill (or sloping soil surfaces in front of a footing when considering passive resistance) will dramatically influence the earth pressure coefficients. Bunnell-Lammons Engineering should be consulted concerning applicable earth pressure coefficients where sloping soil surfaces may be present.

The compacted mass unit weight of the backfill soil, which we estimate to be approximately 125 pcf, should be used with the earth pressure coefficients to calculate lateral earth pressures. Lateral pressure arising from

¹ *Soil Mechanics* by T. William Lambe and Robert V. Whitman; Massachusetts Institute of Technology; 1969; p.165.

surcharge loading, earthquake loading, and groundwater should be added to the above soil earth pressures to determine the total lateral pressures which the walls must resist. Where practical, we recommend that retaining walls and other below grade walls incorporate filtered gravity drainage systems to prevent the buildup of excess hydrostatic pressures behind the walls. In addition, transient loads imposed on the walls by construction equipment during backfilling should be taken into consideration during design and construction. Excessively heavy grading equipment should not be allowed within about 5 feet horizontally of the walls.

7.4 Seismic Site Classification

Geotechnical seismic design requirements are detailed in the International Building Code (IBC). The site class is determined based on the average soil/rock properties within the upper 100 feet. It was beyond the scope of this preliminary exploration to extend borings to a depth of 100 feet. However, partially weathered rock and hard rock was encountered in some of the borings drilled for this preliminary exploration. Based on our knowledge of the area and the conditions encountered in the soil test borings, we recommend that the structures be preliminarily designed for a seismic site class as indicated in the following table.

Location	Seismic Site Class
TN2	D
TN3	C
TN5	C

The seismic site class values indicated in the previous table should be utilized for preliminary planning purposes only. Supplemental geotechnical exploration will be required once the proposed development in each Technology Neighborhood is finalized. Building location/orientation as well as the site grading plans developed for each site will influence the seismic site classification that should be used for final design.

7.5 Grade Slabs

The grade slabs may be soil supported assuming that the site(s) is prepared in accordance with the preliminary recommendations in this report. The grade slab should be jointed around columns and along footing supported walls so that the slab and foundations can settle differentially without damage. This jointing is not required when slabs and foundations are cast as a single unit (i.e. thickened edge foundations). If slab thickness permits, joints containing dowels or keys may be used in the slab to permit movement between parts of the slab without cracking or sharp vertical displacements.

Floor slabs supported on grade which will be carpeted, tiled, painted or receive some other covering or sealant should incorporate a vapor barrier. The vapor barrier should be installed in accordance with the manufacturer's recommendations.

7.6 Secondary Design Considerations

The following items are presented for your consideration. These items are known to generally enhance performance of structural and pavement systems.

- Roof drainage should be collected by a system of gutters and downspouts and directed away from all structures.
- Sidewalks should be sloped so that water drains away from the structures.
- Site grading and paving should result in positive drainage away from the structures. Water should not be allowed to pond around the structures or in such locations that would lead to

saturation of pavement subgrade materials. A minimum slope of approximately ¼ to ½-inch per foot should provide adequate drainage.

- Backfill for utility lines should be placed in accordance with the requirements for engineered fill to minimize the potential for differential settlement.

8.0 PRELIMINARY CONSTRUCTION RECOMMENDATIONS

8.1 Clearing and Grubbing

All existing construction debris, topsoil, vegetation, disturbed soils, limbs, stumps and surface soils containing organic matter or other deleterious materials should be stripped from within the proposed building areas. Topsoil and organic soils may be stockpiled for later use in areas to be landscaped. Stumps and other deleterious material should be disposed of offsite or in areas of the site that will not be developed. Future construction of buildings or pavement in areas containing limbs or stumps, organic soils, burn pit residue or other deleterious materials will first require that these materials be removed.

8.2 Drainage

Groundwater was not encountered within the expected excavation depths. However, it should be noted that groundwater levels may fluctuate several feet with seasonal and rainfall variations and with changes in the water level in adjacent drainage features. Normally, the highest groundwater levels occur in late winter and spring and the lowest levels occur in late summer and fall. The contractor should be prepared to promptly remove any surface water or groundwater from the construction area. This has been done effectively on past jobs by means of gravity ditches and pumping from filtered sumps.

8.3 Difficult Excavation Conditions

Any very dense soil and partially weathered rock such as that encountered in the borings may present some difficulty in excavating during construction. Due to its typically erratic surface, such material may be encountered during site grading in other portions of the site as well. Heavy excavating equipment with ripping tools will likely be required to remove much of this material. Confined excavations (footings, utility trenches, etc.) in partially weathered rock may require ripping tools and pneumatic hammers. However, it is often extremely difficult to excavate partially weathered rock without blasting, especially in confined excavations such as utility trenches and footings. The ease of excavation depends on the quality of grading equipment, skill of the equipment operators, and geologic structure of the material itself such as the direction of bedding, planes of weakness, and spacing between discontinuities. Weathered rock or rock that cannot be penetrated by the mechanical auger will normally require blasting to loosen it for removal.

Based on the subsurface conditions encountered in the borings and depending on the planned finished grade elevations, it should be expected that difficult excavation conditions such as those described above will be more likely in TN5 than the other Technology Neighborhoods.

8.4 Proofrolling

After stripping and rough excavation grading, we recommend that areas to provide support for the foundations, floor slab, engineered fill and pavement be carefully inspected for soft surficial soils and proofrolled with a 25 to 35-ton, four-wheeled, rubber-tired roller or similar approved equipment. The proofroller should make at least four passes over each location, with the last two passes perpendicular to the first two where practical.

Any areas which wave, rut, or deflect excessively and continue to do so after several passes of the proofroller should be excavated to firmer soils. The excavated areas should be backfilled in thin lifts with engineered fill. The proofrolling and excavating operations should be carefully monitored by an experienced engineering technician working under the direction of the geotechnical engineer. Proofrolling should not be performed when the ground is frozen or wet from recent precipitation.

8.5 Engineered Fill

All fill used for raising site grade or for replacement of material that is undercut should be uniformly compacted in thin lifts to at least 95 percent of the standard Proctor maximum dry density (ASTM D698). In addition, at least the upper 12 inches of subgrade fill beneath pavements and floor slabs should be compacted to at least 98 percent of the maximum dry density. We recommend that the fill be placed and compacted at a moisture content within three percent of the standard Proctor optimum moisture content.

Based on our visual examination and experience with similar soil types, the on-site soil appears to be suitable for use as engineered fill with proper moisture adjustment. In general, soils having a Plasticity Index (PI) greater than 30 (less than 15 is preferable) should not be used for fill. Soils used for engineered fill should be reasonably free from organics (less than 3% organics by weight) and should exhibit a standard Proctor maximum dry density greater than 90 pcf.

Before filling operations begin, representative samples of each proposed fill material should be collected and tested to determine the compaction and classification characteristics. The maximum dry density and optimum moisture content should be determined. Once compaction begins, a sufficient number of density tests should be performed by an experienced engineering technician working under the direction of the geotechnical engineer to measure the degree of compaction being obtained. Existing slopes steeper than 6:1 (horizontal:vertical) should be benched prior to placement of engineered fill such that the fill is placed in horizontal layers and keyed into the existing slopes.

The edge of engineered fill extending above surrounding grade should extend horizontally beyond the outside edge of the building foundations at least 10 feet or a distance equivalent to the height of fill to be placed, whichever is greater, before sloping. The edge of fill should extend at least 5 feet beyond paved areas. Fill slope surfaces should be protected from erosion by grassing or some other means.

The surface of compacted subgrade soils can deteriorate and lose its support capabilities when exposed to environmental changes and construction activity. Deterioration can occur in the form of freezing, formation of erosion gullies, extreme drying, exposure for a long period of time or rutting by construction traffic. We recommend that the surfaces of floor slab and pavement subgrades that have deteriorated or softened be recompacted prior to construction of the floor slab or pavement. Additionally, any excavations through the subgrade soils (such as utility trenches) should be properly backfilled in compacted lifts. Recompanction of subgrade surfaces and compaction of backfill should be checked with a sufficient number of density tests to determine if adequate compaction is being achieved.

8.6 Slopes

Confined temporary excavations such as for utility installation or below-grade wall construction should conform to OSHA regulations. For permanent slopes which are not confined, our experience suggests that excavation side slopes through the existing soil overburden at the site should be laid back at a 2H:1V (horizontal to vertical) slope or flatter. Permanent fill slopes placed on a suitable foundation should be constructed at 2.5:1, or flatter. Fill slopes should be adequately compacted. Cut and fill slope surfaces should




be protected from erosion by grassing or other means. Permanent slopes of 3:1 or flatter may be desirable for mowing.

9.0 BASIS OF PRELIMINARY RECOMMENDATIONS

Our preliminary evaluation of foundation support conditions has been based on our understanding of the project information and data obtained in our exploration as well as our experience on similar projects. The general subsurface conditions utilized in our foundation evaluation have been based on interpolation of the subsurface data between the widely spaced borings. Subsurface conditions between the borings will differ. The project information provided for this preliminary exploration is conceptual in nature and it is expected to change during development of detailed project information. Additional site exploration and engineering analysis will be required to develop detailed geotechnical design and construction recommendations. The discovery of any site or subsurface conditions during construction which deviate from the data obtained in this exploration should be reported to us for our evaluation. The assessment of site environmental conditions for presence of pollutants in the soil, rock and groundwater of the site was beyond the scope of this exploration. Soil cuttings used as backfill in boreholes will settle over time resulting in a depression at the surface. It is beyond the scope of our services to return to the site to repair boreholes that have exhibited settlement of the backfill soils.

APPENDIX A
Figures




REFERENCES:
 USGS TOPOGRAPHIC MAP, 7.5
 MINUTE SERIES, MAULDIN. SC.
 QUADRANGLE 2017

DRAWN: K LW	DATE: 7-12-19
CHECKED: GFS	CAD: CLEMSONICAR-01SLM
APPROVED: WAM	JOB NO: J19-9630-01

BLE | **BUNNELL
 LAMMONS
 ENGINEERING**
 6004 Ponders Court, Greenville, SC 29615
 Phone: (864) 288-1265 Fax: (864) 288-4430

SITE LOCATION MAP
 CLEMSON ICAR
 GREENVILLE, SOUTH CAROLINA



LEGEND:
 APPROXIMATE BORING LOCATION B-1

REFERENCE:
 GOOGLE EARTH IMAGE DATED 6-3-2018.

DRAWN:	KLW	DATE:	7-12-19
CHECKED:	GFS	CAD:	CLEMSONICAR-01BLP
APPROVED:	WAM	JOB NO:	J19-9630-87

BLE | **BUNNELL LAMMONS ENGINEERING**
 6004 Ponders Court, Greenville, SC 29615
 Phone: (854) 288-1265 Fax: (864) 288-4430

FIGURE
 BORING LOCATION PLAN
 CLEMSON ICAR
 GREENVILLE, SOUTH CAROLINA
2

APPENDIX B
Field Exploration Procedures



Field Exploration Procedures

The borings were made by mechanically twisting a continuous flight steel auger into the soil. Soil sampling and penetration testing were performed in general accordance with ASTM D 1586. At assigned intervals, soil samples were obtained with a standard 1.4-inch I. D., 2-inch O. D., split-tube sampler. The sampler was first seated 6 inches to penetrate any loose cuttings, and then driven an additional 12 inches with blows of a 140-pound hammer falling 30 inches. The number of hammer blows required to drive the sampler the final 12 inches was recorded and is designated the "standard penetration resistance." The penetration resistance, when properly evaluated, is an index to the strength of the soil and foundation supporting capability.

Representative portions of the soil samples, thus obtained, were placed in glass jars and transported to the laboratory. In the laboratory, the samples were examined by a geotechnical engineer to verify the field classifications of the driller. Test Boring Records are attached, showing the soil descriptions and penetration resistance.

APPENDIX C
Boring Logs




BORING NO. B-1

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN2
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: AFTER 24 HOURS: CAVING>

PROJECT NO.: J19-9630-87
 START: 6-20-19 END: 6-20-19
 ELEVATION: _____
 LOGGED BY: I. Brafford



GEOI_NOWELL_9630-87.GPJ 7/29/19




BORING NO. B-2

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN2
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: ∇ 30 AFTER 24 HOURS: ∇ 28.3 CAVING>

PROJECT NO.: J19-9630-87
 START: 6-20-19 END: 6-20-19
 ELEVATION: _____
 LOGGED BY: I. Brafford



GEOI_NOWELL 9630-87.GPJ 7/29/19



BORING NO. B-2

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
CLIENT: Clemson University ICAR
LOCATION: Greenville, South Carolina - TN2
DRILLER: Landprobe, J. Stewart
DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
DEPTH TO - WATER> INITIAL: ∇ 30 AFTER 24 HOURS: ∇ 28.3 CAVING>

PROJECT NO.: J19-9630-87
START: 6-20-19 END: 6-20-19
ELEVATION: _____
LOGGED BY: I. Brafford

ELEVATION/ DEPTH (FT)	SOIL DESCRIPTION	SOIL TYPE	SAMPLES	STANDARD PENETRATION RESULTS BLOWS/FOOT															
				2	5	10	20	30	40	50	70	90							
	PARTIALLY WEATHERED ROCK sampled as brown and gray, micaceous, silty, fine to medium SAND																		
45	Firm to very firm, brown and gray, silty, fine to medium SAND																		
50	Boring terminated at 50 feet below ground surface. Groundwater encountered at 30 feet at time of drilling and 28.3 feet after 24 hours.																		
55																			
60																			
65																			
70																			
75																			

GEOI_NOWELL_9630-87.GPJ 7/29/19




BORING NO. B-3

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN2
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: AFTER 24 HOURS: CAVING>

PROJECT NO.: J19-9630-87
 START: 6-20-19 END: 6-20-19
 ELEVATION: _____
 LOGGED BY: I. Brafford



GEOI_NOWELL_9630-87.GPJ 7/29/19




BORING NO. B-4

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN2
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: ∇ AFTER 24 HOURS: ∇ CAVING>

PROJECT NO.: J19-9630-87
 START: 6-20-19 END: 6-20-19
 ELEVATION: _____
 LOGGED BY: I. Brafford



GEOI_NOWELL_9630-87.GPJ 7/29/19




BORING NO. B-5

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN2
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: ∇ AFTER 24 HOURS: ∇ CAVING: \otimes

PROJECT NO.: J19-9630-87
 START: 6-20-19 END: 6-20-19
 ELEVATION: _____
 LOGGED BY: I. Brafford



GEOI_NOWELL_9630-87.GPJ 7/29/19




BORING NO. B-6

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN3
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: AFTER 24 HOURS: CAVING>

PROJECT NO.: J19-9630-87
 START: 6-19-19 END: 6-19-19
 ELEVATION: _____
 LOGGED BY: I. Brafford



GEOI_NOWELL_9630-87.GPJ 7/29/19




BORING NO. B-7

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN3
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: ∇ AFTER 24 HOURS: ∇

PROJECT NO.: J19-9630-87
 START: 6-19-19 END: 6-19-19
 ELEVATION: _____
 LOGGED BY: I. Brafford

CAVING>



GEOT_NOWELL_9630-87.GPJ 7/29/19




BORING NO. B-8

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN3
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4

PROJECT NO.: J19-9630-87
 START: 6-19-19 END: 6-19-19
 ELEVATION: _____
 LOGGED BY: I. Brafford

DEPTH TO - WATER> INITIAL: ∇ 32 AFTER 24 HOURS: ∇ 30.8 CAVING>



GEOT_NOWELL_9630-87.GPJ 7/29/19



BORING NO. B-8

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN3
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: ∇ 32 AFTER 24 HOURS: ∇ 30.8 CAVING> ⊗

PROJECT NO.: J19-9630-87
 START: 6-19-19 END: 6-19-19
 ELEVATION: _____
 LOGGED BY: I. Brafford

ELEVATION/ DEPTH (FT)	SOIL DESCRIPTION	SOIL TYPE	SAMPLES	STANDARD PENETRATION RESULTS BLOWS/FOOT															
				2	5	10	20	30	40	50	70	90							
	PARTIALLY WEATHERED ROCK sampled as brown and gray, micaceous, silty, fine to medium SAND																		
45	Auger refusal at 43 feet below ground surface. Groundwater encountered at 32 feet at time of drilling and 30.8 feet after 24 hours.																		
50																			
55																			
60																			
65																			
70																			
75																			

GEOI_NOWELL_9630-87.GPJ 7/29/19



BORING NO. B-9

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN3
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: ∇ AFTER 24 HOURS: ∇

PROJECT NO.: J19-9630-87
 START: 6-19-19 END: 6-19-19
 ELEVATION: _____
 LOGGED BY: I. Brafford

CAVING>

ELEVATION/ DEPTH (FT)	SOIL DESCRIPTION	SOIL TYPE	SAMPLES	STANDARD PENETRATION RESULTS BLOWS/FOOT																
				2	5	10	20	30	40	50	70	90								
0 - 4	4 inches - TOPSOIL Firm to dense, brown and orange, slightly micaceous, silty, fine to medium SAND with trace clay - (residuum)		7																	
4 - 5	absent clay		8																	
5 - 10	trace partially weathered rock fragments, micaceous		12																	
10 - 15	brown and tan		11																	
15 - 20	red and brown		14																	
20 - 21	Boring terminated at 20 feet below ground surface. No groundwater encountered at time of boring.		19																	
21 - 22			9																	
22 - 23			7																	
23 - 24			5																	
24 - 25			7																	
25 - 26			16																	
26 - 27			3																	
27 - 28			7																	
28 - 29			11																	

GEOI_NOWELL_9630-87.GPJ 7/29/19




BORING NO. B-10

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN5
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: ∇ AFTER 24 HOURS: ∇

PROJECT NO.: J19-9630-87
 START: 6-21-19 END: 6-21-19
 ELEVATION: _____
 LOGGED BY: I. Brafford

CAVING>



GEOI_NOWELL_9630-87.GPJ 7/29/19



BORING NO. B-11

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN5
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: ∇ AFTER 24 HOURS: ∇

PROJECT NO.: J19-9630-87
 START: 6-21-19 END: 6-21-19
 ELEVATION: _____
 LOGGED BY: I. Brafford

CAVING>

ELEVATION/ DEPTH (FT)	SOIL DESCRIPTION	SOIL TYPE	SAMPLES	STANDARD PENETRATION RESULTS BLOWS/FOOT															
				2	5	10	20	30	40	50	70	90							
	4 inches - TOPSOIL																		
	PARTIALLY WEATHERED ROCK sampled as tan and white, slightly micaceous, silty, fine to medium SAND with trace organics			50/4"															50/4"
5	Loose, brown, silty, fine to medium SAND with partially weathered rock fragments - (residuum)			4															
				3															
				2															
	PARTIALLY WEATHERED ROCK sampled as red and brown, clayey, fine to medium SAND with trace silt			6															
				5															50/5"
				50/5"															
10	Auger refusal 9 feet below ground surface. No groundwater encountered at time of boring.																		
15																			
20																			
25																			
30																			
35																			




BORING NO. B-12

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN5
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: ▽ AFTER 24 HOURS: ▽

PROJECT NO.: J19-9630-87
 START: 6-21-19 END: 6-21-19
 ELEVATION: _____
 LOGGED BY: I. Brafford

CAVING>






BORING NO. B-13

**BUNNELL-LAMMONS
ENGINEERING, INC.**
GEOTECHNICAL AND ENVIRONMENTAL
CONSULTANTS

PROJECT: Clemson ICAR
 CLIENT: Clemson University ICAR
 LOCATION: Greenville, South Carolina - TN5
 DRILLER: Landprobe, J. Stewart
 DRILLING METHOD: CME 750 Hollow Stem Auger 3 1/4
 DEPTH TO - WATER> INITIAL: AFTER 24 HOURS:

PROJECT NO.: J19-9630-87
 START: 6-21-19 END: 6-21-19
 ELEVATION: _____
 LOGGED BY: I. Brafford

CAVING>



GEOI_NOWELL_9630-87.GPJ 7/29/19

APPENDIX D
A Key to Soil Classification

KEY TO SOIL CLASSIFICATIONS AND CONSISTENCY DESCRIPTIONS

**BUNNELL-LAMMONS ENGINEERING, INC.
GREENVILLE, SOUTH CAROLINA**

Penetration Resistance* Blows per Foot

SANDS

0 to 4
5 to 10
11 to 20
21 to 30
31 to 50
over 50

Relative Density

Very Loose
Loose
Firm
Very Firm
Dense
Very Dense

Particle Size Identification

Boulder: Greater than 300 mm
Cobble: 75 to 300 mm
Gravel:
Coarse - 19 to 75 mm
Fine - 4.75 to 19 mm
Sand:
Coarse - 2 to 4.75 mm
Medium - 0.425 to 2 mm
Fine - 0.075 to 0.425 mm
Silt & Clay: Less than 0.075 mm

Penetration Resistance* Blows per Foot

SILTS and CLAYS

0 to 2
3 to 4
5 to 8
9 to 15
16 to 30
31 to 50
over 50

Consistency

Very Soft
Soft
Firm
Stiff
Very Stiff
Hard
Very Hard

*ASTM D 1586

KEY TO DRILLING SYMBOLS



Grab Sample



Split Spoon Sample



Undisturbed Sample

NR = No reaction to HCL

NA = Not applicable

NS = No sample



Groundwater Table at Time of Drilling




Groundwater Table 24 Hours after Completion of Drilling


KEY TO SOIL CLASSIFICATIONS




Well-graded Gravel
GW



Low Plasticity Clay
CL




Clayey Silt
MH




Silty Sand
SM




Poorly-graded Gravel
GP



Sandy Clay
CLS




Sandy Silt
MLS




Topsoil
TOPSOIL




Partially Weathered Rock
BLDRCBLL




Silty Clay
CL-ML




Sand
SW




Liquid Sludge
SLUDGE




High Plasticity Clay
CH




Silt
ML




Clayey Sand
SC




Fill
FILL



Poorly Graded Sand
SP



Bedrock
BEDROCK



Waste
WOOD

SECTION 01135

BIDDER'S QUALIFICATIONS

Please answer all questions and have your statement notarized. If necessary, you may answer questions on separate sheets of paper and attach them to this statement. Other additional information your firm deems useful in the evaluation of your capabilities may also be included.

1. ORGANIZATION

Date of Response: _____

Legal Name of Bidder: _____

Street Address: _____

City, State, Zip Code: _____

Website: _____

Contact: _____ Phone: _____ Mobile: _____

Email Address: _____

Is the address of the business listed above a: (Please circle one listed below)

Main Office Regional Office Branch Office

When Organized: _____

When and Where Incorporated: _____

Licensed or Registered To Do Business in State of South Carolina: ___Yes _____No

If No, In What (State) _____ Municipality does your Company Have A Business License?_

Business License Number for Said (State) _____ Municipality: _____

Federal Employer I.D. Number: _____

If Partnership, list all partners and their addresses:

If there is no South Carolina Partner, give name and address of agent for service of process in South Carolina.

If an individual owner is not a South Carolina resident, give name and address of agent for service of process in South Carolina.

Is your company: (Please circle one listed below)

MBE WBE DBE MBE/WBE/DBE Certified by:_____

Has your company or any of its principals ever petitioned for bankruptcy, failed in business, defaulted or been terminated on a contract awarded to you?

_____ Yes _____ No

Has your company ever been banned or otherwise precluded from pursuing public work or have ever been found to be non-responsive by a public agency?

_____ Yes _____ No

Has your company ever had a claim made against it for improper, delayed, or non-compliant work or failure to meet warranty obligations?

_____ Yes _____ No

Is your company or any of its owners, officers, or major shareholders currently involved in any arbitration or litigation?

_____ Yes _____ No

Does your company have any outstanding judgments or claims against it?

_____ Yes _____ No

Is your company currently involved or has been involved in the last 3 years with any litigation?

_____ Yes _____ No

Has your organization ever failed to complete any work awarded to it?

_____ Yes _____ No

If yes to any of the above questions, please explain: _____

Please list any litigation brought against your company in the past five (5) years asserting that you failed to make payments to anyone.

Has your company ever had a contract terminated for any reason?

_____ Yes _____ No

If Yes, please explain: _____

List the geographical areas in which you work: _____

List the areas of work that you normally perform with your own forces: _____

What percentage of the Company's work is normally subcontracted? _____%

What is the largest contract your company has completed?

Amount \$ _____ Year _____

Project Name / Scope / Contact Information _____

Should the work require compliance with the South Carolina State Construction Licensing Board Rules and Regulations, the Contractor and any Subcontractor shall list the appropriate License number(s):

Main Contractor's License Number: _____

Subcontractor #1 License Number: _____

Subcontractor #1 Name: _____

Subcontractor #2 License Number: _____

Subcontractor #2 Name: _____

Subcontractor #3 License Number: _____

Subcontractor #3 Name: _____

(List additional if appropriate)

Year Firm Established: _____

2. EXPERIENCE

How many years have you been engaged in the contracting business under your present firm or trade name? _____

List jurisdictions and trade categories in which your organization is legally qualified to do business, and indicate registration or license numbers, if applicable.

Current Employment (Numbers of Employees): Total: _____

Management: _____ Clerical: _____ Professional: _____

Technical: _____ Skilled Labor: _____ Common Labor: _____

Total Value of Projects Completed (last five years): \$ _____

A. Contracts On Hand

Project Name and Location	Owner Name Address Phone No.	Project Description	Bid \$	Actual \$	Anticipated Completion Date

B. Selected Similar Construction Project Examples

At Least Five (5) Projects Similar in Nature:

Project Name and Location	Owner Name Address Phone No.	Project Description	Bid \$	Actual \$	Completion Date

C. Safety Issues Disclosure:

Contractor's Experience Modification Rate (EMR):
List Safety Issues for Last Five Years:

List Major Equipment Proposed To Be Used For This Project:

Description	Make/Model	Owned by Bidder or Sub?	Year Purchased
_____	_____	Yes ___ No ___	_____
_____	_____	Yes ___ No ___	_____
_____	_____	Yes ___ No ___	_____
_____	_____	Yes ___ No ___	_____
_____	_____	Yes ___ No ___	_____

_____	_____	Yes ___ No ___	_____
_____	_____	Yes ___ No ___	_____
_____	_____	Yes ___ No ___	_____
_____	_____	Yes ___ No ___	_____

D. Proposed Superintendent for this Project:

Name: _____

Address: _____

E. Select Project Experience of the Superintendent:

Project Name and Location	Owner Name Address Phone No.	Project Description	Bid \$	Actual \$	Completion Date

3. REFERENCES

Name of your Bank: _____

Address: _____

Phone: _____ Contact Person: _____

Amount of line of credit: _____ Amount Available: _____

Bonding Company: _____

Address: _____

Contact Person: _____ Phone: _____

Bonding Company's Rating: _____

Bonding Capacity: Per Job \$ _____ Aggregate \$ _____

Date of Last Bond: _____ Bond Amount \$ _____

Bond Rate: _____ Remaining Bonding Capacity \$ _____

Please list the persons or entities that provide indemnification to your Surety: _____

List three of your major suppliers:

A. Company: _____
Address: _____
Phone: _____ Fax: _____
Contact: _____

B. Company: _____
Address: _____
Phone: _____ Fax: _____
Contact: _____

C. Company: _____
Address: _____
Phone: _____ Fax: _____
Contact: _____

List three Contractors/Owners you do business with:

A. Company: _____
Address: _____
Phone: _____ Fax: _____
Contact: _____

B. Company: _____
Address: _____
Phone: _____ Fax: _____
Contact: _____

C. Company: _____
Address: _____
Phone: _____ Fax: _____
Contact: _____

4. SIGNATURE

The Undersigned certifies under oath that the information provided herein is true and sufficiently complete so as not to be misleading. The undersigned also recognizes that the Owner is relying on the accuracy of the information and the responses in deciding the demonstrated competence and qualifications for the type of required work.

The foregoing statement of qualifications is submitted under oath:

Respectfully submitted:

Company Name: _____

Street Address: _____

City, State, Zip: _____

By (Signed): _____

By (Typed): _____

Title: _____

Attach satisfactory evidence of the authority of the officer, or officers, signing on behalf of a corporation.

SWORN to before me this

_____ Day of _____, 20____

_____ (SEAL)

Notary Public for _____

My Commission Expires: _____

INDEX TO
DIVISION I – GENERAL REQUIREMENTS
SECTION 01300
SUBMITTALS

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Section Includes	01300-1
1.2	Related Sections	01300-1
1.3	Submittal Procedures	01300-1
1.4	Construction Progress Schedules	01300-2
1.5	Product Data	01300-2
1.6	Shop Drawings	01300-3
1.7	Samples	01300-4
1.8	Design Data	01300-4
1.9	Test Reports	01300-4
1.10	Certificates	01300-4
1.11	Manufacturer's Instructions	01300-5
1.12	Manufacturer's Field Reports	01300-5
1.13	Erection Drawings	01300-5
1.14	Reviewed Shop Drawings	01300-5
1.15	Submittal Checklist	01300-6-7

PART 2 – PRODUCTS

Not Used.

PART 3 – EXECUTION

Not Used.

DIVISION I – GENERAL REQUIREMENTS**SECTION 01300 – SUBMITTALS****PART 1 – GENERAL****1.1 SECTION INCLUDES**

- A. Submittal procedures.
- B. Construction progress schedules.
- C. Product Data.
- D. Shop Drawings.
- E. Samples.
- F. Design data.
- G. Test reports.
- H. Certificates.
- I. Manufacturer's instructions.
- J. Manufacturer's field reports.
- K. Erection drawings.

1.2 RELATED SECTIONS

- A. Section 01400 – Quality Control: Manufacturers' field services and reports.
- B. Section 01702 – Closeout Procedures: Contract warranties, bonds, manufacturers' certificates, and closeout submittals.

1.3 SUBMITTAL PROCEDURES

- A. Transmit each submittal with Engineer accepted form.
- B. Sequentially number the transmittal form. Revise submittals with original number and a sequential alphabetic suffix. Resubmit as specified for initial submittal. Indicate on revised drawings all changes that have been made other than those requested by the Engineer.
- C. Identify Project, Contractor, Subcontractor, or supplier; pertinent drawing and detail number, and specification section number, as appropriate.
- D. Apply Contractor's stamp, signed or initialed verifying review, approval, products required, field dimensions, adjacent construction Work, and coordination of

information is in accordance with the requirements of the Work and Contract Documents. Submittal without the Contractor's stamp will be returned to Contractor without Engineer's review.

- E. Make all submittals far enough in advance of scheduled dates for installation to provide all required time for reviews, for securing necessary approvals, for possible revision and resubmittal, and for placing orders and securing delivery. In scheduling, allow sufficient time for the Engineer's review following the receipt of the submittal. Coordinate submission of related items. For each submittal for review, allow 15 days excluding delivery time to and from the Contractor.
- F. Identify variations from Contract Documents and product or system limitations that may be detrimental to successful performance of the completed Work.
- G. Provide space for Contractor and Architect/Engineer review stamps.
- H. When revised for resubmission, identify all changes made since previous submission.
- I. Distribute copies of reviewed submittals as appropriate. Instruct parties to promptly report any inability to comply with requirements.

1.4 CONSTRUCTION PROGRESS SCHEDULES

- A. Submit initial schedule in duplicate within 15 days after date of Owner-Contractor Agreement.
- B. Revise and resubmit as required.
- C. Submit a computer generated or horizontal bar chart with separate line for each major portion of Work or operation, identifying first work day of each week.
- D. Show complete sequence of construction by activity, identifying Work of separate stages and other logically grouped activities. Indicate the early and late start, early and late finish, float dates, and duration.
- E. Indicate estimated percentage of completion for each item of Work at each submission.
- F. Indicate submittal dates required for shop drawings, product data, samples, and product delivery dates, including those furnished by Owner and required by allowances.

1.5 PRODUCT DATA

- A. Product Data For Review:
 - 1. Submitted to Engineer for review and conformance with information given in specifications and the design concept expressed in contract documents.

2. After review, provide copies and distribute in accordance with SUBMITTAL PROCEDURES article above.
- B. Submit the number of copies Contractor and Owner require, plus two copies retained by Engineer.
 - C. Mark each copy to identify applicable products, models, options, and other data. Supplement manufacturers' standard data to provide information specific to this Project.
 - D. Indicate product utility and electrical characteristics, utility connection requirements, and location of utility outlets for service for functional equipment and appliances.
 - E. After review, distribute in accordance with the Submittal Procedures article above.

1.6 SHOP DRAWINGS

- A. Contractor shall submit a minimum (5) copies of each shop drawing to the Engineer for review.
- B. Submitted to Engineer for review and conformance with information given in specifications and design concept expressed in contract documents. Review of shop drawings by Engineer shall not relieve Contractor of its responsibility for accuracy of shop drawings nor for furnishing of all materials and equipment required by the contract even though such items may not be indicated on shop drawings reviewed by Engineer.
- C. Shop drawings shall include applicable technical information, drawings, diagrams, performance curves, schedules, templates, calculations, instructions, measurements, and similar information as applicable to the specific item for which shop drawing is prepared.
- D. Do not use Engineer's Drawings for shop or erection purposes.
- E. Each shop drawing copy shall bear a Contractor's stamp showing they have been checked. Shop drawings submitted to the Engineer without Contractor's stamp will be returned to Contractor without review.

No review will be given to partial submittals of shop drawings for items which interconnect and/or are interdependent. It is the Contractor's responsibility to assemble shop drawings for all such interconnecting and/or interdependent items, check them and then make one submittal to Engineer.

Schedule of Submittals: Within 30 days of Contract award and prior to any shop drawing submittal, Contractor shall submit a schedule showing the estimated submittal date and desired acceptance date for each shop drawing anticipated. Time lost due to unacceptable submittals shall be the Contractor's responsibility.

1.7 SAMPLES

- A. Samples For Review:
 - 1. Submitted to Engineer for review and conformance with information given in specifications and design concept expressed in contract documents.
 - 2. After review, produce duplicates and distribute in accordance with SUBMITTAL PROCEDURES article above.
- B. Samples For Information:
 - 1. Submitted for Engineer's knowledge as contract administrator or for the Owner.
- C. Include identification on each sample, with full product information.
- D. Submit the number of samples specified in individual specification sections; one (1) of which will be retained by Engineer.
- E. Reviewed samples which may be used in the Work are indicated in individual specification sections.
- F. Samples will not be used for testing purposes unless specifically stated in the specification section.

1.8 DESIGN DATA

- A. Submit for Engineer's knowledge as contract administrator or for the Owner.
- B. Submit for information and conformance with information given in specifications and design concept expressed in contract documents.

1.9 TEST REPORTS

- A. Submit for Engineer's knowledge as contract administrator or for the Owner.
- B. Submit test reports for information and assessing conformance with information given in specifications and design concept expressed in contract documents.

1.10 CERTIFICATES

- A. When specified in individual specification sections, submit certification by manufacturer, installation/application subcontractor, or the Contractor to Engineer, in quantities specified for Product Data.
- B. Indicate material or product conforms to or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.
- C. Certificates may be recent or previous test results on material or product, but must be acceptable to Engineer.

1.11 MANUFACTURER'S INSTRUCTIONS

- A. When specified in individual specification sections, submit printed instructions for delivery, storage, assembly, installation, adjusting, and finishing, to Engineer for delivery to Owner in quantities specified for product Data.
- B. Indicate special procedures, perimeter conditions requiring special attention, and special environmental criteria required for application or installation.
- C. Refer to Section 01400 – Quality Control, Manufacturers' Field Services article.

1.12 MANUFACTURER'S FIELD REPORTS

- A. Submit reports for Engineer's benefit as contract administrator or for the Owner.
- B. Submit report in duplicate within 30 days of observation to Engineer for information.
- C. Submit for information and assessing conformance with information given in specifications and design concept expressed in contract documents.

1.13 ERECTION DRAWINGS

- A. Submit drawings for Engineer's benefit as contract administrator or for the Owner.
- B. Submit for information and assessing conformance with information given in specifications and design concept expressed in contract documents.
- C. Data indicating inappropriate or unacceptable Work may be subject to action by the Engineer or Owner.

1.14 REVIEWED SHOP DRAWINGS

- A. Engineer Review.
 - 1. Acceptable submittals will be marked "No Exceptions Taken." A minimum of three copies will be retained by the Engineer for Engineer's and Owner's use and remaining copies will be returned to Contractor.
 - 2. Submittals requiring minor corrections before the product is acceptable will be marked "Furnish as Corrected." Contractor may order, fabricate, and ship items included in submittals, provided the indicated corrections are made.
 - 3. Submittals marked "Revise and Resubmit" must be revised to reflect required changes and the initial review procedure repeated.
 - 4. The "Rejected" notation is used to indicate products not acceptable. Upon return of a submittal so marked, Contractor shall repeat the initial review procedure utilizing acceptable products.

5. Only two copies of items marked "Revise and Resubmit" and "Rejected" will be reviewed and marked. One copy will be retained by Engineer and the other copy with all remaining unmarked copies will be returned to Contractor for resubmittal.
- B. No Work or products shall be installed without a drawing or submittal bearing the "No Exceptions Taken" or "Furnish as Corrected" notation. Contractor shall maintain at the job site a complete set of shop drawings bearing Engineer's stamp.
- C. Substitutions: In the event Contractor obtains Engineer's acceptance for use of products other than those listed first in Contract Documents, Contractor shall, at Contractor's own expense and using methods accepted by Engineer, make any changes to structures, piping and electrical work necessary to accommodate these products.
- D. Use of "No Exceptions Taken" or "Furnish as Corrected" notation on shop drawings or other submittals is general and shall not relieve Contractor of the responsibility of furnishing products of proper dimension, size, quality, quantity, materials, all performance characteristics, and to efficiently perform requirements and intent of Contract Documents. Engineer's review shall not relieve Contractor of the responsibility of errors of any kind on shop drawings. Review is intended only to assure conformance with design concept of the project and compliance with information given in Contract Documents.

1.15 SUBMITTAL CHECKLIST

- A. This checklist is not necessarily complete. Contractor is responsible to submit all items and materials as specified in each section.

Section	Submittal	Date Received by T & H	Accepted Submittal Returned to Owner/Contractor	Submittal Rejected & Returned	Comments
02210 – Soil Erosion Control					
	Silt Fence				
	Temporary Porous Baffles				
	Temporary Floating Skimmers				
	Erosion Control Blanket				
	Inlet Protections				
02275 – Rip-Rap					
	Stone				
	Filter Fabric				

Section	Submittal	Date Received by T & H	Accepted Submittal Returned to Owner/Contractor	Submittal Rejected & Returned	Comments
02720 – Storm Drainage					
	RCP or CMP				
	Gaskets				
	Drainage Structures				
	Filter Fabric				
02902 – Grassing					
	Seed Mix – Temporary				
	Seed Mix – Permanent				
	Fertilizer				
	Lime				

PART 2 – PRODUCTS

Not Used.

PART 3 – EXECUTION

Not Used.

END OF SECTION

INDEX TO
SECTION 01400 – QUALITY CONTROL

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Section Includes	01400–1
1.2	Related Sections	01400–1
1.3	Quality Assurance – Control of Installation	01400–1
1.4	Tolerance	01400–1
1.5	References and Standards	01400–2
1.6	Testing Services	01400–2
1.7	Manufacturer's Field Services	01400–3
PART 2 – PRODUCTS		
	Not Used	
PART 3 – EXECUTION		
3.1	Examination	01400–3
3.2	Preparation	01400–3

SECTION 01400
QUALITY CONTROL

PART 1 – GENERAL

1.1 SECTION INCLUDES

- A. Quality assurance – control of installation.
- B. Tolerances
- C. References and standards.
- D. Testing laboratory services.
- E. Manufacturer's field services.

1.2 RELATED SECTIONS

- A. Section 01300 – Submittals: Submission of manufacturer's instructions and certificates.
- B. Section 01410 – Testing Services.

1.3 QUALITY ASSURANCE – CONTROL OF INSTALLATION

- A. Monitor quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce Work of specified quality.
- B. Comply with manufacturer's instructions, including each step in sequence.
- C. Should manufacturer's instructions conflict with Contract Documents, request clarification from Engineer before proceeding.
- D. Comply with specified standards as minimum quality for the Work except where more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.
- E. Perform Work by persons qualified to produce required and specified quality.
- F. Verify field measurements are as indicated on shop drawings or as instructed by the manufacturer.
- G. Secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion, or disfigurement.

1.4 TOLERANCES

- A. Monitor fabrication and installation tolerance control of products to produce acceptable Work. Do not permit tolerances to accumulate.

- B. Comply with manufacturer's tolerances. Should manufacturer's tolerances conflict with Contract Documents, request clarification from Architect/Engineer before proceeding.
- C. Adjust products to appropriate dimensions and position before securing in place.
- D. Accessible routes shall not exceed maximum ADA allowable slopes.

1.5 REFERENCES AND STANDARDS

- A. For products or workmanship specified by association, trade, or other consensus standards, complies with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.
- B. Conform to reference standard by date of issue current with date specified in the individual specification sections, except where a specific date is established by code.
- C. Obtain copies of standards where required by product specification sections.
- D. Neither the contractual relationships, duties, nor responsibilities of the parties in Contract or those of the Architect/Engineer shall be altered from the Contract Documents by mention or inference otherwise in any reference document.

1.6 TESTING SERVICES

- A. Owner will appoint, employ, and pay for specified services of an independent firm to perform testing. Contractor shall pay for all retesting of failed tests.
- B. The independent firm will perform tests and other services specified in individual specification sections and as required by the Owner.
- C. Testing and source quality control may occur on or off the project site. Perform off-site testing as required by the Owner.
- D. Reports will be submitted by the independent firm to the Engineer and Contractor, in duplicate, indicating observations and results of tests and indicating compliance or non-compliance with Contract Documents.
- E. Cooperate with independent firm; furnish samples of materials, design mix, equipment, tools, storage, safe access, and assistance by incidental labor as requested.
 - 1. Notify Architect/Engineer and independent firm 48 hours prior to expected time for operations requiring services.
 - 2. Make arrangements with independent firm and pay for additional samples and tests required for Contractor's use.
- F. Testing does not relieve Contractor to perform Work to contract requirements.

- G. Re-testing required because of non-conformance to specified requirements shall be performed by the same independent firm on instructions by the Engineer. Payment for re-testing will be made by the Contractor.

1.7 MANUFACTURER'S FIELD SERVICES

Omitted

PART 2 – PRODUCTS

Not Used

PART 3 – EXECUTION

3.1 EXAMINATION

- A. Verify existing site conditions and substrate surfaces are acceptable for subsequent Work. Beginning new Work means acceptance of existing conditions.
- B. Verify existing substrate is capable of structural support or attachment of new Work being applied or attached.
- C. Examine and verify specific conditions described in individual specification sections.
- D. Verify utility services are available, of the correct characteristics, and in the correct locations.

3.2 PREPARATION

- A. Clean substrate surfaces prior to applying next material or substance.
- B. Seal cracks or openings of substrate prior to applying next material or substance.
- C. Apply manufacturer required or recommended substrate primer, sealer, or conditioner prior to applying any new material or substance in contact or bond.

END OF SECTION

INDEX TO
SECTION 01410 – TESTING SERVICES

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Section Includes	01410-1
1.2	Related Sections	01410-1
1.3	References	01410-1
1.4	Selection and Payment	01410-2
1.5	Quality Assurance	01410-2
1.6	Contractor Submittal	01410-2
1.7	Testing Agency Responsibilities	01410-3
1.8	Testing Agency Reports	01410-3
1.9	Limits on Testing Authority	01410-3
1.10	Contractor Responsibilities	01410-3
1.11	Schedule of Tests	01410-4

PART 2 – PRODUCTS

Not Used.

PART 3 – EXECUTION

Not Used.

SECTION 01410

TESTING SERVICES

PART 1 – GENERAL

1.1 SECTION INCLUDES

- A. Selection and payment.
- B. Contractor submittals.
- C. Testing agency responsibilities.
- D. Testing agency reports.
- E. Limits on testing authority.
- F. Contractor responsibilities.
- G. Schedule of tests.

1.2 RELATED SECTIONS

- A. Testing and approvals required by public authorities.
- B. Section 01300 – Submittals: Manufacturer's certificates.
- C. Section 01702 – Contract Closeout: Project record documents.

1.3 REFERENCES (LATEST REVISION)

- A. ASTM C 802 – Practice for Conducting an Interlaboratory Test Program to Determine the Precision of Test Methods for Construction Materials.
- B. ASTM C 1077 – Practice for Laboratories Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Laboratory Evaluation.
- C. ASTM C 1093 – Practice for Accreditation of Testing Agencies for Masonry.
- D. ASTM D 3740 – Practice for Minimum Requirements for Agencies Engaged in Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction.
- E. ASTM D 4561 – Practice for Quality Control Systems for Organizations Producing and Applying Bituminous Paving Materials.
- F. ASTM E 329 – Specification for Agencies Engaged in Construction Inspection and/or Testing.
- G. ASTM E 543 – Practice for Agencies Performing Nondestructive Testing.

- H. ASTM E 548 – Guide for General Criteria Used for Evaluating Laboratory Competence.
- I. ASTM E 699 – Practice for Evaluation of Agencies Involved in Testing, Quality Assurance, and Evaluating of Building Components.

1.4 SELECTION AND PAYMENT

- A. Owner will employ and pay for services of an independent testing agency or laboratory to perform specified testing. Contractor shall pay for all retesting of failed tests.
- B. Employment of testing agency or laboratory in no way relieves Contractor of obligation to perform Work in accordance with requirements of Contract Documents.

1.5 QUALITY ASSURANCE

- A. Comply with requirements of practices listed in paragraph 1.3.
- B. Laboratory: Authorized to operate in State in which project is located.
- C. Laboratory Staff: Maintain a full time registered Engineer on staff to review services.
- D. Testing Equipment: Calibrated at reasonable intervals with devices of an accuracy traceable to either National Bureau of Standards or accepted values of natural physical constants.

1.6 CONTRACTOR SUBMITTALS

- A. Prior to start of Work, submit testing laboratory name, address, and telephone number, and names of full time registered Engineer and responsible officer.
- B. Submit copy of report of laboratory facilities inspection made by Materials Reference Laboratory of National Bureau of Standards during most recent inspection, with memorandum of remedies of any deficiencies reported by the inspection.

1.7 TESTING AGENCY RESPONSIBILITIES

- A. Test samples of mixes submitted by Contractor.
- B. Provide qualified personnel at site. Cooperate with Engineer and Contractor in performance of services.
- C. Perform specified sampling and testing of products in accordance with specified standards.
- D. Ascertain compliance of materials and mixes with requirements of Contract Documents.
- E. Promptly notify Engineer and Contractor of observed irregularities or non-conformance of Work or products.

- F. Perform additional tests required by Engineer.
- G. Attend preconstruction meetings and progress meetings.

1.8 TESTING AGENCY REPORTS

- A. After each test, promptly submit two (2) copies of report to Engineer and to Contractor.
- B. Include:
 - 1. Date issued.
 - 2. Project title and number.
 - 3. Name of inspector.
 - 4. Date and time of sampling or inspection.
 - 5. Identification of product and specifications section.
 - 6. Location in the Project.
 - 7. Type of inspection or test.
 - 8. Date of test.
 - 9. Results of tests.
 - 10. Conformance with Contract Documents.
- C. When requested by Engineer, provide interpretation of test results.

1.9 LIMITS ON TESTING AUTHORITY

- A. Agency or laboratory may not release, revoke, alter, or enlarge on requirements of Contract Documents.
- B. Agency or laboratory may not approve or accept any portion of the Work.
- C. Agency or laboratory may not assume any duties of Contractor.
- D. Agency or laboratory has no authority to stop the Work.

1.10 CONTRACTOR RESPONSIBILITIES

- A. Deliver to agency or laboratory at designated location, adequate samples of materials proposed to be used requiring testing, along with proposed mix designs.
- B. Cooperate with laboratory personnel, and provide access to the Work.
- C. Provide incidental labor and facilities:
 - 1. To provide access to Work to be tested.
 - 2. To obtain and handle samples at the site or at source of products to be tested.
 - 3. To facilitate tests.
 - 4. To provide storage and curing of test samples.
- D. Notify Engineer and laboratory 48 hours prior to expected time for operations requiring testing services.

1.11 SCHEDULE OF TESTS

Section	Test	Frequency	Date	Performed By	Notes
02204 – Earthwork					
	Compaction				
	Unpaved	1 test per horizontal layer per 10,000 sf of fill area			
	Paved	1 test per horizontal layer per 5,000 sf of subgrade			
	Building Pad	1 test per horizontal layer per 1,500 sf of fill area			
	Curb & gutter	1 test per 300 lf			
	Proof Rolling	As necessary			
02720 – Storm Drainage					
	Compaction				
	Traffic Areas	1 per 100 lf or less for each 4 ft. of depth			
	Non-Traffic	1 per 500 lf or less for each 6 ft. of depth			

PART 2 – PRODUCTS

Not Used.

PART 3 – EXECUTION

Not Used.

END OF SECTION

INDEX TO
SECTION 01702 – CONTRACT CLOSEOUT

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Section Includes	01702-1
1.2	Related Sections	01702-1
1.3	Closeout Procedures	01702-1
1.4	Final Cleaning	01702-1
1.5	Adjusting	01702-1
1.6	Project Record Documents	01702-1

PART 2 – PRODUCTS

Not Used

PART 3 – EXECUTION

Not Used

SECTION 01702
CONTRACT CLOSEOUT

PART 1 – GENERAL

1.1 SECTION INCLUDES

- A. Closeout procedures.
- B. Project record documents.
- C. Operation and maintenance data.
- D. Warranties and bonds.
- E. Maintenance service.

1.2 RELATED SECTIONS

- A. Section 01300 – Submittals

1.3 CLOSEOUT PROCEDURES

- A. Submit written verification Contract Documents being reviewed, Work has been observed at appropriate times, and Work is complete in accordance with Contract Documents and ready for Engineer's review.
- B. Provide submittals to Engineer required by governing or other authorities.
- C. Submit final Application for Payment identifying total adjusted Contract Sum, previous payments, and sum remaining due.

1.4 FINAL CLEANING

- A. Execute final cleanup prior to final project assessment.
- B. Remove waste and surplus materials, rubbish, and construction facilities from the site.

1.5 ADJUSTING

- A. Adjust operating products and equipment to ensure smooth and unhindered operation.

1.6 PROJECT RECORD DOCUMENTS

- A. Maintain on site one set of the following record documents; record actual revisions to the Work:
 - 1. Drawings.
 - 2. Specifications.

3. Addenda.
 4. Change Orders and other modifications to the Contract.
 5. Reviewed Shop Drawings, Product Data, and Samples.
 6. Manufacturer's instruction for assembly, installation, and adjusting.
- B. Ensure entries are complete and accurate, enabling future reference by Owner.
- C. Store record documents separate from documents used for construction.
- D. Record information concurrent with construction progress.
- E. Equipment Specifications: Legibly mark and record at each product section description of actual products installed, including the following:
1. Manufacturer's name and product model and number.
 2. Product substitutions or alternates utilized.
 3. Changes made by Addenda and modifications.
- F. Project Record Drawings: Legibly mark each item to record actual construction including:
1. Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 2. Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Work.
 3. Where proposed and existing utilities cross, the Contractor shall measure and record the horizontal location and vertical separation between each crossing. Separation shall be measured between exteriors and pipes.
 4. Field changes of dimension and detail.
 5. Details not on original Contract drawings.
 6. Piling data locations, tip and cut-off elevations, and driving records.
- G. Submit documents to Engineer with claim for final Application for Payment.

PART 2 – PRODUCTS

Not Used

PART 3 – EXECUTION

Not Used

END OF SECTION

INDEX TO
SECTION 02070 - SELECTIVE DEMOLITION

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Related Documents	02070-1
1.2	Description of Work	02070-1
1.3	Submittals	02070-1
1.4	Job Conditions	02070-1
1.5	Damages	02070-1
1.6	Traffic	02070-1
1.7	Explosives	02070-2
1.8	Utility Services	02070-2
1.9	Environmental Controls	02070-2
1.10	Measurement and Payment	02070-2
PART 2 – PRODUCTS		
	None this Section	
PART 3 – EXECUTION		
3.1	Preparation	02070-2
3.2	Demolition	02070-3
3.3	Salvage Materials	02070-3
3.4	Disposal of Demolished Materials	02070-3
3.5	Clean-up and Repair	02070-3

SECTION 02070

SELECTIVE DEMOLITION

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions apply to work of this section.

1.2 DESCRIPTION OF WORK

- A. Extent of selective demolition work is indicated on drawings.

1.3 SUBMITTALS

- A. Schedule: Submit schedule indicating proposed methods and sequence of operations for selective demolition work to Owner's representative for review prior to commencement of work. Include coordination for shut-off, capping, and continuation of utility services as required, together with details for dust and noise control protection. Include schedule and location for return of items identified on plans to be delivered to Owner of property.

1.4 JOB CONDITIONS

- A. Condition of Structures: Owner assumes no responsibility for actual condition of items to be demolished.
- B. Partial Demolition and Removal: Items indicated to be removed but of value to Contractor may be removed as work progresses. Transport salvaged items from site as they are removed.

Storage or sale of removed items on site will not be permitted.
- C. Protections: Provide temporary barricades and other forms of protection as required to protect Owner's personnel and general public from injury due to selective demolition work.

Protect from damage existing finish work to remain in place and becomes exposed during demolition operations. Remove protections at completion of work.

1.5 DAMAGES

- A. Promptly repair damages caused to adjacent facilities by demolition work at no cost to Owner.

1.6 TRAFFIC

- A. Conduct selective demolition operations and debris removal in a manner to ensure minimum interference with roads, streets, walks, and other adjacent occupied or used facilities.

Do not close, block or otherwise obstruct streets, walks, or other occupied or used facilities without written permission from authorities having jurisdiction. Provide alternate routes around closed or obstructed traffic ways.

1.7 EXPLOSIVES

- A. Use of explosives will not be permitted.

1.8 UTILITY SERVICES

- A. Maintain existing utilities indicated to remain, keep in service, and protect against damage during demolition operations.

Do not interrupt existing utilities serving occupied or used facilities, except when authorized in writing by authorities having jurisdiction. Provide temporary services during interruptions to existing utilities, as acceptable to governing authorities.

1.9 ENVIRONMENTAL CONTROLS

- A. Use water sprinkling, temporary enclosures, and other suitable methods to limit dust and dirt rising and scattering in air to lowest practical level. Comply with governing regulations pertaining to environmental protection.

Do not use water when it may create hazardous or objectionable conditions such as ice, flooding, and pollution.

1.10 MEASUREMENT AND PAYMENT

- A. Payment for demolition will be made at the contract lump sum price. Payment will include equipment, labor, materials, protection, clean-up, disposal, and all work necessary to complete the selective demolition shown on the construction drawings.

PART 2 – PRODUCTS

None in this section

PART 3 – EXECUTION

3.1 PREPARATION

- A. Prior to commencement of selective demolition work, check areas in which work will be performed. Photograph or video existing conditions of surfaces, equipment, or surrounding properties that could be misconstrued as damage resulting from selective demolition work. File with Owner's representative prior to starting work.
- B. Cover and protect equipment and fixtures to remain from soiling or damage when demolition work is performed in areas from which such items have not been removed.

3.2 DEMOLITION

- A. Perform selective demolition work in a systematic manner. Use such methods as required to complete work indicated on drawings in accordance with demolition schedule and governing regulations.

Demolish concrete in small sections. Cut concrete at junctures with construction to remain using power-driven masonry saw or hand tools. Do not use power-driven impact tools.

Completely fill below-grade areas and voids resulting from demolition work. Provide fill consisting of approved earth, gravel and sand, free of trash and debris, stones over 2" diameter, roots or other organic matter.

If unanticipated mechanical, electrical, or structural elements, which conflict with intended function or design, are encountered, investigate and measure both nature and extent of the conflict. Submit report to Owner's representative in written, accurate detail. Pending receipt of directive from Owner's representative, rearrange selective demolition schedule as necessary to continue overall job progress without delay.

3.3 SALVAGE MATERIALS

Any articles of historic significance will remain the property of the Owner. Notify Owner's representative if such items are encountered and obtain acceptance regarding method of removal and salvage for Owner.

3.4 DISPOSAL OF DEMOLISHED MATERIALS

- A. Remove debris, rubbish and other materials resulting from demolition operations from site. Transport and legally dispose of materials off site.

If hazardous materials are encountered during demolition operations, comply with applicable regulations, laws, and ordinances concerning removal, handling, and protection against exposure or environmental pollution.

Burning of removed materials is not permitted on project site.

3.5 CLEAN-UP AND REPAIR

- A. Upon completion of demolition work, remove tools, equipment and demolished materials from site. Remove protections and leave site clean.

Repair demolition performed in excess of required work. Return structures and surfaces to remain to the condition existing prior to commencement of selective demolition work. Repair adjacent construction or surfaces soiled or damaged by selective demolition work.

Fill in all voids created by selective demolition and grade site to drain. Grass all disturbed areas for erosion control.

END OF SECTION

INDEX TO
SECTION 02110 – SITE CLEARING

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Section Includes	02110-1
1.2	Related Sections	02110-1
1.3	Measurement and Payment	02110-1
1.4	Regulatory Requirements	02110-1
PART 2 – PRODUCTS		
2.1	Materials	02110-1
PART 3 – EXECUTION		
3.1	Preparation	02110-2
3.2	Protection	02110-2
3.3	Clearing	02110-3
3.4	Removal	02110-3
3.5	Disposal	02110-3
3.6	Grubbing	02110-4

SECTION 02110**SITE CLEARING****PART 1 – GENERAL****1.1 SECTION INCLUDES**

- A. Removal of surface debris.
- B. Removal of trees, shrubs, and other plant life.
- C. Topsoil excavation.

1.2 RELATED SECTIONS

- A. Section 02204 – Earthwork.

1.3 MEASUREMENT AND PAYMENT

- A. Site Clearing: Clearing, grubbing and other items to be removed will be included in the lump sum price in the proposal for clearing work. Includes clearing site, removing stumps, loading and removing waste materials from site.

1.4 REGULATORY REQUIREMENTS

- A. Conform to applicable code for environmental requirements, disposal of debris, and burning debris on site.
- B. Coordinate clearing Work with utility companies.

PART 2 – PRODUCTS**2.1 MATERIALS**

- A. Provide tree protection materials as detailed on the construction drawings.

PART 3 – EXECUTION**3.1 PREPARATION**

- A. Verify existing plant life designated to remain is tagged or identified.

3.2 PROTECTION

- A. All trees onsite which are outside of the limits of disturbance are to remain. No trees may be removed prior to the preconstruction conference. All trees not to be removed will be protected from injury to their roots and to their top to a distance three feet beyond the drip-line and no grading, trenching, pruning, or

storage of materials may go in this area except as provided by an Owner's representative stakeout. Contractor will pay a penalty for any tree removed from the site outside of the limits of disturbance. Contractor also will pay for any tree that dies due to damage during construction. This applies to all trees on site whether or not they are shown on the plans.

- B. Contractor shall not be held accountable for damages to trees resulting from placement of fill or removal of soils where such action is required by the contract documents. Any tree, the trunk of which is within 10 feet of any footing or trench, shall be exempt from these penalties except Contractor shall exercise all reasonable precautions to preserve even these trees. Contractor agrees to pay fines as established below in the event he or any of his subcontractors causes loss or removal of trees designated to be saved under provisions of this contract.

The fines are as follows:

<u>Caliper</u>	<u>Fine</u>
1" – 2"	\$ 150.00
2" – 3"	200.00
3" – 4"	250.00
4" – 5"	400.00
5" – 6"	500.00
6" – 7"	600.00
7" – 8"	750.00
8" – 11"	1,500.00
12" – 20"	2,000.00
21" & larger	\$ 2,500.00

- C. Trees shall be graded by Owner's representative as to variety, condition, and site importance, with above figures acting as a maximum fine. Lowest assessment amount shall be no less than one-half of the above fine figures.
- D. Protect bench marks, survey control points, and existing structures from damage or displacement.
- E. Protect all remaining utilities.
- F. Clearing operations shall be conducted to prevent damage by falling trees to trees left standing, to existing structures and installations, and to those under construction, and to provide for the safety of employees and others.

3.3 CLEARING

- A. Clear areas required for access to site and execution of work. Clearing shall consist of felling and cutting trees into sections, and satisfactory disposal of trees and other vegetation designated for removal, including downed timber, snags, brush, and rubbish occurring within area to be cleared. Trees, stumps, roots, brush, and other vegetation in areas to be cleared shall be [burned or] removed completely from the site, except such trees and vegetation as may be indicated or directed to be left standing. Trees designated to be left standing within cleared areas shall be trimmed of dead branches 1-1/2 inch or more in diameter.

Limbs and branches to be trimmed shall be neatly cut close to the trunk of the tree or main branches. Cuts more than 1-1/2 inches in diameter shall be painted with an accepted treewound paint. Trees and vegetation to be left standing shall be protected from damage incident to clearing, grubbing, and construction operations, by the erection of timber barriers or by such other means as circumstances require. Such barriers must be placed and be checked by the OWNER before construction observations can proceed (See 3.2). Clearing shall also include removal and disposal of structures obtruding, encroaching upon, or otherwise obstructing the work.

3.4 REMOVAL

- A. Work shall include felling of such trees and removal of their stumps and roots. Trees shall be disposed of as hereinafter specified.
- B. Remove debris, rock, and other extracted plant life from site.
- C. Partially remove paving, curbs, and sidewalk as indicated. Neatly saw cut edges at right angle to surface.

3.5 DISPOSAL

- A. Disposal of trees, branches, snags, brush, stumps, etc., resulting from clearing and grubbing shall be the Contractor's responsibility and shall be disposed of by burning, removal from site, or a combination of both. All costs in connection with disposing of materials will be at the Contractor's expense. Material disposed of by burning shall be burned in a manner avoiding all hazards, such as damage to existing structures, construction in progress, trees, and vegetation. Contractor shall be responsible for compliance with all local and State laws and regulations relative to the building of fires. Disposal by burning shall be kept under constant attendance until fires have burned out or extinguished. All liability of any nature resulting from disposal of cleared and grubbed material shall become the Contractor's responsibility. Disposal of all materials cleared and grubbed will be in accordance with rules and regulations of the State of South Carolina. No material will be burned unless directed to do so by the OWNER. Contractor shall obtain a permit to burn on site from local fire department, before beginning the work.

3.6 GRUBBING

- A. Grubbing shall consist of removal and disposal of stumps, roots larger than one inch in diameter, and matted roots from designated grubbing areas. This material, together with logs and other organic or metallic debris not suitable for building of pavement subgrade or building pads, shall be excavated and removed to a depth of not less than 18 inches below original surface level of the ground in embankment areas and not less than 2 feet below finished earth surface in excavated areas. Depressions made by grubbing shall be filled with suitable material and compacted to make the surface conform to original adjacent ground.

END OF SECTION

INDEX TO
SECTION 02204 – EARTHWORK

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Section Includes	02204-1
1.2	Related Sections	02204-1
1.3	Measurement and Payment	02204-1
1.4	References	02204-2
1.5	Submittals	02204-2
1.6	Quality Assurance	02204-2
1.7	Testing	02204-2
PART 2 – PRODUCTS		
2.1	Materials	02204-3
2.2	Source Quality Control	02204-3
PART 3 – EXECUTION		
3.1	Topsoil	02204-4
3.2	Excavation	02204-4
3.3	Ground Surface Preparation for Fill	02204-4
3.4	Fill	02204-5
3.5	Finished Grading	02204-5
3.6	Disposal of Waste Material	02204-5
3.7	Protection	02204-5
3.8	Drainage	02204-6
3.9	Field Quality Control	02204-6
3.10	Proof Rolling	02204-6

SECTION 02204**EARTHWORK****PART 1 – GENERAL****1.1 SECTION INCLUDES**

- A. Grading
- B. Excavation
- C. Backfilling
- D. Compaction
- E. Remove and Replace Topsoil
- F. Dressing of Shoulders and Banks
- G. Stone Drainage Filter
- H. Water Control
- I. Testing

1.2 RELATED SECTIONS

- A. Section 01012 – Soil Investigation for Bidders
- B. Section 01400 – Quality Control
- C. Section 01410 – Testing Services
- D. Section 02110 – Site Clearing

1.3 MEASUREMENT AND PAYMENT

- A. Grading to subgrades, construction of ditches, dressing of disturbed areas, removing and replacing topsoil, excavating, backfilling and compacting to required elevations, testing, staking, and construction supervision shall be included in the contract lump sum price for "Earthwork."
- B. Mass Rock Excavation – Mass Rock Excavation is defined as any material that cannot be dislodged by a Caterpillar D-8 Bulldozer, or equivalent, equipped with a single tooth ripper, without the use of impact hammers or drilling and blasting. Contractor is to notify the Owner and Engineer if mass rock is present. Mass rock volume will be measured with a pre and post excavation survey. Mass rock shall be paid for at the unit price included in the contract. All rock shall be removed to depths as specified by the geotechnical engineer.

- C. Trench Rock Excavation – Trench rock excavation is defined as any material that cannot be dislodged by a Caterpillar 325 hydraulic backhoe, or equivalent, without the use of impact hammers or drilling and blasting. Contractor is to notify the Owner and Engineer if trench rock is present. Trench rock volume will be measured with a pre and post excavation survey. Trench rock shall be paid for at the unit price included in the contract.
- D. Unsuitable Material – If encountered and qualified by the geotechnical engineer, payment will be made on a contract unit price for each cubic yard removed. Payment will include excavation and disposal of unsuitable material.
- E. Earthwork – All earthwork associated with the installation of bulkheads, headwalls, wingwalls, weir structures, drainage filters, rip-rap, etc. shall not be measured for direct payment. Payment for the earthwork shall be included in the item to which it pertains.
- F. Dewatering – No direct payment shall be made for dewatering. Dewatering shall be included in the item to which it pertains.
- G. Proof Rolling – No direct pavement shall be made for proof rolling. Proof rolling shall be included in the item to which it pertains.

1.4 REFERENCES (LATEST REVISION)

- A. ASTM D 448 – Sizes of Aggregate for Road and Bridge Construction.
- B. ASTM D 698 – Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort.
- C. ASTM D 2487 – Classification of Soils for Engineering Purposes (Unified Soil Classification System).
- D. ASTM D 6938 – In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth).
- E. ASTM D 3740 – Minimum Requirements for Agencies Engaged in Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction.
- F. ASTM E 329 – Agencies Engaged in Construction Inspection and/or Testing.

1.5 SUBMITTALS

- A. Section 01300 – Submittals: Procedures for submittals.
- B. Materials Source: Submit gradation analysis, proctor results, and soil classification for all borrow material.

1.6 QUALITY ASSURANCE

- A. Perform work in accordance with SCDHEC and City of Greenville standards.

1.7 TESTING

- A. Laboratory tests for moisture density relationship for fill materials shall be in accordance with ASTM D 698, (Standard Proctor).
- B. In place density tests in accordance with ASTM D 6938.
- C. Testing laboratory shall operate in accordance with ASTM D 3740 and E 329 and be acceptable to the Engineer.
- D. The testing laboratory and Project Engineer/Project Representative shall be given a minimum of 48 hours notice prior to taking any of the tests.
- E. Owner shall select and engage the testing laboratory. Testing laboratory shall be responsible to the Owner and Owner's Engineer. Payment for laboratory and all tests shall be by the Owner, except Owner specifically reserves the right to deduct from Contractor's payment, expenses and charges of testing laboratory when:
 - 1. Contractor gives notice the work is ready for inspection and testing, and fails to be ready for the test, and/or
 - 2. Testing of the Contractor's work, products or materials fail, and retesting is required, and/or
 - 3. Contractor abuses the services or interferes with the work of the testing laboratory in the conduct of this work.
- F. Test results shall be furnished to the Engineer prior to continuing with associated or subsequent work.

PART 2 – PRODUCTS

2.1 MATERIALS

- A. Borrow shall consist of sand or sand-clay soils capable of being readily shaped and compacted to the required densities, and shall be reasonably free of roots, trash, rock larger than 2 inches, and other deleterious material.
- B. All soils used for structural fills shall have a PI (plastic index) of less than 10, and a LL (liquid limit) of less than 30. Fill soils shall be dried or wetted to appropriate moisture contents prior to compaction. Additionally, fill soils used for the top 2 feet of fill beneath roads and parking lots shall have no more than 15% passing the # 200 sieve.
- C. Contractor shall furnish all borrow material.
- D. Contractor shall be responsible for and bear all expenses in developing borrow sources including securing necessary permits, drying the material, haul roads, clearing, grubbing, excavating the pits, placing, compaction and restoration of pits and haul roads to a condition satisfactory to property owners and in compliance with applicable federal, state, and local laws and regulations.

2.2 SOURCE QUALITY CONTROL

- A. If tests indicate materials do not meet specified requirements, change material and retest.
- B. Provide materials of each type from same source throughout the Work.

PART 3 – EXECUTION

3.1 TOPSOIL

- A. Contractor shall strip topsoil and stockpile on site at a location determined by the Owner at the Contractor's expense.
- B. Topsoil shall be placed to a depth of 4 inches over all disturbed or proposed landscaped areas.
- C. Topsoil shall be provided at Contractor's expense if it is not available from site.
- D. Any remaining topsoil will be hauled off site at the Contractor's expense.
- D. Do not excavate wet topsoil.

3.2 EXCAVATION

- A. Suitable excavation material shall be transported to and placed in fill areas within limits of the work.
- B. Unsuitable material encountered in areas to be paved and under building pads, shall be excavated to depths as specified by the geotechnical engineer, and replaced with suitable material from site or borrow excavations. Contractor shall notify Engineer and Owner if unsuitable material is encountered.
- C. Unsuitable and surplus excavation material not required for fill shall be disposed of off site.
- D. Proper drainage, including sediment and erosion control, shall be maintained at all times. Methods shall be in accordance with the National Pollutant Discharge Elimination System standards and other local, state, and federal regulations.
- E. Unsuitable materials as stated herein are defined as highly plastic clay soils, of the CH and MH designation, border line soils of the SC-CH description, and organic soils of the OL and OH description based on the Unified Soils Classification System. Further, any soils for the top two feet of pavement subbase shall have no more than 15% passing the # 200 sieve.

3.3 GROUND SURFACE PREPARATION FOR FILL

- A. All vegetation, roots, brush, heavy sods, heavy growth of grass, decayed vegetable matter, rubbish, and other unsuitable material within the areas to be filled shall be stripped and removed prior to beginning the fill operation.

- B. Sloped ground surfaces steeper than 1 vertical to 4 horizontal, on which fill is to be placed shall be plowed, stepped, or benched, or broken up as directed, in such a manner where fill material will bond with the existing surface.
- C. Surfaces on which fill is to be placed and compacted shall be wetted or dried as may be required to obtain the specified compaction.

3.4 FILL

- A. Shall be placed in successive horizontal layers 8 inches to 12 inches in loose depth for the full width of the cross-section and compacted as required.

3.5 FINISHED GRADING

- A. All areas covered by the project including excavated and filled sections and adjacent transition areas shall be smooth graded and free from irregular surface changes.
- B. Degree of finish shall be that ordinarily obtainable from either blade-grader or scraper operations, supplemented with hand raking and finishing, except as otherwise specified.
- C. Unpaved areas to within 0.1 feet of elevations shown on the drawings provided such deviation does not create low spots that do not drain.
- D. Paved Areas – grade to within 0.05 feet of the drawing elevations. Potential paved areas are shown on the “Potential Building and Pavement Limits” Exhibit at the end of this section.
- E. Building Pads –grade to within 0.05 feet of the drawing elevations. Potential paved areas are shown on the “Potential Building and Pavement Limits” Exhibit at the end of this section.
- F. Ditches and pond banks shall be finished graded, dressed, and seeded within 14 calendar days of work to reduce erosion and permit adequate drainage.

3.6 DISPOSAL OF WASTE MATERIAL

- A. All vegetation, roots, brush, sod, broken pavements, curb and gutter, rubbish, and other unsuitable or surplus material stripped or removed from limits of construction shall be disposed of by the Contractor.

3.7 PROTECTION

- A. Graded areas shall be protected from traffic, erosion, settlement, or any washing away occurring from any cause prior to acceptance.
- B. Contractor shall be responsible for protection of below grade utilities shown on the drawings or indicated by the Owner at all times during earthwork operations.

- C. Repair or re-establishment of graded areas prior to final acceptance shall be at the Contractors expense.
- D. Site drainage shall be provided and maintained by Contractor during construction until final acceptance of the project. Drainage may be by supplemental ditching, or pumping if necessary, prior to completion of permanent site drainage.

3.8 DRAINAGE

- A. Contractor shall be responsible for providing surface drainage away from all construction areas. This shall include maintenance of any existing ditches or those constructed in the immediate vicinity of the work. Contractor shall provide proper and effective measures to prevent siltation of wetlands, streams, and ditches on both the Owner's property, and those properties downstream.

3.9 FIELD QUALITY CONTROL

- A. Compaction testing shall be performed in accordance with ASTM D 6938. Where tests indicate the backfill does not meet specified requirements, the backfill shall be reworked or removed and replaced, and then retested at the Contractor's expense.
- B. Unpaved areas – at least 95% of the standard Proctor maximum dry density (ASTM D698) within 3% optimum moisture content unless otherwise approved by the Engineer.
- C. Paved Areas and Under Structures – top 12-inch layer of subbase to at least 98% of maximum dry density within 3% optimum moisture content. Areas below the top 12-inches are to be compacted to at least 95% of the standard Proctor maximum dry density (ASTM D698) within 3% optimum moisture content unless otherwise approved by the Engineer. Potential building pad and paving limits are shown on the "Potential Building and Pavement Limits" Exhibit included at the end of this section.
- D. Rolling and compaction equipment and methods shall be subject to acceptance by the Engineer. Acceptance in no way relieves Contractor of the responsibility to perform in correct and timely means.
- E. Number of Tests – Under paved areas, no less than one density test per horizontal layer per 5,000 square feet of subbase shall be made. In unpaved areas, no less than one density test per horizontal layer per 10,000 square feet of fill area shall be made. Under curb and gutter, no less than one density test per every 300 linear feet. On building pads, no less than one density test per horizontal layer per 1,500 square feet of fill area shall be made.




3.10 PROOF ROLLING

- A. Shall be required on the subbase of all curb and gutter and paved areas and on the base of all paved areas where designated by the Engineer. Proof rolling shall

take place after all underground utilities are installed and backfilled. The operation shall consist of rolling the subbase or base with a fully loaded 10 wheeled dump truck. A full load shall consist of 10 to 12 cubic yards of soil or rock. The dump truck shall be capable of traveling at a speed of two to five miles per hour and be in sound mechanical shape with no exhaust leaks or smoking from burning oil. The Engineer shall determine number of passes and areas rolled.

END OF SECTION

Z:\28283\28283.0000\Engineering\Drawings\Exhibits\28283.0000 - Potential Pavement Limits.dwg - May 13, 2020 - 11:55:15 AM



MASS GRADING AT CUICAR TN3
 ACTIVITY:
 BUILDING PAD AND PAVEMENT LIMITS
 CLIENT:
 LICAR, LLC
 LOCATION: GREENVILLE COUNTY, SC
 DATE: MAY 13, 2020 DRAWN BY: RWP SHEET: 1
 JOB NUMBER: J-28283.0000 REVIEWED BY: RWP SCALE: 1" = 200'



501 River Street • Suite 200
 Greenville, SC 29601 • 864.412.2222
www.thomasandhutton.com

INDEX TO
SECTION 02210 – SOIL EROSION CONTROL

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Related Documents	02210-1
1.2	Description of Work	02210-1
1.3	Purposes	02210-1
1.4	Quality Assurance	02210-1
1.5	Submittals	02210-2
1.6	Measurement and Payment	02210-2
PART 2 – PRODUCTS		
2.1	Grassing Materials	02210-3
2.2	Hay Bales	02210-3
2.3	Silt Fence	02210-3
2.4	Chemicals for Dust Control	02210-4
2.5	Rip-Rap	02210-4
2.6	Erosion Control Blanket	02210-4
2.7	Temporary Floating Skimmer	02210-4
2.8	Temporary Porous Baffles	02210-4
2.9	Product Review	02210-4
PART 3 – EXECUTION		
3.1	General	02210-4
3.2	Grassing	02210-5
3.3	Sediment Barriers	02210-5
3.4	Silt Fence	02210-6
3.5	Dust Control	02210-6
3.6	Sediment Basin	02210-6
3.7	Rip-Rap	02210-6
3.8	Construction Exit	02210-6
3.9	Inlet Protection	02210-6
3.10	Erosion Control Blanket	02210-6
3.11	Temporary Floating Skimmer	02210-6
3.12	Temporary Porous Baffles	02210-7

SECTION 02210
SOIL EROSION CONTROL

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Special Conditions apply to this section.

1.2 DESCRIPTION OF WORK

- A. Extent of soil erosion control work includes all measures necessary to meet the requirements of this section.

Erosion and sediment control measures shall be installed prior to any construction activity.

Soil erosion and sediment control measures shall include all temporary and permanent means of protection and trapping soils of the construction site during land disturbing activity. Activity covered in this contract shall meet standards of NPDES General Permit for the state where work is performed.

1.3 PURPOSES

- A. Contractor is to achieve the following goals:
1. Minimize soil exposure by proper timing of grading and construction.
 2. Retain existing vegetation whenever feasible.
 3. Vegetate and mulch denuded areas as soon as possible.
 4. Divert runoff away from denuded areas.
 5. Minimize length and steepness of slopes when it is practical.
 6. Reduce runoff velocities with sediment barriers or by increasing roughness with stone.
 7. Trap sediment on site.
 8. Inspect and maintain erosion control measures.

1.4 QUALITY ASSURANCE

- A. Manufacturer's Qualifications: Firms regularly engaged in the manufacture of soil erosion control systems products of types and sizes required, whose materials have been in satisfactory use for not less than 5 years.

- B. Codes and Standards: Comply with all applicable Local, State and Federal Standards pertaining to soil erosion control.

1.5 SUBMITTALS

- A. Product Data: Submit manufacturer's technical product data and installation instruction for soil erosion control materials and products.

1.6 MEASUREMENT AND PAYMENT

- A. Payment will be made at the contract lump sum price as shown on the bid proposal for each item under Erosion Control section.
 1. Grassing – Payment for permanent or temporary grassing will be made at the contract lump sum price. Payment shall include all equipment, labor, materials, and maintenance necessary to establish a stand of grass.
 2. Silt Fence – Payment will be made at the contract lump sum price. Payment shall include all equipment, labor, materials, and maintenance necessary to install and keep silt fence functioning properly.
 3. Ditch Check – Payment will be made at the contract lump sum price. Payment shall include all equipment, labor, materials, and maintenance necessary to install and keep ditch check functioning properly.
 4. Rip-Rap – Payment will be made at the contract lump sum price. Payment shall include all equipment, labor, materials, and maintenance necessary to install rip-rap per the construction drawing.
 5. Construction Exit – Payment will be made at the contract lump sum price. Payment shall include all equipment, labor, materials, and maintenance necessary to install and keep construction exit functioning properly.
 6. Sediment Marker – Payment will be made at the contract lump sum price. Payment shall include all equipment, labor, materials, and maintenance necessary to install and keep sediment marker functioning properly.
 7. Temporary Porous Baffle – Payment will be made at the contract lump sum price. Payment shall include all equipment, labor, materials, and maintenance necessary to install and keep baffles functioning properly.
 8. Temporary Floating Skimmer – Payment shall be made at the contract lump sum price. Payment shall include all equipment, labor, materials, and maintenance necessary to install skimmer configurations and keep skimmer functioning properly. Payment also includes removing skimmers upon final stabilization and plugging/grouting hole in outlet control structures.
 9. Erosion Control Blanket – Payment shall be made at the contract lump sum price. Payment shall include all equipment, labor, materials, and maintenance necessary to install and keep erosion control blanket functioning properly.

10. Inlet Protection – Payment will be made at the contract lump sum price. Payment shall include all equipment, labor, materials, and maintenance necessary to install and keep inlet protection functioning properly.
11. Dust Control – There will be no separate payment for dust control. Any costs Connected thereto shall be a subsidiary responsibility of the Contractor.

PART 2 – PRODUCTS

2.1 GRASSING MATERIALS

- A. Refer to Section 02902 – Grassing.
 1. General: All grass seed shall be free from noxious weeds, grade A recent crop, re-cleaned and treated with appropriate fungicide at time of mixture. Deliver to site in original sealed containers with dealer's guarantee as to year grown, percentage of purity, percentage of germination and date of the test by which percentages of purity and germination were determined. All seed sown shall have a date of test within six months of the date of sowing.
 2. Type of Seed: Either Annual Rye or Common Bermuda Grass seed will be used depending on time of year in which seeding is to occur.
 3. Mulch: Straw.
 4. Fertilizer: Commercial balanced 4-12-12 fertilizer.

2.2 HAY BALES

- A. Standard size, densely baled straw or hay, wrapped with synthetic or wire bands (two minimum per bale).

2.3 SILT FENCE

- A. Silt fence shall be a woven geotextile fabric sheet. Fabric shall be a synthetic polymer composed of at least 85% by weight propylene, ethylene, amide, ester, or vinylidene chloride, and shall contain stabilizer and/or inhibitors added to the base plastic to make filaments resistant to deterioration due to ultra-violet and/or heat exposure. Fabric should be finished so the filaments will retain their relative position with respect to each other. Fabric shall be free of defects, rips, holes, or flaws.

Fabric shall meet the following requirements:

Woven Fabrics	
Grab Strength	90 lbs.
Burst Strength	175 PSI
UV Resistance	80%

2.4 CHEMICALS FOR DUST CONTROL

- A. Calcium Chloride, Anionic Asphalt Emulsion, latex Emulsion or Resin-in-Water Emulsion may be used for dust control.

2.5 RIP-RAP

- A. Shall be hard quarry or field stone of such quality the pieces will not disintegrate on exposure to water, sunlight, or weather. Stone shall range in weight from a minimum of 25 pounds to a maximum of 125 pounds. At least 50 percent of the stone shall weigh more than 60 pounds. The stone shall have a minimum dimension of 12 inches.

2.6 EROSION CONTROL BLANKET

- A. Use erosion control blanket SC150, from North American Green or approved equal; see Construction Drawings for installation details.
 - 1. Use Bio stakes where staples are required or indicated on the drawings for stabilization.
 - a. Staple in pattern recommended by blanket manufacturer.
 - 2. Staple locations must be clearly marked on the blanket when stakes are used.
 - 3. Ensure product is rated to last at least 24 months.

2.7 TEMPORARY FLOATING SKIMMER

- A. Use temporary floating skimmer specified on the construction plans. Product should at a minimum be equal to the 6" Faircloth Skimmer.
 - 1. Inlet extension shall be at least 6" in diameter.
 - 2. Skimmer should allow for drainage of pond from the water surface level to provide maximum sediment fallout.

2.8 TEMPORARY POROUS BAFFLES

- A. See product/material requirements specified on Porous Baffle detail.

2.9 PRODUCT REVIEW

- A. Contractor shall provide the Engineer with a complete description of all products before ordering. Engineer will review all products before they are ordered.

PART 3 – EXECUTION

3.1 GENERAL

- A. All disturbed soil areas except those to support paving shall be graded and protected from erosion by grassing. Disturbed areas must be grassed within 14 days of work ending unless work is to begin again before 21 days. Storm water conveyance systems shall have sediment barriers installed at all entrances, intersections, change in direction and discharge points.

3.2 GRASSING

- A. Refer to Section 02902 – Grassing.

3.3 SEDIMENT BARRIERS

- A. Hay Bales for Sheet Flow Applications:

1. Excavate a 4 inch deep trench the width of a bale and length of proposed barrier. Barrier should be parallel to the slope. Place barrier 5 to 6 feet away from toe of slope, unless otherwise instructed.
2. Place bales in the trench with their ends tightly abutting. Corner abutment is not acceptable. A tight fit is important to prevent sediment from escaping through spaces between the bales.
3. Backfill the trench with previously excavated soil and compact it. Backfill soil should conform to ground level on downhill side of barrier and should be built up to 4 inches above ground on uphill side of bales.
4. Inspect and repair or replace damaged bales promptly. Remove hay bales when uphill sloped areas have been permanently stabilized.

- B. Rock Ditch Check

1. Excavate a 6 inch deep trench the width and length of proposed barrier. Install a non-woven geotextile fabric in the trench before placing rock for the ditch check.
2. The body of the ditch check shall be constructed of 12 inch rip-rap. The upstream face may be covered with 1-inch washed stone.
3. Ditch checks shall not exceed a height of 2 feet at centerline of the channel and have a minimum top flow length of 2 feet.
4. Rip-rap shall be placed over the channel banks to prevent water from flowing around ditch check. Rock must be installed by hand or mechanical placement (no dumping of rock) to achieve complete coverage of the ditch and ensure the center of the check is lower than the edges.
5. The maximum spacing between ditch checks shall be where the toe of the upstream check is at the same elevation as the top of the downstream check.
6. Contractor shall maintain ditch checks as required by State regulations.

3.4 SILT FENCE

- A. Silt fence shall be placed at approximate location shown and installed in accordance with the detail on the construction drawings. Contractor shall maintain silt fence as required by state regulations.

3.5 DUST CONTROL

- A. Dust raised from vehicular traffic will be controlled by wetting down access road with water or by the use of a deliquescent chemical, such as calcium chloride, if relative humidity is over 30%. Chemicals shall be applied in accordance with manufacturer's recommendations.
- B. Contractor shall use all means necessary to control dust on and near the work, or off-site borrow areas when dust is caused by operations during performance of work or if resulting from the condition in which any subcontractor leaves the site. Contractor shall thoroughly treat all surfaces required to prevent dust from being a nuisance to the public, neighbors, and concurrent performance of work on site.

3.6 SEDIMENT BASIN

- A. A sediment basin equal in volume to 3,600 cubic feet per disturbed acre is required. The sediment basin/lagoon adjacent to the outfall for the site shall be constructed and stabilized prior to any additional land disturbed activity. Install the sediment marker as shown on construction plans: maintain pond at proper cleanout depth per SCDHEC guidelines (50% storage volume minimum)

3.7 RIP-RAP

- A. Rip-Rap shall be placed at the locations shown and installed in accordance with the detail on the construction drawings.

3.8 CONSTRUCTION EXIT

- A. Construct exit at the location shown per detail on the construction drawings. Contractor shall maintain construction exit as required by state regulations.

3.9 INLET PROTECTION

- A. Install inlet protection per detail on the construction drawings. Contractor shall maintain inlet protection as required by state regulations until all disturbed surfaces are stabilized.

3.10 EROSION CONTROL BLANKET

- A. Provide on areas as shown on the construction plans.

3.11 TEMPORARY FLOATING SKIMMER

- A. Provide as shown on the construction plans in sequence with the pond and sediment basins.

3.12 TEMPORARY POROUS BAFFLES

- A. Construct temporary porous baffles as shown on the construction plans and detail. Baffles shall be installed perpendicular to the length of the sediment basin.

END OF SECTION

INDEX TO
SECTION 02275 – RIP–RAP

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Section Includes	02275–1
1.2	Related Sections	02275–1
1.3	Allowable Tolerances	02275–1
1.4	Measurement and Payment	02275–1
1.5	References	02275–1
PART 2 – PRODUCTS		
2.1	Materials	02275–1
2.2	Product Review	02275–2
PART 3 – EXECUTION		
3.1	Preparation	02275–2
3.2	Placement	02275–2

SECTION 02275**RIP-RAP****PART 1 – GENERAL****1.1 SECTION INCLUDES**

- A. Material placed as bank protection and erosion control.

1.2 RELATED SECTIONS

- A. Section 2210 – Soil Erosion Control

1.3 ALLOWABLE TOLERANCES

- A. Depth of rip-rap blanket as shown on the drawings and in these specifications is a minimum depth.

1.4 MEASUREMENT AND PAYMENT

- A. Rip-Rap: Payment will be made at the contract price. Payment will include furnishing all labor, materials, and equipment and placing on a prepared surface.

1.5 REFERENCES (LATEST REVISION)

- A. ASTM C 150 – Portland Cement.

PART 2 – PRODUCTS**2.1 MATERIALS**

- A. Stone Rip-Rap: Shall be hard quarry or field stone of such quality the pieces will not disintegrate on exposure to water, sunlight or weather. Stone shall be solid and non-friable and range in weight from a minimum of 25 pounds to a maximum of 150 pounds. At least 50 percent of the stone pieces shall weigh more than 60 pounds. The stone pieces shall have a minimum dimension of 12 inches. Documents indicating stone analysis, source and other pertinent data (i.e. – filter fabric) shall be submitted for review by the Engineer prior to delivery.
- B. Sand-Cement Bag Rip-Rap:
 - 1. Bags: Shall be of cotton, burlap, or fiber-reinforced paper capable of containing the sand-cement mixture without leakage during handling and placing. Bags previously used for any purpose shall not be used. Capacity shall be not less than 0.75 cubic foot nor more than two cubic feet.

2. Cement: Portland cement shall be Type I meeting requirements of ASTM C 150. Cement which has been damaged, or which is partially set, lumpy, or caked shall not be used.
 3. Fine Aggregate: Shall be composed of hard, durable particles, free from injurious amounts of organic impurities and shall contain, in the material passing the No. 10 sieve, not more than 7 percent clay, and not more than 20 percent passing the No. 200 sieve.
- C. Filter Fabric: Shall be a woven fabric of monofilament and multifilament yarn equivalent to Mirafi FW700. Fabric shall be finished so the filaments will retain their relative position with respect to each other. Fabric shall contain stabilizers and/or inhibitors added to make filaments resistant to deterioration due to ultraviolet and/or heat exposure. Fabric shall be free of flaws, rips, holes or defects.

2.2 PRODUCT REVIEW

- A. Contractor shall provide the Engineer with a complete description of all products before ordering. Engineer will review all products before they are ordered.

PART 3 – EXECUTION

3.1 PREPARATION

- A. The surface to receive rip-rap shall be prepared to a relatively smooth condition free of obstruction, depressions, debris, rises, and soft or low density pockets of material. Contours and elevations on construction drawings are to the surface of rip-rap material.

3.2 PLACEMENT

- A. Filter fabric shall be placed with the long dimension running up slope. The strips shall be placed to provide a minimum width of one foot of overlap for each joint. Fabric shall be anchored in place with securing pins of the type recommended by fabric manufacturer. Pins shall be placed on or within 3 inches of the overlap. Place fabric so upstream strip will overlap the downstream strip. Fabric shall be placed loosely to give and avoid stretching and tearing during placement of the stones.
- B. Minimum depth or thickness of stone blanket shall be 12 inches with no under tolerance. Stones shall be dropped no more than three feet during construction. Placing shall begin at bottom of slope. Provide a toe trench if required as detailed on the construction drawings. Entire mass of stone shall be placed to conform with lines, grades, and thickness shown on the plans. Rip-rap shall be placed to its full course thickness at one operation and in such a manner as to avoid displacing the underlying material. Placing of rip-rap in layers, or by dumping into chutes, or by similar methods likely to cause segregation, will not be permitted.

Larger stones shall be well distributed and the entire mass of stone shall conform to gradation specified. All material used in rip-rap protection shall be placed

and distributed so there will be no large accumulations of either the larger or smaller sizes of stone.

It is the intent of these specifications to produce a fairly compact rip-rap protection in which all sizes of material are placed in their proper proportions. Hand placing or rearranging of individual stones by mechanical equipment may be required to secure the results specified.

- C. Sand-Cement Bag Rip-Rap: Bags shall be uniformly filled. Bagged rip-rap shall be placed by hand with tied ends facing the same direction, with close, broken joints. After placing, bags shall be rammed or packed against one another to produce the required thickness and form a consolidated mass. The top of each bag shall not vary more than 3 inches above or below required plane. When directed by the Engineer or required by construction drawings, header courses shall be placed.

END OF SECTION

INDEX TO
SECTION 02720 – STORM DRAINAGE

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Section Includes	02720-1
1.2	Related Sections	02720-1
1.3	Options	02720-1
1.4	References	02720-1
1.5	Quality Assurance	02720-2
1.6	Product Delivery, Storage, and Handling	02720-3
1.7	Sequencing and Scheduling	02720-3
1.8	Alternatives	02720-3
1.9	Guarantee	02720-3
1.10	Existing Utilities	02720-3
1.11	Measurement and Payment	02720-4
1.12	Testing	02720-4
PART 2 – PRODUCTS		
2.1	Pipe	02720-5
2.2	Drainage Structures	02720-6
2.3	Filter Fabric	02720-7
2.4	Tracing Wire – Omitted	02720-7
2.5	Soils and Stone Aggregates	02720-7
2.6	Product Review	02720-8
PART 3 – EXECUTION		
3.1	On Site Observations of Work	02720-8
3.2	Excavation for Pipe and Structures	02720-9
3.3	Trenching for Pipe	02720-9
3.4	Protection of Utility Lines	02720-9
3.5	Foundation and Bedding	02720-10
3.6	Haunching, Initial Backfill, and Final Backfill	02720-11
3.7	Placing Pipe	02720-11-12
3.8	Joints in Pipes	02720-12
3.9	Field Quality Control	02720-13-14
3.10	Drainage Structures	02720-14
3.11	Remove and Replace Pavement	02720-15
3.12	Connect Pipe to Existing Structures	02720-15

SECTION 02720
STORM DRAINAGE

PART 1 – GENERAL

1.1 SECTION INCLUDES

- A. Construction of pipes, drainage inlets, manholes, headwalls, and various drainage structures.

1.2 RELATED SECTIONS

- A. Section 02210 – Soil Erosion Control

1.3 OPTIONS

- A. The bid form and specifications describe several pipe materials. Where manufacturers of material or equipment are named in the specifications, Contractor may use equipment or materials of other manufacturers provided they are reviewed and accepted by Engineer as equivalent to those specified.

1.4 REFERENCES (Latest Revision)

- A. ASTM B 745/B 745M – Corrugated Aluminum Pipe for Sewers and Drains.
- B. ASTM C 55 – Concrete Building Brick.
- C. ASTM C 62 – Building Brick (Solid Masonry Units Made From Clay or Shale).
- D. ASTM C 76 – Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe.
- E. ASTM C 144 – Aggregate for Masonry Mortar.
- F. ASTM C 150 – Portland Cement.
- G. ASTM C 207 – Hydrated Lime for Masonry Purposes.
- H. ASTM C 443 – Joints for Concrete Pipe and Manholes, Using Rubber Gaskets.
- I. ASTM C 478 – Precast Reinforced Concrete Manhole Sections.
- J. ASTM C 913 – Precast Concrete Water and Wastewater Structures.
- K. ASTM C 1433 – Precast Reinforced Concrete Monolithic Box Sections for Culverts, Storm Drains, and Sewers.
- L. ASTM D 1056 – Flexible Cellular Materials – Sponge or Expanded Rubber.

- M. ASTM D 698 – Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort.
- N. ASTM D 1751 – Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Non-extruding and Resilient Bituminous Types).
- O. ASTM D 1752 – Preformed Sponge Rubber Cork and Recycled PVC Expansion Joint Fillers for Concrete Paving and Structural Construction.
- P. ASTM D 2321 – Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity Flow Applications.
- Q. ASTM D 3212 – Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals.
- R. ASTM D 3740 – Minimum Requirements for Agencies Engaged in Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction.
- S. ASTM D 6938 – In Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth).
- T. ASTM E 329 – Agencies Engaged in Construction Inspection, Testing, or Special Inspection.
- U. ASTM F 405 – Corrugated Polyethylene (PE) Pipe and Fittings.
- V. ASTM F 477 – Elastomeric Seals (Gaskets) for Joining Plastic Pipe.
- W. ASTM F667 – 3 through 24 in. Corrugated Polyethylene Pipe and Fittings.
- X. ASTM F 2306/F 2306M – 12 to 60-Inch (300 to 1,500 mm) Annular Corrugated Profile-Wall Polyethylene (PE) Pipe and Fittings for Gravity-Flow Storm Sewer and Subsurface Drainage Applications.
- Y. AASHTO M 294 – Corrugated Polyethylene Pipe, 300 to 1500-mm (12 – to 60-in.) Diameter.

1.5 QUALITY ASSURANCE

- A. Material Review – Contractor will furnish the Engineer and Owner a description of all material before ordering. Engineer will review the Contractor's submittals and provide in writing an acceptance or rejection of material.
- B. Manufacturer – Material and equipment shall be standard products of a manufacturer who has manufactured them for a minimum of 2 years and provides published data on their quality and performance.
- C. Subcontractor – A subcontractor for any part of the work must have experience on similar work, and if required, furnish Engineer with a list of projects and Owners or Engineers who are familiar with their competence.

- D. Design – Devices, equipment, structures, and systems not designed by Engineer and Contractor wishes to furnish, shall be designed either by a Registered Professional Engineer or by someone the Engineer accepts as qualified. If required, complete design calculations and assumptions shall be furnished to the Engineer or Owner before ordering.
- E. Testing Agencies – Soil tests shall be taken by a testing laboratory operating in accordance to ASTM D-3740 and E-329 and be acceptable to the Engineer prior to engagement. Mill certificates of tests on materials made by manufacturers will be accepted provided the manufacturer maintains an adequate testing laboratory, makes regularly scheduled tests, spot checked by an outside laboratory and furnishes satisfactory certificates.

1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Material shall be unloaded in a manner avoiding damage and shall be stored where it will be protected and will not be hazardous to traffic. Contractor shall repair any damage caused by the storage. Material shall be examined before installation. Neither damaged nor deteriorated material shall be used in the work.

1.7 SEQUENCING AND SCHEDULING

- A. Contractor shall arrange work so sections of pipes between structures are backfilled, checked, pavement replaced, and the section placed in service as soon as reasonable after installation.

1.8 ALTERNATIVES

- A. The intention of these specifications is to produce the best system for the Owner. If Contractor suggests alternate material, equipment or procedures will improve results at no additional cost, the Engineer and Owner will examine suggestion, and if accepted, it may be used. The basis upon which acceptance of an alternate will be given is its value to Owner and not for Contractor's convenience.

1.9 GUARANTEE

- A. Contractor shall guarantee quality of materials, equipment, and workmanship for a minimum period of 12 months or as required by the local governing agency after acceptance. Defects discovered during this period shall be repaired by Contractor at no cost to the Owner.

1.10 EXISTING UTILITIES

- A. All known utility facilities are shown schematically on the construction drawings, and are not necessarily accurate in location as to plan or elevation. Utilities such as service lines or unknown facilities not shown will not relieve the Contractor of responsibility under this requirement. "Existing Utilities Facilities" means any utility existing on the project in its original, relocated, or newly installed position. Contractor will be held responsible for cost of repairs to damaged underground facilities, even when such facilities are not shown on the drawings.

- B. The Contractor shall call for underground utility locations before starting work. Underground utilities location service can be contacted at 1-888-721-7877 (SC).

1.11 MEASUREMENT AND PAYMENT

- A. Pipe Culverts and Storm Drains – Payment will be made at the contract lump sum price. Payment of which will constitute full payment for all pipe, joints, filter fabric and bedding, including trenching, dewatering, excavation, backfill and compaction, surface clean-up, and all incidental labor and material necessary to complete the construction of pipe as required by this section of specifications.
- B. Drainage Structures – Payment will be made at the contract lump sum price. Payment will constitute full payment for all dewatering, excavation, formwork, precast concrete, backfill, compaction, frames, gratings or covers, concrete, brick and all miscellaneous materials, surface clean-up and labor necessary to complete the construction.

1.12 TESTING

- A. Laboratory tests for moisture density relationship for fill materials shall be in accordance with ASTM D 698, (Standard Proctor).
- B. In place density tests in accordance with ASTM D 6938.
- C. Testing laboratory shall operate in accordance with ASTM D 3740 and E 329 and be acceptable to the Engineer.
- D. Testing laboratory and Project Engineer/Project Representative shall be given a minimum of 48-hours' notice prior to taking any tests.
- E. Owner shall select and engage the testing laboratory. Testing laboratory shall be responsible to the Owner and Owner's Engineer. Payment for laboratory and all tests shall be by Owner, except Owner specifically reserves the right to deduct from Contractor's payment, expenses and charges of testing laboratory when:
 - 1. Contractor gives notice work is ready for inspection and testing, and fails to be ready for the test, and/or
 - 2. testing of the Contractor's work, products, or materials fail, and retesting is required, and/or
 - 3. Contractor abuses the services or interferes with work of testing laboratory in conduct of this work.
- F. Test results shall be furnished to the Engineer prior to continuing with associated or subsequent work.

PART 2 – PRODUCTS

2.1 PIPE

- A. Concrete Pipe – Shall be reinforced Class III, Class IV, or Class V and shall conform to ASTM Specification C-76. Pipe less than 48 inch inside diameter shall be manufactured without lifting holes. Joints shall be either 'O' ring watertight flexible rubber, or tongue and groove as indicated on the plans. Gasketed single offset joints may be used in lieu of 'O' ring joints if acceptable to the Engineer.
1. 'O' Ring Joints – Shall be water tight flexible rubber gasket and shall meet ASTM Specification C-443.
 2. Gasketed single offset joint shall be soil tight and shall meet ASTM Specification C-443.
 3. Tongue and groove joints shall utilize mastic sealant and the exterior shall be wrapped with geotextile material.
- B. Corrugated Aluminum Alloy Pipe – Shall conform to ASTM B745. Pipe may be annular or helical.
1. Joints – Coupling bands shall be one piece lap-type, having a width conforming to the pipe manufacturer's recommendations. They shall be of the angle lug, rod and lug, or U-bolt type. The type, size, and gauge of bands and size of angles, bolts, and rods shall be as specified in applicable standards or specifications for pipe. Exterior rivet heads in the longitudinal seam under coupling band shall be countersunk or rivets shall be omitted and the seam welded.
 2. Gaskets – Gaskets shall be made of 3/8 inch thick by 6-1/2 inch minimum width closed cell expanded synthetic rubber, fabricated in the form of a cylinder with a diameter approximately 10% less than nominal pipe size. The gasket material shall conform to requirements of ASTM D1056, Grade Number SBE-43.
 3. Bends – Where specified, shall be shop fabricated to angles and dimensions shown on the construction drawings.
- C. Polyethylene – Shall be high density polyethylene corrugated pipe having an integrally formed smooth interior, equivalent to Advanced Drainage Systems N-12WT, N-12STIB or Hancor Blue Seal or Sure-Lok ST. Pipe shall conform to ASTM F667 and F2306.
1. Joints – Pipe shall be joined using an integral bell and spigot joint meeting ASTM F2306 specifications. The joint shall be soil and water tight and gaskets, when applicable, shall meet requirements of ASTM F477. A joint lubricant supplied by manufacturer shall be used on the gasket and bell during assembly.
- D. Subgrade Drain – Shall be heavy duty corrugated polyethylene perforated pipe manufactured by Advanced Drainage Systems (ADS) or equivalent and shall conform to ASTM F-405.

2.2 DRAINAGE STRUCTURES

- A. Details – See plans.
- B. Concrete – Reinforced and non-reinforced.
 - 1. Minimum compressive strength = 3,000 p.s.i. at 28 days.
 - 2. Reinforcing shall be covered by a minimum 1-inch of concrete for top slabs and 1-1/2 inches for walls and bases and 3 inches where concrete is deposited directly against the ground.
 - 3. Expansion joint filler materials shall conform to ASTM D 1751 or D 1752.
- C. Mortar – Connection of pipe and drainage structures shall be composed of one part by volume of Portland cement and two parts of sand. The Portland cement shall conform to ASTM C-150, Type I or II. The sand shall conform to ASTM C-144 and shall be of an accepted gradation. Hydrated lime may be added to the mixture of sand and cement in an amount equal to 25% of cement volume used. Hydrated lime shall conform to ASTM C-207, Type S. Quantity of water in the mixture shall be sufficient to produce a workable mortar, but shall in no case exceed 7 gallons of water per sack of cement. Water shall be clean and free of harmful acids, alkalies, and organic impurities. The mortar shall be used within 30 minutes from time ingredients are mixed with water.
- D. Brick Masonry – Brick shall conform to ASTM Specification C-62, Grade SW or C-55, Grade S. Mortar for jointing and plastering shall consist of one part Portland cement and two parts fine sand. Lime may be added to the mortar in an amount not more than 25% of the cement volume used. Joints shall be completely filled and shall be smooth and free from surplus mortar on the inside of structure. Brick structures shall be plastered with 1/2 inch of mortar over entire outside surface of the walls. For square or rectangular structures, brick shall be laid in stretcher courses with a header course every sixth course, and for round structures, brick shall be laid radially with every sixth course a stretcher course.
- E. Precast – Shall be constructed in accordance with ASTM C-478, C-913, or C-1433 and conform to details on the project drawings.
 - 1. Joints – Shall be tongue and groove sealed with flexible gaskets or mastic sealant. Gaskets shall be O-Ring or Type A or B "Tylox" conforming to ASTM C443 and mastic shall be "Ram-nek" or equivalent with primer. Primer shall be applied to all contact surfaces of manhole joints at the factory in accordance with manufacturer's instructions.
 - 2. Steps – Shall be polypropylene equivalent to M.A. Industries, Type PS-1 or PS-1-PF. Steps shall be installed at the manhole factory and in accordance with recommendations of step manufacturer. Manholes will not be acceptable if steps are not installed accordingly.
 - 3. Leaks – No leaks in the manhole will be acceptable. All repairs made from inside the manhole shall be made with mortar composed of one part

portland cement and two parts clean sand; mixing liquid shall be straight bonding agent equivalent to "Acryl 60."

- F. Frame, cover & grating shall conform to details shown on the project drawings. Grates in pavement and in other flush-mounted type surfaces shall be of a "bicycle-safe" configuration consisting of 45-degree diagonal bars or slotted grates with a maximum clear opening of 1 inch and a maximum length of 9-inches. In any case, the long dimension of openings should be located transverse to direction of traffic when possible.

2.3 FILTER FABRIC

- A. Shall be a non-woven heat-bonded fiber of polypropylene and nylon filaments equivalent to Mirafi 140 N. The fabric shall be finished so filaments will retain their relative position with respect to each other. Fabric shall contain stabilizers and/or inhibitors added to the base plastic to make filaments resistant to deterioration due to ultraviolet and/or heat exposure. The product shall be free of flaws, rips, holes, or defects.

2.4 TRACING WIRE

Omitted

2.5 SOILS AND STONE AGGREGATES

- A. Stone aggregate shall be clean crushed granite or concrete meeting the gradation requirements of grade No. 57.
- B. Soils used for bedding, haunching, and initial backfill shall be as shown in the following table and shall meet requirements and classifications of ASTM D2321 and ASTM D2487.

Class	Type	Soil Group Symbol D 2487	Description	Percentage Passing Sieve Sizes		
				1-1/2 inch (40 mm)	No. 4 (4.75 mm)	No. 200 (0.075 mm)
IB	Manufactured, Processed Aggregates; dense-graded, clean.	None	Angular, crushed stone (or other Class 1A materials) and stone/sand mixtures with gradations selected to minimize migration of adjacent soils; contain little or no fines.	100%	≤50%	<5%
II	Coarse – Grained Soils, clean	GW	Well-graded gravels and gravel-sand mixtures; little or no fines.	100%	<50% of "Coarse Fraction"	<5%
		GP	Poorly-graded gravels and gravel-sand mixtures; little or no fines.			
		SW	Well-graded sands and gravelly sands; little or no fines.		>50% of "Coarse"	

		SP	Poorly-graded sands and gravelly sands; little or no fines.		Fraction "	
	Coarse-Grained Soils; borderline clean to w/fines.	Eg. GW-GC, SP-SM.	Sands and gravels that are borderline between clean and with fines.	100%	Varies	5% to 12%
III	Coarse-Grained Soils with Fines	GM	Silty gravels, gravel-sand-silt mixtures.	100%	<50% of "Coarse Fraction "	5%
		GC	Clayey gravels, gravel-sand-clay mixtures.			
		SM	Silty sands, sand-silt mixtures.		>50% of "Coarse Fraction "	
		SC	Clayey sands, sand-clay mixtures.			
IVA	Fine-grained soils (inorganic)	ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands, silts with slight plasticity.	100%	100%	>50%
		CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays.			

2.4 PRODUCT REVIEW

- A. Contractor shall provide the Engineer with a complete description of all products before ordering. Engineer will review all products by the submittal of shop drawings before they are ordered.

PART 3 – EXECUTION

3.1 ON SITE OBSERVATIONS OF WORK

- A. The line, grade, deflection, and infiltration of storm sewers shall be tested by Contractor under direction of Engineer. Owner's Representative or Engineer will have the right to require any portion of work be completed in their presence and if work is covered up after such instruction, it shall be exposed by Contractor for observation. However, if Contractor notifies Engineer such work is scheduled and the Engineer fails to appear within 48-hours, Contractor may proceed. All work completed and material furnished shall be subject to review by the Engineer or Project Representative. All improper work shall be reconstructed. All materials not conforming to requirements of specifications shall be removed from the work upon notice being received from Engineer for rejection of such materials. Engineer shall have the right to mark rejected materials to distinguish them as such.

Contractor shall give the Project Engineer or Project Representative a minimum of 48-hours' notice for all required observations or tests. Storm sewers shall be dry for observation by the Engineer. Lines under water shall be pumped out by Contractor prior to observation, at no additional cost to the Owner.

It will also be required of Contractor to keep accurate, legible records of the location of all storm sewer lines and appurtenances. These records will be prepared in accordance with paragraph on "Record Data and Drawings" in the Special Conditions. Final payment to the Contractor will be withheld until all such information is received and accepted.

3.2 EXCAVATION FOR PIPE AND STRUCTURES

- A. Excavated material shall be piled a sufficient distance from the trench banks to avoid overloading to prevent slides or cave-ins.
- B. Remove from site all material not required or suitable for backfill.
- C. Grade as necessary to prevent water from flowing into excavations.
- D. Remove all water accumulating in the excavation, from surface flow, seepage, or otherwise, by pumping or other acceptable method.
- E. Sheet piling, bracing or shoring shall be used as necessary for protection of the work and safety of personnel.

3.3 TRENCHING FOR PIPE

- A. Trenching for Pipe – The width of trenches at any point below top of pipe shall be not greater than outside diameter of pipe plus 4 feet to permit satisfactory jointing and thorough bedding, haunching, backfilling and compacting under and around pipes. Sheet piling and bracing where required shall be placed within the trench width as specified. Care shall be taken not to over-excavate. Where trench widths are exceeded, redesign with a resultant increase in cost of stronger pipe or special installation procedures shall be necessary. Cost of this re-design and increased cost of pipe or installation shall be borne by Contractor without additional cost to the Owner. When installing pipe in a positive projecting embankment installation, the embankment shall be installed to an elevation of at least 1 foot above top of pipe for a width of five pipe diameters on each side of pipe before installation of pipe.
- B. Removal of Unsuitable Material – Where wet or otherwise unstable soil, incapable of supporting the pipe is encountered in bottom of trench, such material shall be removed to depth required and replaced to proper grade with stone or sand foundation as determined by Engineer. This foundation shall be compacted to 95% modified proctor.

3.4 PROTECTION OF UTILITY LINES

- A. Existing utility lines shown on drawings or locations of which are made known to the Contractor prior to excavation, and are to be retained, as well as utility lines constructed during excavation operations, shall be protected from damage during excavation and backfilling, and if damaged, shall be repaired at Contractor's expense. If the Contractor damages any existing utility lines not shown on drawings or locations of which are not known to Contractor, report thereof shall be made immediately. If Engineer determines repairs shall be made by Contractor, such repairs will be ordered under the clause in GENERAL

CONDITIONS of contract entitled "CHANGES." When utility lines to be removed are encountered within the area of operations, Contractor shall notify Engineer in ample time for necessary measures taken to prevent interruption of service.

3.5 FOUNDATION AND BEDDING

- A. Stone Foundation – Where the subgrade of pipe is unsuitable material, Contractor shall remove unsuitable material to a depth determined by Engineer or Geotechnical Consultant and furnish and place stone foundation in trench to stabilize subgrade.
- B. Sand Foundation – Where the character of soil is unsuitable, even though dewatered, additional excavation to a depth determined by Engineer or Geotechnical Consultant shall be made and replaced with clean sand furnished by Contractor.
- C. Bedding for pipe shall provide a firm surface of uniform density throughout the entire length of pipe. Before laying pipe, trench bottom shall be de-watered by the use of well points. Where well points will not remove the water, Contractor shall construct sumps and use pumps to remove all water from bedding surface. Pipe shall be carefully bedded in stone accurately shaped and rounded to conform to lowest 1/3 outside portion of circular pipe, or lower curved portion of arch pipe for the entire length of pipe. Bell holes and depressions for joints shall be only of such length, depth, and width as required for properly making the particular type joint.
- D. Concrete Pipe:
 - 1. Materials for bedding concrete pipe shall be either Class II, Class III, or Class IB if processed, to minimize migration of adjacent material.
 - 2. Depth of bedding shall be equal to 1/24 the outer diameter of pipe or 3 inches, whichever is greater.
 - 3. Bedding area under the center of pipe, for a width 1/3 outer diameter of pipe, known as middle bedding, shall be loosely placed. Remainder of bedding for full width of the trench shall be compacted to a minimum density of 85% for Class II bedding and 90% for Class III bedding as determined by ASTM D1557.
- E. Polyethylene and Corrugated Aluminum Alloy Pipe
 - 1. Materials for bedding polyethylene and corrugated aluminum alloy pipe shall be either Class II, Class III, or Class IB if processed to minimize migration of adjacent materials.
 - 2. Depth of bedding shall be equal to 1/10 the outer diameter of pipe or a minimum of 6 inches, whichever is greater.
 - 3. Bedding area under the center of pipe, for a width 1/3 outer diameter of pipe, known as middle bedding, shall be loosely placed. Remainder of

bedding for full width of the trench shall be compacted to a minimum density of 90% for Class II bedding and 95% for Class III bedding.

3.6 HAUNCHING, INITIAL BACKFILL, AND FINAL BACKFILL

- A. Haunching – After the bedding has been prepared and pipe is installed, Class II or Class III soil shall be placed along both sides of pipe, in layers not exceeding 6 inches in compacted depth. Care shall be taken to insure thorough compaction and fill under haunches of the pipe. Each layer shall be thoroughly compacted with mechanical tampers and rammers. Haunching shall extend up to the spring line of pipe and be compacted to following densities:
1. RCP: Minimum density shall be 90% as determined by ASTM D1557.
 2. HDPE and Corrugated Aluminum Alloy Pipe: Minimum density shall be 95% as determined by ASTM D1557.
- B. Initial Backfill – HDPE and corrugated aluminum alloy pipe require initial backfill material of either Class II or Class III soils to be placed from the spring line to a minimum of 6 inches above top of pipe in 6-inch lifts. This initial backfill shall be compacted to a minimum density of 95% as determined by ASTM D1557. Reinforced concrete pipe does not specifically require initial backfill. Initial backfill for reinforced concrete pipe can be the same as final backfill.
- C. Final Backfill – For all pipes, it should extend to the surface and shall be select materials compacted to a minimum of 98% as determined by ASTM D1557 if pipe is under pavement. If pipe is in grassed areas final backfill may be native materials compacted to a minimum density of 90% as determined by ASTM D1557.

3.7 PLACING PIPE

- A. Each pipe shall be carefully examined before being laid and defective or damaged pipe shall not be used. Pipe lines shall be laid to the grades and alignment indicated. Proper facilities shall be provided for lowering sections of pipe into trenches. Under no circumstances shall pipe be laid in water, and no pipe shall be laid when trench conditions or weather are unsuitable for such work. Diversion of drainage or dewatering of trenches during construction shall be provided as necessary. All pipe in place shall have been checked before backfilling. When storm drain pipe terminates in a new ditch, headwall or end section, together with ditch pavement, if specified, shall be constructed immediately as called for on the plans. Ditch slopes and disturbed earth areas shall be grassed and mulched as required. Contractor will be responsible for maintaining these newly constructed ditches and take immediate action subject to acceptance, keeping erosion of the ditch bottom and slopes to a minimum during life of contract. No additional compensation will be given to Contractor for the required diversion of drainage and/or dewatering of trenches. Grassing the trench backfill shall conform to requirements of Section 02902 – “Grassing.”
- B. Concrete Pipe: Laying shall proceed upgrade with spigot ends of bell and spigot pipe and tongue ends of tongue and groove pipe pointing in the direction of flow. Place pipe in trench with the invert conforming to required elevations,

slopes, and alignment. Provide bell holes in pipe bedding in order to insure uniform pipe support. Fill all voids under the pipe by working in backfill material.

- C. Corrugated Aluminum Pipe: Shall be laid with separate sections joined firmly together, with outside laps of circumferential joints pointing upstream and with longitudinal laps on the side. Lifting lugs, where used, shall be placed to facilitate moving the pipe without damage to exterior or interior coatings. Place pipe in trench with the invert conforming to required elevations, slopes, and alignment. Fill all voids under the pipe by working in backfill material.
- D. Polyethylene Pipe – Laying shall proceed upgrade with spigot ends of bell and spigot pipe pointing in the direction of flow. Place pipe in trench with the invert conforming to required elevations, slopes, and alignment. Provide bell holes in pipe bedding in order to ensure uniform pipe support. Fill all voids under the pipe by working in bedding material. Pipe shall be installed in accordance with ASTM D-2321.
- E. Subgrade Drain Tubing – Shall be laid as detailed on construction drawings with the invert conforming to required elevations and alignment.

3.8 JOINTS IN PIPES

- A. Concrete Pipe – Joints in concrete pipe shall be either 'O' ring watertight flexible rubber or tongue and groove as indicated on the plans. Gasketed, single offset joints may be used if accepted by the Engineer. Maintain pipe alignment and prevent infiltration of fill material at joints during installation.
 - 1. 'O' ring and single offset joints shall meet the requirements of ASTM C443. They shall utilize either a rubber gasket with a circular cross section or a rectangular cross section. Gaskets shall have no more than one splice, except two splices of the gasket will be permitted if nominal diameter of pipe exceeds 54 inches. Manufacturer's recommendations and requirements shall be followed.
 - 2. Tongue and groove joints shall utilize a bituminous mastic such as Ram- Nek or accepted equivalent. The joint surfaces shall be primed according to manufacturer's recommendations. Care shall be taken to insure mastic material completely and uniformly seals the joint.
 - 3. All tongue and groove joints shall receive one layer of filter fabric completely around exterior of the joint. Filter fabric shall be a minimum of 2 feet wide, centered on the joint, and overlapped a minimum of 1 foot.
- B. Corrugated Aluminum Pipe – Maintain pipe alignment and prevent infiltration of fill material at joints during installation.
 - 1. Installation of Gaskets – Shall be in accordance with recommendations of the manufacturer in regard to use of lubricants and cements and other special installation requirements. Gasket shall be placed over one end of a section of pipe for half the width of a gasket. The other half shall be doubled over end of same pipe. When adjoining section of pipe is in place, the double-over half of gasket shall then be rolled over the

adjoining section. Any unevenness in overlap shall be corrected so gasket covers ends of pipe sections equally. Connecting bands shall then be centered over the adjoining sections of pipe, and rods or bolts placed in position and nuts tightened. The band shall be tightened evenly. Tension shall be kept on rods or bolts and gasket shall be closely observed to see it is seating properly in the corrugations.

2. Installation of Filter Fabric at Joint – After the connecting band has been tightened; Contractor shall place one layer of filter fabric completely around exterior of joint, a minimum of 2 feet wide, centered on joint, and overlapped a minimum of 1 foot.
- C. Polyethylene and PVC Pipe – Maintain pipe alignment and prevent infiltration of fill material at joints during installation.
1. Joints shall be gasketed soil-tight and water-tight bell and spigot meeting ASTM F2306. Gaskets shall meet the requirements of ASTM F477. A joint lubricant supplied by manufacturer shall be used on the gasket and bell during assembly. Spigot end of pipe shall be inserted into bell using methods recommended by the manufacturer. Pipe shall be kept true to line and grade during assembly.
 2. Installation of Filter Fabric at Joint – All polyethylene pipe joints shall receive one layer of filter fabric completely around exterior of the joint. Filter fabric shall be a minimum of 2 feet wide, centered on the joint, and overlapped a minimum of 1 foot.
- D. Subgrade Drain Tubing – Joints shall be joined using snap couplings. When installing sock wrapped pipe, overlap sock ends over coupling and secure with polyethylene tape.

3.9 FIELD QUALITY CONTROL

- A. Owner shall select and engage the testing laboratory. Laboratory tests of the soil shall be made in accordance with ASTM D 698. In-place density tests shall be made in accordance with ASTM D 6938. Results of tests shall be furnished to the Engineer.

The minimum number of tests required shall be:

Haunching and Initial Backfill in all areas....	1 per 100-linear feet of pipe, minimum of one per run of pipe for both the haunching and initial backfill zones.
Final Backfill over pipe in traffic areas.....	1 per 100-linear feet or less for each 4-feet of depth or portion thereof.
Final Backfill over pipe in non-traffic areas.....	1 per 500-linear feet or less for each 6-feet of depth or portion thereof.

The minimum percent of compaction of the backfill material (in accordance to ASTM D698) shall be the following:

In traffic Areas. 98% of maximum laboratory density.

In non-traffic Areas . . 95% of maximum laboratory density, unless otherwise accepted by the Engineer.

- B. It is the Contractor's responsibility to assure backfill is sufficient to limit pipe deflection to no more than 5%. When flexible pipe is used, a deflection test shall be made by the Contractor on entire length of installed pipeline, not less than 30-days after completion of all backfill and placement of any fill. Deflection shall be determined by use of a deflection device or by use of a spherical, spheroidal, or elliptical ball, a cylinder, or circular sections fused to a common shaft. The ball, cylinder, or circular sections shall have a diameter, or minor diameter as applicable, of 95% the inside pipe diameter. The ball, cylinder, or circular sections shall be of a homogeneous material throughout, shall have a density greater than 1.0 as related to water at 39.2 degrees F, and shall have a surface brinell hardness of not less than 150. The device shall be center bored and through bolted with a 1/4 inch minimum diameter steel shaft having a yield strength of 70,000 p.s.i. or more, with eyes at each end for attaching pulling cables. The eye shall be suitably backed with flange or heavy washer; a pull exerted on opposite end of shaft shall produce compression throughout remote end of ball, cylinder, or circular section. Circular sections shall be spaced so the distance from external faces of front and back sections shall equal or exceed diameter of circular section. Failure of the ball, cylinder, or circular section to pass freely through a pipe run, either by being pulled through by hand or by being flushed through with water, shall be cause for rejection of a run. When a deflection device is used for the test in lieu of a ball, cylinder, or circular sections described, such device shall be given acceptance prior to use. Device shall be sensitive to 1.0% of pipe diameter being measured and shall be accurate to 1.0% of the indicated dimension. Installed pipe showing deflections greater than 5% of normal pipe diameter shall be retested by a run from the opposite direction. If retest also fails, the suspect pipe shall be repaired or replaced at no cost to Owner.

3.10 DRAINAGE STRUCTURES

- A. Drainage structures shall be constructed of materials specified for each type and in accordance with details shown on the drawings.

3.11 REMOVE AND REPLACE PAVEMENT

- A. Pavement shall only be removed after prior written authorization by the Owner. Pavement removed and replaced shall be constructed in accordance with latest specifications of the State Department of Transportation. Traffic shall be maintained and controlled per State Department of Transportation regulations.

3.12 CONNECT PIPE TO EXISTING STRUCTURES

- A. Contractor shall connect pipe to the existing structure where indicated. For brick or precast structures, a hole not more than 4 inches larger than outside diameter

of new pipe shall be cut or cored neatly in the structure, new pipe laid so it is flush with inside face of structure, and annular space around pipe filled with a damp, expanding mortar or grout to make a watertight seal.

END OF SECTION

INDEX TO
SECTION 02902 - GRASSING

Paragraph	Title	Page
PART 1 – GENERAL		
1.1	Section Includes	02902-1
1.2	Related Work	02902-1
1.3	Delivery, Storage & Handling	02902-1
1.4	Planting Dates	02902-1
1.5	Measurement and Payment	02902-1
PART 2 – PRODUCTS		
2.1	Seed	02902-2
2.2	Seeding Schedule	02902-2
2.3	Fertilizer	02902-2
2.4	Lime	02902-2
2.5	Sprig	02902-2
2.6	Sprigging Schedule	02902-2
2.7	Sod	02902-3
2.8	Accessories	02902-3
2.9	Product Review	02902-3
PART 3 – EXECUTION		
3.1	Preparation	02902-3
3.2	Stand of Grass	02902-4
3.3	Seeding and Sprigging Dates	02902-4
3.4	Applying Lime and Fertilizer	02902-4
3.5	Seeding	02902-5
3.6	Seed Protection (Straw Mulch)	02902-5
3.7	Seed Protection (Excelsior Mulch)	02902-5
3.8	Seed Protection (Wood Cellulose Fiber Mulch)	02902-5
3.9	Sprigging	02902-6
3.10	Sodding	02902-6
PART 4 – MAINTENANCE, WARRANTY AND ACCEPTANCE		
4.1	Maintenance	02902-7
4.2	Warranty	02902-7
4.3	Acceptance	02902-7

SECTION 02902

GRASSING

PART 1 – GENERAL

1.1 SECTION INCLUDES

- A. Seeding, planting grass, and fertilizing graded areas behind the structures, pipeline rights-of-way, roadway shoulders and other disturbed areas.
- B. Seed protection.
- C. Maintaining seeded areas until final acceptance.

1.2 RELATED WORK

- A. Civil and Landscape plans and specifications.

1.3 DELIVERY, STORAGE, AND HANDLING

- A. Deliver grass seed in original containers showing analysis of seed mixture, percentage of pure seed, year of production, net weight, date of packaging, and location of packaging. Damaged packages are not acceptable. Store in cool, dry locations away from contaminants.
- B. Deliver fertilizer in waterproof bags showing weight, chemical analysis, and name of manufacturer. Damaged bags are not acceptable. Store in cool, dry locations away from contaminants.
- C. All material shall be acceptable to Engineer prior to use.

1.4 PLANTING DATES

- A. This specification provides for establishment of a permanent grass cover between the dates of March 1 and September 30. If finished earth grades are not completed in time to permit planting and establishment of permanent grass during the favorable season between dates specified above unless otherwise accepted, Contractor will be required to plant a temporary cover to protect new graded areas from erosion and to keep windborne dust to a minimum. The temporary cover shall be planted between October 1 and February 28 unless otherwise permitted.

1.5 MEASUREMENT AND PAYMENT

- A. When the season or stage of project is such results of grassing work cannot be determined, conditional acceptance will be made on work completed. When conditional acceptance is made for items of work covered, Contractor shall be entitled to 50% of bid price for the actual work placed and shall receive remaining 50% of bid price when final acceptance is made. Conditional acceptance shall not apply to the remaining items of work, and full bid price payment shall be made when work is acceptably placed and completed in accordance with specifications.

- B. Payment for grassing will be made at contract lump sum price for the item "Grassing" and such payment shall constitute full compensation for furnishing and placing seed and fertilizer where directed and protecting and maintaining seed in all graded and disturbed areas.

PART 2 – PRODUCTS

- A. Contractor shall submit source and species certification documents to Engineer and Owner's Representative for review prior to installation. Supply complete information on all analysis/test methodologies and results; laboratory certifications, manufacturer's specifications, and agency approvals to the Landscape Architect/Project Engineer prior to placement of soil mixtures. In addition, provide the Landscape Architect/Project Engineer with thoroughly mixed sample of soil mixes for acceptance prior to placement. Landscape Contractor shall make modifications and improvements to soil mixes deemed necessary by the soil analysis to meet requirements specified here in before, and to ensure proper growing medium for plant material.

2.1 SEED

- A. All seed shall conform to State Laws and requirements and regulations of the State Department of Agriculture.
- B. The varieties of seed, as specified in Section 2.2, shall be individually packaged or bagged, and tagged to show name of seed, net weight, origin, germination, lot number, and other information required by the State Department of Agriculture.
- C. Engineer reserves the right to test, reject, or accept all seed before seeding.

2.2 SEEDING SCHEDULE

- A. See construction plans for seeding schedule.

2.3 FERTILIZER

- A. Commercial fertilizer of accepted type, conforming to State fertilizer laws at the rate as recommended by soils test.

2.4 LIME

- A. Agricultural grade, ground limestone at the rate as recommended by soils test.

2.5 SPRIG

- A. Omitted

2.6 SPRIGGING SCHEDULE

- A. Omitted

2.7 SOD

- A. Omitted

2.8 ACCESSORIES

- A. Straw Mulch: Oat or wheat straw, reasonably free from weeds, foreign matter detrimental to plant life, and in dry condition.
- B. Excelsior Mulch: Excelsior mulch shall consist of wood fibers cut from sound, green timber. The average length of fibers shall be 4 to 6 inches. Cut shall be made in such a manner as to provide maximum strength of fiber, but at a slight angle to natural grain of the wood to cause splintering of fibers when weathering in order to provide adherence to each other and to soil.
- C. Wood cellulose fiber shall be made from wood chip particles manufactured particularly for discharging uniformly on the ground surface when dispersed by a hydraulic water sprayer. It shall remain in uniform suspension in water under agitation and blend with grass seed and fertilizer to form a homogenous slurry. Mulch fibers shall intertwine physically to form a strong moisture holding mat on the ground surface and allow rainfall to percolate into underlying soil. The mulch shall be heat processed to contain no germination or growth-inhibiting factors. It shall be dyed (non-toxic) an appropriate color to facilitate metering of material.

2.9 PRODUCT REVIEW

- A. Contractor shall provide the Engineer with a complete description of all products before ordering. The Engineer will review all products before they are ordered.

PART 3 – EXECUTION**3.1 PREPARATION**

- A. Areas to be seeded shall be made smooth and uniform and shall conform to the finished grade indicated on plans.
- B. Remove foreign materials, plants, roots, stones, and debris from surfaces to be seeded.
- C. Grassing areas, if not loose, shall be loosened to a minimum depth of 3 inches before fertilizer or seed is applied.
- D. Amendments to soils shall be incorporated into loosened 3-inch top soil layer as recommended by soils tests.
- E. Contractor shall provide Topsoil Analysis Tests performed by a State Agricultural Experiment Station, Soil and Water Conservation District, State University, or other qualified private testing laboratory, as acceptable to Landscape Architect/Project Engineer. Soils test shall identify existing pH and nutrient levels, as well as recommended adjustments based on the type of grass to be installed.

3.2 STAND OF GRASS

- A. Before acceptance of seeding is performed for the establishment of permanent vegetation, Contractor will be required to produce a satisfactory stand of perennial grass whose root system shall be developed sufficiently to survive dry periods and winter weather and be capable of re-establishment in spring.
- B. Before acceptance of seeding is performed for the establishment of temporary vegetation, Contractor will be required to produce a stand of grass sufficient to control erosion for a given area and length of time before the next phase of construction or establishment of permanent vegetation is to commence.

3.3 SEEDING DATES

- A. Seeding shall be performed during periods and at rates specified in the seeding schedule. Seeding work may, at discretion of Contractor, be performed throughout the year using schedule prescribed for given period. Seeding work shall not be conducted when the ground is frozen or excessively wet. Contractor will be required to produce a satisfactory stand of grass regardless of the period of year work is performed.

3.4 APPLYING LIME AND FERTILIZER

- A. Following advance preparation and placing selected material for shoulders and slopes, lime and fertilizer, if called for based on soil tests, shall be spread uniformly over the designated areas, and shall be thoroughly mixed with the soil to a depth of approximately 2 inches. Fertilizer and lime shall be applied at the rate recommended by required soils test. Unless otherwise provided, lime will not be applied for temporary seeding. In all cases where practicable, acceptable mechanical spreaders shall be used for spreading fertilizer. On steep slopes subject to slides and inaccessible to power equipment, the slopes shall be adequately scarified. Fertilizer may be applied on steep slopes by hydraulic methods as a mixture of fertilizer and seed. When fertilizer is applied with combination seed and fertilizer drills, no further incorporation will be necessary. The fertilizer and seed shall be applied together when Wood Cellulose Fiber Mulch is used. Any stones larger than 2-1/2 inches in any dimension, larger clods, roots, or other debris brought to the surface shall be removed.

3.5 SEEDING

- A. Seed shall be sown within 24 hours following application of fertilizer and lime and preparation of the seedbed as specified in Section 3.4. Seed shall be uniformly sown at rate specified by the use of acceptable mechanical seed drills. Rotary hand seeders, power sprayers or other satisfactory equipment may be used on steep slopes or on other areas inaccessible to seed drills.
- B. Seeds shall be covered and lightly compacted by means of cultipacker or light roller if the drill does not perform this operation. On slopes inaccessible to compaction equipment, the seed shall be covered by dragging spiked chains, by light harrowing or by other satisfactory methods.
- C. Apply water with fine spray immediately after each area has been sown.

- D. Do not sow seed when ground is too dry, during windy periods or immediately following a rain.
- E. If permitted by the special provisions, wood cellulose fiber mulch or excelsior fiber mulch may be used.

3.6 SEED PROTECTION (STRAW MULCH)

- A. All seeded areas seeded with permanent grasses shall be uniformly mulched in a continuous blanket immediately following seeding and compacting operations, using at least 2 tons of straw per acre.

3.7 SEED PROTECTION (EXCELSIOR MULCH)

- A. Seed shall be sown as specified in Section 3.5. Within 24 hours after covering of seed, excelsior mulch shall be uniformly applied at the rate of 2 tons per acre. The mulch may be applied hydraulically or by other acceptable methods. Should the mulch be placed in a dry condition, it shall be thoroughly wetted immediately after placing. Engineer may require light rolling of the mulch to form a tight mat.

3.8 SEED PROTECTION (WOOD CELLULOSE FIBER MULCH)

- A. After the lime has been applied and ground prepared as specified in Section 3.4, wood cellulose fiber mulch shall be applied at a rate of 1,500 pounds per acre in a mixture of seed and fertilizer. Hydraulic equipment shall be used for application of fertilizer, seed, and slurry of the prepared wood pulp. This equipment shall have a built-in agitation system with an operating capacity sufficient to agitate, suspend, and homogeneously mix a slurry of the specified amount of fiber, fertilizer, seed, and water. The slurry distribution lines shall be large enough to prevent stoppage. The discharge line shall be equipped with a set of hydraulic spray nozzles which will provide an even distribution of slurry on various areas to be seeded. The slurry tank shall have a minimum capacity of 1,000 gallons.

Seed, fertilizer, wood pulp mulch, and water shall all be combined into the slurry tank for distribution of all ingredients in one operation by hydraulic seeding method specified herein. Materials shall be combined in a manner recommended by the manufacturer. The slurry mixture shall be regulated so amounts and rates of application shall result in a uniform application of all materials at rates not less than amount specified. Using the color of wood pulp as a guide, equipment operator shall spray prepared seedbed with a uniform visible coat. The slurry shall be applied in a sweeping motion, in an arched stream to fall like rain, allowing wood fibers to build upon each other until an even coat is achieved.

3.9 SPRIGGING

- A. Omitted

3.10 SODDING

- A. Omitted

PART 4 – MAINTENANCE, WARRANTY AND ACCEPTANCE

4.1 MAINTENANCE

- A. Maintain grassed surfaces until final acceptance.
- B. Maintenance shall consist of providing protection against traffic, watering to ensure uniform seed germination and to keep surface of soil damp, and repairing any areas damaged as a result of construction operations or erosion. Maintenance shall also include, but is not limited to, watering, weeding, cultivating, removal of dead material, lawn mowing, fertilizing, and other necessary operations.
- C. The Contractor shall maintain all proposed plantings until the date of substantial completion issued by the Owner.

4.2 WARRANTY

- A. All grassed areas shall be guaranteed by Contractor to be alive and healthy for a one (1) year period from date of substantial completion issued by the Owner. A final walk through with the Owner shall be conducted at end of warranty period to determine if any areas require replanting.
- B. Any grassed area which is dead or not showing satisfactory growth shall be replaced at Contractor's expense at the end of warranty period. All replacement shall be of original quality. Replacement required because of vandalism, excessive use, or other causes beyond the control of Contractor are not part of this contract.

4.3 ACCEPTANCE

- A. Before acceptance of seeding performed for the establishment of permanent vegetation, Contractor will be required to produce a satisfactory stand of perennial grass whose root system shall be developed sufficiently to survive dry periods and winter weather and be capable of reestablishment in spring.
- B. A minimum coverage of 80% density over 100% of the disturbed area is required for seeded areas before project acceptance.

END OF SECTION